

Lake Walk- Bathroom Building

The Lake Walk Bathroom Building is located near Canal Park. The toilet rooms are currently accessible.

Lake Walk- Bathroom Building

Accessibility Review

Location JQP # / Item #	Solution / Comments	Qty	Unit Cost	Total Cost	Priority	Estimated Compl. Date	Person Responsible	Actual Compl. Date	Actual Cost
Men's Toilet Room									
22H1 16680	Provide staple style pulls on both sides of the accessible stall door near the latch. ANSI 604.8.3 <i>Add a pull to the 'outside' of the 5' stall and to the 'inside' of the ambulatory stall.</i>	2	\$50	\$100	3				
22L (MN) 16679	Reposition the toilet paper dispenser so it is located below the horizontal grab bar. Operable parts should be located within an area 12" - 40" from the rear wall, and 18" minimum above the floor and 1 1/2" minimum below the horizontal grab bar. MN 1341 604.7 <i>In the 5' wide and ambulatory accessible stall. Photos 2 and 3.</i>	2	\$50	\$100	3				
				<i>Location Subtotal:</i>					\$200
Women's Toilet Room									
22H1 16677	Provide staple style pulls on both sides of the accessible stall door near the latch. ANSI 604.8.3 <i>Add a pull to the 'outside' of the 5' stall and to the 'inside' of the ambulatory stall.</i>	2	\$50	\$100	3				
22L (MN) 16676	Reposition the toilet paper dispenser so it is located below the horizontal grab bar. Operable parts should be located within an area 12" - 40" from the rear wall, and 18" minimum above the floor and 1 1/2" minimum below the horizontal grab bar. MN 1341 604.7 <i>In the 5' wide and ambulatory accessible stall. Photos 2 and 3.</i>	2	\$50	\$100	3				
				<i>Location Subtotal:</i>					\$200
				Priority # 3 Total					\$400

Location JQP # / Item #	Solution / Comments	Qty	Unit Cost	Total Cost	Priority	Estimated Compl. Date	Person Responsible	Actual Compl. Date	Actual Cost
Men's Toilet Room									
22P5 16681	Lower lavatory so top edge is no higher than 34" AFF. ICC / ANSI 606.3 <i>Currently at 34 1/2".</i>	1	\$500	\$500	4				
Women's Toilet Room									
22P5 16678	Lower lavatory so top edge is no higher than 34" AFF. ICC / ANSI 606.3 <i>Currently at 34 1/2".</i>	1	\$500	\$500	4				
				Priority # 4 Total		\$1,000			
<i>Transition Plan - (location/priority)</i>									



Photo 1: An accessible route is provided to the toilet rooms and signs with raised and braille characters are posted.



Photo 2: The toilet rooms currently provide features of accessibility. Relocate the toilet paper dispenser to below the side grab bar.



Photo 3: The toilet rooms currently provide features of accessibility. Relocate the toilet paper dispenser to below the side grab bar in the ambulatory accessible stall.