



City of Duluth

DEPARTMENT OF PUBLIC WORKS/UTILITIES
Engineering Division
211 City Hall • Duluth MN 55802
(218) 730-5200 Fax: (218) 730-5907

Date: October 27, 2011

City of Duluth Bid #11-0533

Job Description: CDBG-ARRA sidewalk Replacement and Pedestrian Ramps on Superior Street from 19th Avenue to 20th Avenue West

City Project No. 0936TR

Addendum #1

General note to the contractor:

The bid tabulation sheets Exhibit A and Add Alternate are modified by replacing the 4 Salvage items with Remove and Replace. This is for the Bench items, Trash Receptacle items, Monument item and Parking Meter items. This will match the note descriptions on the plan sheets. Specifications are added to clarify the 4 Remove and Replace items.

Bid Form:

The attached Exhibit A and the attached Add Alternate are modified and replace the Exhibit A and Add Alternate tabulations in the bound Project Proposal. Complete the attached Exhibit A and the attached Add Alternate, and include them with your bid.

Specifications:

ADD to the special provisions:

(2540) REMOVE AND REPLACE BENCH

Remove and replace bench. Note on plans state existing bench is bolted to sidewalk. Protect bench between removal and replacement. The replaced bench shall be bolted to the new sidewalk. Removal and replacement of benches will be measured and paid under Item 2540.602 Remove and Replace Bench at the contract price per each, which shall be compensation in full.

(2540) REMOVE AND REPLACE TRASH RECEPTACLE

Remove and replace trash receptacle. Removal and replacement of trash receptacle will be measured and paid under Item 2540.602 Remove and Replace Trash Receptacle at the contract price per each, which shall be compensation in full.

(2540) REMOVE AND REPLACE MONUMENT

Remove and replace monument. Removal and replacement of monument will be measured and paid under Item 2540.602 Remove and Replace Monument at the contract price per each, which shall be compensation in full.

(2540) REMOVE AND REPLACE PARKING METER

Remove and replace parking meters according to the City Detail T-1, Typical Parking Meter Installation and according to the City of Duluth Standard Construction Specifications 2011 Edition, 2540 Parking Meter Post/Bracket Installation. Removal and replacement of parking meters will be measured and paid under Item 2540.602 Remove and Replace Parking Meter at the contract price per each, which shall be compensation in full.

(2564) REMOVE AND REINSTALL SIGN

Remove and reinstall signs. Provide a temporary stop sign when the permanent sign is down. Provide post installation according to the City of Duluth Standard Construction Specifications 2011 Edition, 2564 Traffic Signs and Sign Post Installation, Section C, Post Installation, and also according to the City Detail T-2, Sign Installation. Removal and replacement of signs will be measured and paid under Item 2564.602 Remove and Reinstall Sign at the contract price per each, which shall be compensation in full.

All other items remain the same.

Be sure to acknowledge this addendum on page 2 of your bid form. Return the entire bound Project Proposal and all addenda as your bid.

Sincerely,



Greg Stoewer
Project Engineer

Exhibit A - Base Bid

CITY JOB NO. 0936TR - 2011 CDBG ARRA Sidewalk Replacement Project						
SPEC. NO.	DESCRIPTION	UNIT	ESTIMATED QUANTITY	UNIT PRICE	TOTAL PRICE	
1	2021.501 MOBILIZATION	LUMP SUM	1			
2	2104.501 REMOVE CURB & GUTTER	L.F.	32			
3	2104.511 SAWING CONCRETE PAVEMENT	L.F.	238			
4	2104.503 REMOVE BRICK AND CONCRETE SIDEWALK	SQ. FT.	5710			
5	2540.602 REMOVE AND REPLACE BENCH	EACH	1			
6	2540.602 REMOVE AND REPLACE TRASH RECEPTACLE	EACH	1			
7	2540.602 REMOVE AND REPLACE MONUMENT	EACH	0			
8	2540.602 REMOVE AND REPLACE PARKING METERS	EACH	4			
9	2104.603 REMOVE KIOSK	EACH	0			
10	2211.503 AGGREGATE BASE (CV), CLASS 5 (P)	CU. YD.	49			
11	2503.603 TRENCH DRAIN	L.F.	88			
12	2504.602 ADJUST VALVE BOX	EACH	7			
13	2521.501 4" CONCRETE WALK	SQ. FT.	5066			
14	2521.501 6" CONCRETE WALK	SQ. FT.	644			
15	2531.501 CONCRETE CURB & GUTTER DESIGN B624	L.F.	32			
16	2531.618 TRUNCATED DOME	SQ. FT.	40			
17	2563.601 TRAFFIC CONTROL	LUMP SUM	1			
18	2564.602 REMOVE AND REINSTALL SIGN	EACH	3			

GRAND TOTAL \$ _____

Bid Number 11-0533, Addendum 1

ADD - ALTERNATE

CITY JOB NO. 0936TR - 2011 CDBG ARRA Sidewalk Replacement Project

SPEC. NO.	DESCRIPTION	UNIT	ESTIMATED QUANTITY	UNIT PRICE	TOTAL PRICE
1	2021.501 MOBILIZATION	LUMP SUM	1		
2	2104.501 REMOVE CURB & GUTTER	L.F.	44		
3	2104.511 SAWING CONCRETE PAVEMENT	L.F.	122		
4	2104.503 REMOVE BRICK AND CONCRETE SIDEWALK	SQ. FT.	6365		
5	2540.602 REMOVE AND REPLACE BENCH	EACH	2		
6	2540.602 REMOVE AND REPLACE TRASH RECEPTACLE	EACH	1		
7	2540.602 REMOVE AND REPLACE MONUMENT	EACH	1		
8	2540.602 REMOVE AND REPLACE PARKING METERS	EACH	4		
9	2104.603 REMOVE KIOSK	EACH	1		
10	2211.503 AGGREGATE BASE (CV), CLASS 5 (P)	CU. YD.	55		
11	2503.603 TRENCH DRAIN	L.F.	60		
12	2504.602 ADJUST VALVE BOX	EACH	4		
13	2521.501 4" CONCRETE WALK	SQ. FT.	5735		
14	2521.501 6" CONCRETE WALK	SQ. FT.	630		
15	2531.501 CONCRETE CURB & GUTTER DESIGN B624	L.F.	44		
16	2531.618 TRUNCATED DOME	SQ. FT.	40		
17	2563.601 TRAFFIC CONTROL	LUMP SUM	1		
18	2564.602 REMOVE AND REINSTALL SIGN	EACH	3		

GRAND TOTAL \$ _____

Initial _____