

SPIRIT MOUNTAIN CITY OF DULUTH, MINNESOTA


CONSTRUCTION PLANS FOR INFRASTRUCTURE IMPROVEMENTS

CONTRACT "A" REVERSABLE RUNOFF COLLECTION AND WATER SUPPLY LINE

CLIENT PROJECT NO. 129137

LEGEND

	STREET CENTERLINE
	SURVEY BASELINE
	COUNTY SECTION
	QUARTER
	SIXTEENTH
	CORPORATE LIMITS
EXISTING	
	RIGHT OF WAY
	PERMANENT EASEMENT
	PROPERTY LINE
	R.R. RIGHT OF WAY
	SANITARY SEWER AND MANHOLE
	FORCE MAIN
	SANITARY SEWER SERVICE & CLEANOUT
	WATER MAIN, HYDRANT AND VALVE
	WATER SERVICE AND CURB STOP BOX
	WATER VALVE MANHOLE
	STORM SEWER, APRON, MANHOLE AND CATCH BASIN
	CULVERT
	BULKHEAD
	BURIED FIBER OPTIC CABLE
	BURIED FIBER OPTIC DUCT OR CONDUIT
	BURIED PHONE CABLE AND PEDESTAL
	BURIED PHONE DUCT OR CONDUIT AND MANHOLE
	BURIED TV CABLE AND PEDESTAL
	BURIED ELECTRIC CABLE
	BURIED ELECTRIC DUCT OR CONDUIT AND MANHOLE
	OVERHEAD ELECTRIC, POLE AND DOWN GUY ANCHOR
	LIGHT POLE
	TRAFFIC SIGNAL STANDARD
	GAS MAIN
	GAS SIGN, VALVE AND VENT
	PETROLEUM PIPELINE
	SOIL BORING
	TRAVERSE POINT
	CONCRETE CURB AND GUTTER
	EXISTING PAVEMENT OR SIDEWALK
	SIGN (HWY, PARK, STOP, ETC.)
	STREET NAME SIGN
	DITCH
	RAILROAD TRACKS
	FENCE (UNIDENTIFIED)
	BARBED WIRE FENCE
	CHAIN LINK FENCE
	ELECTRIC WIRE FENCE
	WOOD FENCE
	WOVEN WIRE FENCE
	PLATE BEAM GUARDRAIL
	CABLE GUARDRAIL
	DECIDUOUS AND CONIFEROUS TREE
	BUSH-SHRUB
	WOODED AREA
	WETLAND
	BUILDING
PROPOSED	
	NEW RIGHT OF WAY
	PERMANENT EASEMENT
	TEMPORARY EASEMENT
	SANITARY SEWER AND MANHOLE
	FORCE MAIN
	SANITARY SEWER SERVICE & CLEANOUT
	WATER MAIN, HYDRANT AND VALVE
	WATER SERVICE AND CURB STOP BOX
	WATER VALVE MANHOLE
	STORM SEWER, MANHOLE AND CATCH BASIN
	CULVERT
	BULKHEAD
	DRAIN PIPE
	DITCH
	CONCRETE CURB AND GUTTER
	SILT FENCE
	FLOATATION SILT CURTAIN
	BIOROLL
	LIGHT POLE
	TRAFFIC SIGNAL, STANDARD
	SIGN (HWY, PARK, STOP, ETC.)
	STREET LIGHT FEED POINT
	STREET LIGHTING CABLE



INDEX

SHEET NO.	DESCRIPTION
C1	TITLE SHEET
C2	GENERAL LAYOUT
C3	SCREEN INLET DETAILS / STRUCTURE SCHEDULE
C4	ROCK EX, TRENCH DAM, DETAILS
C5	GRIT CHAMBER DETAILS
C6	RIVER PUMP STATION DETAILS
C7-C15	WATER SUPPLY LINE PLAN & PROFILE SHEETS
C16-C19	EROSION CONTROL
C20-C23	SWPP PLAN / DETAILS
C24-C25	KNOWLTON CREEK REGRADING
B1-B2	BRIDGE REPLACEMENT SHEETS
S1-S2	STRUCTURAL BOX DETAILS
S3	STRUCTURAL GENERAL NOTES

THIS PLAN CONTAINS 30 SHEETS.

PROJECT LOCATION



DULUTH, MINNESOTA



NOTE:
THE SUBSURFACE UTILITY QUALITY INFORMATION IN THIS PLAN IS LEVEL D. THIS UTILITY QUALITY LEVEL WAS DETERMINED ACCORDING TO THE GUIDELINES OF CI/ASCE 38-02 ENTITLED "STANDARD GUIDELINES FOR THE COLLECTION AND DEPICTION OF EXISTING SUBSURFACE UTILITY DATA."

THE CONTRACTOR SHALL CALL THE GOPHER STATE ONE CALL SYSTEM AT 811 BEFORE COMMENCING EXCAVATION.


I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

Signature: *Jeffery R. Ledin* JEFFERY R. LEDIN P.E.

Date: 10/17/2014 Lic. No. 25222

FILE NO. FOSJJ129137

C1 / 30



P:\J\J\J\CON\106141\50-Cod\dwg\Plnshts\JOCN106141_GEN.dwg 9/29/2014 1:35 PM rhoehn

DRAWN BY: RVH
 DESIGNER: GJK/RVH
 CHECKED BY: JRL
 DESIGN TEAM

NO.	BY	DATE	REVISIONS



I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.
 Date: 10/17/2014 Lic. No. 25222
 JEFFERY R. LEDIN, P.E.







PHONE: 218.855.1700
 416 S 6TH ST, STE 200
 BRAINERD, MN 56401-3540
 www.sehinc.com

**SPIRIT MOUNTAIN
 IMPROVEMENTS
 DULUTH, MINNESOTA**



GENERAL LAYOUT

FILE NO.
 FOSJU129137

C2
30











INTAKE SCREEN ASSEMBLY
 11'-6"
 2'-6"
 36"
TOP VIEW
INTAKE SCREEN DETAIL
1 REQUIRED
NOT TO SCALE



TRANSFER PIPE STRUCTURE SCHEDULE							
LINE	STRUCTURE NO.	TC	INV IN	INV OUT	ADDT'L INV'S	MH DIA	COVER TYPE
1	110			677.50			APRON
2	112			677.50			APRON
3	114	700.70	688.00	688.00		48"	1733 SOLID LID
4	116	715.34	706.00	706.00		60"	1733 SOLID LID
RUNOFF COLLECTION STRUCTURE SCHEDULE							
5	298		758.53				APRON
6	299			749.63			APRON
7	300	764.45	751.72	750.16		72"	1733 SOLID LID
8	GRIT CHAMBER	765.05	751.77	751.77	756.00	35'X14'X10'	1733 SOLID LID
9	301	768.81	752.37	752.37	758.88	84"	1733 SOLID LID
10	302		761.00				APRON
11	304A	764.12	753.99	753.49		84"	1733 SOLID LID
12	304	762.43	754.72	754.72		72"	1733 SOLID LID
13	305	773.51	766.50	760.00	760.00	84"	1733 SOLID LID
14	306	775.84		761.84		72"	1733 SOLID LID
15	308		776.24				APRON
16	309			782.77			APRON
17	310	785.45	783.87	783.87	780.87	48"	1733 SOLID LID
18	311		786.02				APRON

CASTINGS REFERENCED TO NEENAH TYPE STAMPED DRAIN





P:\F\J\JOCON\106141\50-Cod\dwg\Pinshis\JOCON106141.DT.dwg 10/15/2014 10:56 AM rfoehn

DRAWN BY: RVH
DESIGNER: GKG/RVH
CHECKED BY: JRL
DESIGN TEAM

NO.	BY	DATE	REVISIONS

FOSTER, JACOBS, & JOHNSON, INC.
PROFESSIONAL ENGINEERS


I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.
JEFFERY R. LEDIN, P.E.
Date: 10/17/2014 Lic. No. 25222

SEH
PHONE: 218.855.1700
416 S 6TH ST, STE 200
BRainerd, MN 56401-3540
www.sehinc.com


SPRIT MOUNTAIN IMPROVEMENTS
DULUTH, MINNESOTA

ROCK EXCAVATION, TRENCH DAM, DETAILS

FILE NO. FOSJ129137
C4
30



5' INLET SECTION
 4- 6' X 14' X 10' SECTIONS
 5' OUTLET SECTION



PLAN VIEW

P:\F\U\JOCON\06141\50-Cod\dwg\Pinshis\JOCON106141.DT.dwg 10/15/2014 10:56 AM rhoehn

DRAWN BY:	RVH			
DESIGNER:	GGK/RVH			
CHECKED BY:	JRL			
DESIGN TEAM	NO.	BY	DATE	REVISIONS



I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

Jeffery R. Ledin
 JEFFERY R. LEDIN, P.E.
 Date: 10/17/2014 Lic. No. 25222






PHONE: 218.855.1700
 416 S 6TH ST, STE 200
 BRAINERD, MN 56401-3540
 www.sehinc.com

SPIRIT MOUNTAIN IMPROVEMENTS
 DULUTH, MINNESOTA

GRIT CHAMBER DETAILS

FILE NO. C5
 FOSJJ129137 30



P:\F\J\JOCON\106141\50-Cod\dwg\Pinshits\river_pump_detail.dwg 10/17/2014 3:17 PM rhoehn

DRAWN BY: RVH
 DESIGNER: GKG/RVH
 CHECKED BY: JRL

DESIGN TEAM	NO.	BY	DATE	REVISIONS



I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.



Jeffery R. Ledin
 JEFFERY R. LEDIN, P.E.
 Date: 10/17/2014 Lic. No. 25222



PHONE: 218.855.1700
 416 S 6TH ST, STE 200
 BRAINERD, MN 56401-3540
 www.sehinc.com


SPIRIT MOUNTAIN IMPROVEMENTS
DULUTH, MINNESOTA

FILE NO. FOSJ129137
C6
30



NOTE: SEE SHEET C21 FOR TEMPORARY WETLAND IMPACTS AND PROCEDURES

RUNOFF COLLECTION SYSTEM



P:\F\J\JOCON\06141\50-Cod\dwg\Pinshis\Storm Outlet - (9) - (02).dwg 10/7/2014 3:34 PM rnoehn

DRAWN BY: RVH
 DESIGNER: GJK/RVH
 CHECKED BY: JRL

NO.	BY	DATE	REVISIONS



I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

Jeffery R. Ledin
 Date: 10/17/2014
 Lic. No.: 25222





PHONE: 218.855.1700
 416 S 6TH ST, STE 200
 BRAINERD, MN 56401-3540
 www.sehinc.com

SPIRIT MOUNTAIN IMPROVEMENTS
 DULUTH, MINNESOTA



PLAN AND PROFILE
 WATER IN/OUTFLOW

FILE NO. FOSJJ129137

C7
30



RUNOFF COLLECTION SYSTEM



DRAWN BY: RVH
 DESIGNER: GJK/RVH
 CHECKED BY: JRL

NO.	BY	DATE	REVISIONS





I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.
 JEFFERY R. LEDIN, P.E.
 Date: 10/17/2014 Lic. No. 25222




PHONE: 218.855.1700
 416 S 6TH ST, STE 200
 BRAINERD, MN 56401-3540
 www.sehinc.com

FILE NO. C8
 FOSJ129137
 PLAN AND PROFILE
 WATER IN/OUTFLOW
 30

P:\FJV\JOCON\106141\50-Cod\dwg\Pinshis\Storm_Outlet - (9) - (02).dwg 10/17/2014 3:34 PM rhoehh



TRANSFER PIPE



P:\F\J\JOCON\06141\50-Cad\dwg\Pinshis\Storm Outlet - (01).dwg 10/17/2014 3:19 PM rnoehn

DRAWN BY: RVH
 DESIGNER: GKG/RVH
 CHECKED BY: JRL

NO.	BY	DATE	REVISIONS



I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

Jeffery R. Ledin
 JEFFERY R. LEDIN, P.E.
 Date: 10/17/2014 Lic. No. 25222




PHONE: 218.855.1700
 416 S 6TH ST, STE 200
 BRAINERD, MN 56401-3540
 www.sehinc.com

SPIRIT MOUNTAIN IMPROVEMENTS
 DULUTH, MINNESOTA

PLAN AND PROFILE
 WATER IN/OUTFLOW


FILE NO. FOSJJ129137

C9
30



NOTE: SEE SHEET C21 FOR TEMPORARY WETLAND IMPACTS AND PROCEDURES

TRANSFER PIPE



P:\F\J\JOCON\106141\50-Cad\dwg\Pinshis\Storm Outlet - (01).dwg 10/17/2014 3:19 PM rhoehn

DRAWN BY: RVH
 DESIGNER: GGK/RVH
 CHECKED BY: JRL

NO.	BY	DATE	REVISIONS



I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

Jeffery R. Ledin
 JEFFERY R. LEDIN, P.E.
 Date: 10/17/2014 Lic. No. 25222





PHONE: 218.855.1700
 416 S 6TH ST, STE 200
 BRAINERD, MN 56401-3540
 www.sehinc.com

SPIRIT MOUNTAIN IMPROVEMENTS
 DULUTH, MINNESOTA


PLAN AND PROFILE
 WATER IN/OUTFLOW

FILE NO. FOSJJ129137

C10
30



TRANSFER PIPE / SUPPLY LINE



P:\F\J\JOCON\106141\50-Cad\dwg\Pinshis\Storm Outlet - (01).dwg 10/17/2014 3:19 PM rnoehn

DRAWN BY: RVH
 DESIGNER: GGK/RVH
 CHECKED BY: JRL

NO.	BY	DATE	REVISIONS



I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

Jeffery R. Ledin
 JEFFERY R. LEDIN, P.E.
 Date: 10/17/2014 Lic. No. 25222





PHONE: 218.855.1700
 416 S 6TH ST, STE 200
 BRAINERD, MN 56401-3540
 www.sehinc.com

**PLAN AND PROFILE
 WATER IN/OUTFLOW**


FILE NO.
 FOSJJ129137

**C11
 30**



SUPPLY LINE

NOTE: SEE SHEET C21 FOR TEMPORARY WETLAND IMPACTS AND PROCEDURES



P:\F\J\JOCON\06141\50-Cad\dwg\Pinshis\Storm Outlet - (01).dwg 10/17/2014 3:19 PM rnoehn

DRAWN BY: RVH
 DESIGNER: GKG/RVH
 CHECKED BY: JRL

NO.	BY	DATE	REVISIONS





I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.
 JEFFERY R. LEDIN, P.E.
 Date: 10/17/2014 Lic. No. 25222



PHONE: 218.855.1700
 416 S 6TH ST, STE 200
 BRAINERD, MN 56401-3540
 www.sehinc.com


**PLAN AND PROFILE
 WATER IN/OUTFLOW**

FILE NO. FOSJJ129137
**C12
 30**



NOTE: SEE SHEET C21 FOR TEMPORARY WETLAND IMPACTS AND PROCEDURES

SUPPLY LINE



P:\F\J\JOCON\106141\50-Cad\dwg\Pinshis\Storm Outlet - (01).dwg 10/17/2014 3:19 PM rthoehn

DRAWN BY: RVH
 DESIGNER: GGK/RVH
 CHECKED BY: JRL

NO.	BY	DATE	REVISIONS





I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.
 Date: 10/17/2014
 Lic. No. 25222



PHONE: 218.855.1700
 416 S 6TH ST, STE 200
 BRAINERD, MN 56401-3540
 www.sehinc.com


PLAN AND PROFILE
 WATER IN/OUTFLOW

FILE NO. FOSJJ129137
 C13
 30



SUPPLY LINE / RIVER INTAKE LINE

NOTE: SEE SHEET C21 FOR TEMPORARY WETLAND IMPACTS AND PROCEDURES



P:\F\J\JOCON\06141\50-Cad\dwg\Pinshis\Storm Outlet - (01).dwg 10/17/2014 3:19 PM rhoehn

DRAWN BY: RVH
 DESIGNER: GGK/RVH
 CHECKED BY: JRL

NO.	BY	DATE	REVISIONS




I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.
 JEFFERY R. LEDIN, P.E.
 Date: 10/17/2014 Lic. No. 25222




PHONE: 218.855.1700
 416 S 6TH ST, STE 200
 BRAINERD, MN 56401-3540
 www.sehinc.com

PLAN AND PROFILE WATER IN/OUTFLOW

FILE NO. **C14**
 FOSJJ129137
30



RIVER INTAKE LINE



DRAWN BY: RVH
 DESIGNER: GGK/RVH
 CHECKED BY: JRL

NO.	BY	DATE	REVISIONS



I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

JEFFERY R. LEDIN, P.E.
 Lic. No. 25222

Date: 10/17/2014



PHONE: 218.855.1700
 416 S 6TH ST, STE 200
 BRAINERD, MN 56401-3540
 www.sehinc.com

**PLAN AND PROFILE
 WATER IN/OUTFLOW**

FILE NO.
 FOSJJ129137

**C15
 30**


P:\F\J\JOCON\106141\50-Cad\dwg\Pinshis\Storm Outlet - (01).dwg 10/17/2014 3:19 PM rthohn

LEGEND:

-  INLET PROTECTION
-  SILT FENCE MACHINE SLICED
-  SILT CURTAIN
-  EROSION CONTROL BLANKET

NOTE: CONTRACTOR TO PLACE CONSTRUCTION ENTRANCES IN FIELD ONCE ENTRY POINTS ARE ESTABLISHED.

SEE CREEK RESTORATION PLAN



WETLAND PERIMETER
GN1 SHEET C21

WETLAND PERIMETER
GN1 SHEET C21



P:\J\J\JOCON\106141\50-Cad\C3D\C122747ec.dwg 10/7/2014 2:05 PM rhaehn

DRAWN BY: RVH				
DESIGNER: GJK/RVH				
CHECKED BY: JRL				
DESIGN TEAM	NO.	BY	DATE	REVISIONS



I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

Jeffery R. Ledin
JEFFERY R. LEDIN, P.E.
Date: 10/17/2014 Lic. No. 25222




PHONE: 218.855.1700
416 S 6TH ST, STE 200
BRainerd, MN 56401-3540
www.sehinc.com

**SPIRIT MOUNTAIN
IMPROVEMENTS
DULUTH, MINNESOTA**

**RUNOFF COLLECTION SYSTEM
EROSION CONTROL**

FILE NO.
FOSJU129137

C16
30



LEGEND:

-  INLET PROTECTION
-  SILT FENCE MACHINE SLICED
-  SILT CURTAIN
-  EROSION CONTROL BLANKET

NOTE: CONTRACTOR TO PLACE CONSTRUCTION ENTRANCES IN FIELD ONCE ENTRY POINTS ARE ESTABLISHED.

WETLAND PERIMETER
SILT FENCE



P:\F\J\JOCON\06141\50-Cad\C3D\C122747ec.dwg 10/7/2014 2:05 PM rnoehn

DRAWN BY: RVH				
DESIGNER: GGK/RVH				
CHECKED BY: JRL				
DESIGN TEAM	NO.	BY	DATE	REVISIONS



I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

Jeffery R. Ledin
JEFFERY R. LEDIN, P.E.
Date: 10/17/2014 Lic. No. 25222




PHONE: 218.855.1700
416 S 6TH ST, STE 200
BRainerd, MN 56401-3540
www.sehinc.com

**SPIRIT MOUNTAIN
IMPROVEMENTS
DULUTH, MINNESOTA**

**TRANSFER PIPE
EROSION CONTROL**


FILE NO. C17
FOSJJ129137 30



LEGEND:

-  INLET PROTECTION
-  SILT FENCE MACHINE SLICED
-  SILT CURTAIN
-  EROSION CONTROL BLANKET

NOTE: CONTRACTOR TO PLACE CONSTRUCTION ENTRANCES IN FIELD ONCE ENTRY POINTS ARE ESTABLISHED.



P:\F\J\JOCON\06141\50-Cod\Cad\C3D\C122747.ec.dwg 10/17/2014 2:05 PM rtoehr

DRAWN BY: RVH				
DESIGNER: GGK/RVH				
CHECKED BY: JRL				
DESIGN TEAM	NO.	BY	DATE	REVISIONS



I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

Jeffery R. Ledin
 JEFFERY R. LEDIN, P.E.
 Date: 10/17/2014 Lic. No. 25222



SPIRIT MOUNTAIN IMPROVEMENTS
DULUTH, MINNESOTA

SUPPLY LINE EROSION CONTROL


FILE NO. **C18**
 FOSJJ129137
30

WETLAND PERIMETER
GN1 SHEET C21
SILT FENCE POST CONSTRUCTION

LEGEND:

-  INLET PROTECTION
-  SILT FENCE MACHINE SLICED
-  SILT CURTAIN
-  EROSION CONTROL BLANKET

NOTE: CONTRACTOR TO PLACE CONSTRUCTION
ENTRANCES IN FIELD ONCE ENTRY POINTS ARE ESTABLISHED.



P:\F\J\JOCON\06141\50-Cad\C3D\C122747ec.dwg 10/7/2014 2:05 PM rhdh

DRAWN BY: RVH				
DESIGNER: GJK/RVH				
CHECKED BY: JRL				
DESIGN TEAM	NO.	BY	DATE	REVISIONS



I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

Jeffery R. Ledin
JEFFERY R. LEDIN, P.E.
Date: 10/17/2014 Lic. No. 25222



PHONE: 218.855.1700
416 S 6TH ST, STE 200
BRainerd, MN 56401-3540
www.sehinc.com

**SPIRIT MOUNTAIN
IMPROVEMENTS
DULUTH, MINNESOTA**

**RIVER INTAKE
EROSION CONTROL**

FILE NO. **C19**
FOSJJ129137

30

SWPPP SUMMARY / OVERVIEW:

THIS STORM WATER POLLUTION PREVENTION PLAN (SWPPP) HAS BEEN DEVELOPED TO ADDRESS THE REQUIREMENTS OF NPDES PERMIT MN R100001, PART III, SUBPART A. THIS SWPPP INCLUDES A COMBINATION OF NARRATIVE, ATTACHED FIGURE(S) AND PLAN SHEETS THAT DESCRIBE THE TEMPORARY AND PERMANENT STORM WATER MANAGEMENT PLAN FOR THE PROJECT.

CONTACTS:

OWNER: CITY OF DULUTH
CONTACT: X
PHONE: X
EMAIL: X

ENGINEER: SHORT ELLIOTT HENDRICKSON INC.
CONTACT: GREG KIMMAN, PE
PHONE: 218-855-1717
EMAIL: GKIMMAN@SEHINC.COM

THE GENERAL CONTRACTOR SHALL ATTACH THEIR REQUIRED CONTACT INFORMATION TO THE SWPPP AFTER THE CONTRACT FOR THE PROJECT IS AWARDED.

CONTRACTOR: TBD
CONTACT: TBD
PHONE: TBD
EMAIL: TBD

GENERAL PROJECT INFORMATION:

PROJECT NAME: SPIRIT MOUNTAIN REVERSABLE RUNOFF COLLECTION AND WATER SUPPLY LINE
PROJECT LOCATION: DULUTH, MN
CONSTRUCTION START DATE: AUGUST 2014
CONSTRUCTION END DATE: AUGUST 2015
THIS PROJECT WILL CONSIST OF: CLEARING, GRUBBING, GRADING, STORM SEWER, TRAIL CONSTRUCTION, & TURF ESTABLISHMENT

AMENDMENTS TO THE SWPPP:

THE SWPPP WILL BE AMENDED AS NEEDED AND/OR AS REQUIRED BY PROVISIONS OF THE PERMIT. AMENDMENTS WILL BE APPROVED BY BOTH THE OWNER AND CONTRACTOR AND WILL BE ATTACHED TO THE SWPPP AS AN ADDITIONAL SHEET. THE SWPPP AMENDMENTS SHALL BE INITIATED, FACILITATED, AND PROCESSED BY THE CONTRACTOR. THE SWPPP AND AMENDMENTS SHALL BE KEPT ON SITE BY THE CONTRACTOR WHENEVER CONSTRUCTION ACTIVITY IS IN PROGRESS.

GENERAL SWPPP RESPONSIBILITIES

GENERAL SWPPP RESPONSIBILITIES:

THE CONTRACTOR SHALL PROVIDE A KNOWLEDGEABLE AND EXPERIENCED PERSON(S) TO OVER SEE THE IMPLEMENTATION OF THE SWPPP, AND THE INSTALLATION, INSPECTION AND MAINTENANCE OF THE EROSION AND SEDIMENT CONTROL BMP'S BEFORE AND DURING CONSTRUCTION.

BOTH THE OWNER AND CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROPER TERMINATION AND/OR TRANSFER OF THE PERMIT.

THE OWNER WILL BE RESPONSIBLE OR WILL OTHERWISE IDENTIFY WHO WILL BE RESPONSIBLE FOR THE LONG TERM OPERATION AND MAINTENANCE OF THE PERMANENT STORM WATER MANAGEMENT SYSTEM(S).

TRAINING REQUIREMENTS:

PREPARER/DESIGNER OF SWPPP: GREG KIMMAN
EMPLOYER: SEH INC.
TRAINING OBTAINED: UNIVERSITY OF MN, EROSION AND STORMWATER MANAGEMENT CERTIFICATION PROGRAM DESIGN OF SWPPP-JUNE 2013

THE CONTRACTOR (OPERATOR) SHALL PROVIDE AT LEAST ONE TRAINED PERSON TO OVERSEE THE IMPLEMENTATION OF THE SWPPP AND TO INSTALL, INSPECT, MAINTAIN AND REPAIR BMP'S.

TRAINING MUST BE IN CONFORMANCE WITH THE NPDES CONSTRUCTION PERMIT REQUIREMENTS. TRAINING DOCUMENTATION MUST KEPT ON-SITE WITH THE SWPPP AND THE TRAINED PERSON MUST BE AVAILABLE ON-SITE WITHIN 72 HOURS.

IMPLEMENTATION SEQUENCE:

THE CONTRACTOR SHALL COMPLY WITH THE FOLLOWING SEQUENCE. THE ENGINEER MAY APPROVE ADJUSTMENTS TO THE SEQUENCE AS NEEDED.

1. INSTALL ROCK CONSTRUCTION ENTRANCE(S)
2. INSTALL PERIMETER CONTROL AND STABILIZE DOWN GRADIENT BOUNDARIES
3. CLEAR AND GRUB STORM WATER POND AREAS
4. CONSTRUCT STORM WATER PONDS
5. CLEAR AND GRUB REMAINING SITE
6. COMPLETE GRADING
7. INSTALL STORM SEWER, INLET PROTECTION, CURB & GUTTER, AND PAVING.
8. AFTER CONSTRUCTION IS COMPLETED AND THE SITE IS STABILIZED REMOVE ACCUMULATED SEDIMENT FROM STORM WATER POND, REMOVE BMP'S, AND RE-SEED ANY AREAS DISTURBED BY THEIR REMOVAL.

INSPECTION AND MAINTENANCE:

ALL INSPECTIONS, MAINTENANCE, REPAIRS, REPLACEMENTS, AND BMP'S ARE TO BE CONSIDERED INCIDENTAL TO THE BMP BID ITEM.

THE CONTRACTOR IS RESPONSIBLE FOR COMPLETING REQUIRED INSPECTIONS, MAINTENANCE AND OBSERVATION OF WEATHER CONDITIONS AND RAINFALL AMOUNTS TO ENSURE COMPLIANCE WITH THE PERMIT REQUIREMENTS.

THE CONTRACTOR SHALL INSPECT THE CONSTRUCTION SITE ONCE EVERY SEVEN (7) DAYS DURING ACTIVE CONSTRUCTION AND WITHIN TWENTY-FOUR (24) HOURS AFTER A RAINFALL EVENT GREATER THAN HALF (0.5) AN INCH IN TWENTY-FOUR (24) HOURS.

THE CONTRACTOR SHALL KEEP A MAINTENANCE AND INSPECTIONS REPORT TO BE RECORDED AFTER EACH SITE VISIT AND/OR OBSERVATION. RECORDS SHALL INCLUDE THE FOLLOWING:

1. DATE AND TIME OF INSPECTION/MAINTENANCE.
2. NAME OF PERSON(S) CONDUCTING INSPECTION/MAINTENANCE.
3. FINDINGS AND RECOMMENDATIONS FOR CORRECTIVE ACTIONS, IF NECESSARY.
4. CORRECTIVE ACTIONS TAKEN.
5. DATE AND AMOUNT OF RAINFALL(S) GREATER THAN HALF (0.5) INCHES IN 24 HOURS.
6. DOCUMENTATION OF CHANGES MADE TO THE SWPPP.
7. A SITE MAP INDICATING ACTIVE AREAS AND LAND DISTURBING ACTIVITIES.

THE CONTRACTOR SHALL SUBMIT A COPY OF THE WRITTEN INSPECTIONS TO THE ENGINEER AND OWNER ON A MONTHLY BASIS. IF MONTHLY INSPECTION REPORTS ARE NOT , MONTHLY PAYMENTS MAY BE HELD.

THE CONTRACTOR MUST KEEP A COPY OF THE SWPPP, INSPECTION REPORTS, AND AMENDMENTS ONSITE. THE CONTRACTOR SHALL DESIGNATE A SPECIFIC LOCATION TO KEEP THE RECORDS WHENEVER CONSTRUCTION ACTIVITY IS IN PROGRESS.

ALL EROSION PREVENTION AND SEDIMENTATION CONTROL BMP'S MUST BE INSPECTED TO ENSURE INTEGRITY AND EFFECTIVENESS. ALL NONFUNCTIONAL BMP'S MUST BE REPAIRED, REPLACED, OR SUPPLEMENTED WITH FUNCTIONAL BMP'S. THE CONTRACTOR MUST INVESTIGATE AND COMPLY WITH THE FOLLOWING INSPECTION AND MAINTENANCE REQUIREMENTS:

ALL SEDIMENT BARRIERS, INCLUDING SILT FENCE MUST BE REPAIRED, REPLACED, OR SUPPLEMENTED WHEN THEY BECOME NONFUNCTIONAL OR THE SEDIMENT REACHES 1/3 OF THE FENCE HEIGHT. THESE REPAIRS SHALL BE MADE WITHIN 24 HOURS OF DISCOVERY.

TEMPORARY AND PERMANENT SEDIMENT BASINS MUST BE DRAINED AND THE SEDIMENT REMOVED WHEN THE DEPTH OF SEDIMENT COLLECTED IN THE BASIN REACHES THE STORAGE VOLUME. DRAINAGE AND REMOVAL MUST BE COMPLETED WITHIN 72 HOURS OF DISCOVERY.

SURFACE WATERS, INCLUDING DRAINAGE DITCHES AND CONVEYANCE SYSTEMS, MUST BE INSPECTED FOR EVIDENCE OF EROSION AND SEDIMENT DEPOSITION. THE CONTRACTOR SHALL REMOVE ALL DELTAS AND SEDIMENT DEPOSITED IN SURFACE WATERS, INCLUDING DRAINAGE WAYS, CATCH BASINS, AND OTHER DRAINAGE SYSTEMS. THE CONTRACTOR SHALL RESTABILIZE THE AREAS WHERE SEDIMENT REMOVAL RESULTS IN EXPOSED SOIL. REMOVAL AND STABILIZATION MUST TAKE PLACE WITHIN 7 DAYS OF DISCOVERY, UNLESS PRECLUDED BY LEGAL, REGULATORY, OR PHYSICAL CONSTRAINTS. THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING ALL LOCAL, REGIONAL, STATE AND FEDERAL AUTHORITIES AND RECEIVING ANY APPLICABLE PERMITS, PRIOR TO CONDUCTING ANY WORK.

CONSTRUCTION SITE VEHICLE EXIT LOCATIONS SHALL BE INSPECTED DAILY FOR EVIDENCE OF OFF-SITE SEDIMENT TRACKING ONTO PAVED SURFACES. TRACKED SEDIMENT MUST BE REMOVED FROM ALL PAVED SURFACES WITHIN 24 HOURS OF DISCOVERY.

THE CONTRACTOR IS RESPONSIBLE FOR THE OPERATION AND MAINTENANCE OF TEMPORARY AND PERMANENT WATER QUALITY BMP'S, AS WELL AS EROSION AND CONTROL BMP'S, FOR THE DURATION OF THE CONSTRUCTION WORK AT THE SITE.

IF SEDIMENT ESCAPES THE CONSTRUCTION SITE, OFF-SITE ACCUMULATIONS OF SEDIMENT MUST BE REMOVED IN A MANOR AND AT A FREQUENCY SUFFICIENT TO MINIMIZE OFF-SITE IMPACTS.

ALL INFILTRATION AREAS MUST BE INSPECTED TO ENSURE THAT NO SEDIMENT FROM ONGOING CONSTRUCTION ACTIVITIES IS REACHING THE INFILTRATION AREAS AND THESE AREAS ARE PROTECTED FROM COMPACTION DUE TO CONSTRUCTION EQUIPMENT DRIVING ACROSS THE INFILTRATION AREA.

RELATED REVIEWS AND PERMITS:

ENVIRONMENTAL, ARCHEOLOGICAL, LOCAL, STATE, AND/OR FEDERAL REVIEWS/PERMIT:

TYPE OF PERMIT/REVIEW:	REQUIRED ACTIONS
WETLAND DISTURBANCE	NONE

POLLUTION PREVENTION MANAGEMENT MEASURES:

THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL POLLUTION PREVENTION MANAGEMENT MEASURES. THE CONTRACTOR IS RESPONSIBLE FOR INFORMING ALL VISITORS AND/OR PERSONNEL ON-SITE OF THE POLLUTION PREVENTION MANAGEMENT MEASURES. ALL POLLUTION PREVENTION MANAGEMENT MEASURES ARE TO BE CONSIDERED INCIDENTAL TO THE MOBILIZATION BID ITEM, UNLESS OTHERWISE NOTED. POLLUTION PREVENTION MANAGEMENT MEASURES INCLUDE BUT ARE NOT LIMITED TO THE FOLLOWING:

THE CONTRACTOR IS RESPONSIBLE FOR THE PROPER DISPOSAL, IN COMPLIANCE WITH MPCA DISPOSAL REQUIREMENTS, OF ALL SOLID WASTE AND HAZARDOUS MATERIALS ON-SITE.

CONCRETE TRUCKS SHALL NOT BE ALLOWED TO WASH OUT OR DISCHARGE SURPLUS CONCRETE OR DRUM WASH WATER ON-SITE, UNLESS DONE IN AN ENGINEERED LEAK-PROOF CONTAINMENT SYSTEM. THE ENGINEERED SYSTEM PROVIDED BY THE CONTRACTOR MUST INCLUDE SITE DRAWINGS FOR THE PROJECT FILE AND WRITTEN ASSURANCE THAT THE SYSTEM WILL WORK AS DESIGNED AND LEAVE NO DISCHARGE OF CONCRETE OR CONCRETE RESIDUE POTENTIAL TO WATERS OF THE STATE DURING A MINIMUM OF A 100-YEAR STORM EVENT. ANY LIQUID AND SOLID WASTE MUST BE DISPOSED OF PROPERLY AND IN COMPLIANCE WITH MPCA REGULATIONS. A SIGN MUST BE INSTALLED ADJACENT TO EACH WASHOUT SYSTEM TO INFORM CONCRETE EQUIPMENT OPERATORS TO UTILIZE THE PROPER FACILITIES. THE CONCRETE WASHOUT CONTAINMENT SYSTEM AND ALL RELATED ITEMS SHALL BE CONSIDERED INCIDENTAL TO THE MOBILIZATION BID ITEM.

ALL NONHAZARDOUS WASTE MATERIALS SHALL BE COLLECTED AND STORED IN A SECURELY LIDDED METAL DUMPSTER OR OTHER APPROVED CONTAINMENT METHOD AT THE END OF EACH DAY. ANY ALTERNATIVE TO A METAL DUMPSTER MUST BE SUBMITTED IN WRITING FOR APPROVAL BY THE PROJECT ENGINEER. THE DUMPSTER SHALL BE EMPTIED AS NECESSARY TO FUNCTION AS INTENDED FOR DEBRIS COLLECTION. NO CONSTRUCTION GARBAGE OR WASTE MATERIAL SHALL BE BURIED ON-SITE.

A LICENSED SANITARY WASTE MANAGEMENT CONTRACTOR SHALL COLLECT ALL SANITARY WASTE FROM THE PORTABLE UNITS AT A RATE NECESSARY TO MAINTAIN DESIGNED FUNCTION.

ALL VEHICLES ON-SITE SHALL BE MONITORED FOR LEAKS AND RECEIVE REGULAR PREVENTION MAINTENANCE TO REDUCE THE CHANCE OF LEEKAGE.

FERTILIZERS SHALL BE STORED IN A COVERED SHELTER. PARTIALLY USED BAGS SHALL BE TRANSFERRED TO A SEALABLE BIN TO REDUCE THE CHANCE OF SPILLAGE.

PETROLEUM PRODUCTS SHALL BE STORED IN TIGHTLY SEALED CONTAINERS, WHICH ARE CLEARLY LABELED.

SPILL KITS SHALL BE INCLUDED WITH ALL FUELING SOURCES AND MAINTENANCE ACTIVITIES. SECONDARY CONTAINMENT MEASURES SHALL BE INSTALLED AND MAINTAINED BY THE OPERATOR.

ANY ASPHALT SUBSTANCES USED ON-SITE SHALL BE APPLIED IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS.

ALL PAINT CONTAINERS AND CURING COMPOUNDS SHALL BE TIGHTLY SEALED AND STORED WHEN NOT REQUIRED FOR USE. EXCESS PAINT AND/OR CURING COMPOUNDS SHALL NOT BE DISCHARGED INTO THE STORM SEWER SYSTEM AND SHALL BE PROPERLY DISPOSED OF ACCORDING TO MANUFACTURE'S INSTRUCTION.

MATERIALS AND EQUIPMENT NECESSARY FOR SPILL CLEAN-UP SHALL BE KEPT IN AN ENCLOSED TRAILER OR SHED ON-SITE. EQUIPMENT SHALL BE INCLUDE, BUT NOT LIMITED TO, BROOMS, MOPS, DUST PANS, RAGS, GLOVES, GOGGLES, ABSORBENT (KITTY LITTER), OIL ABSORBENT BOOMS AND DIAPERS, AND BUCKETS.

ALL SPILLS SHALL BE CONTAINED AND CLEANED UP IMMEDIATELY UPON DISCOVERY. SPILLS LARGE ENOUGH TO REACH THE STORM WATER CONVEYANCE SYSTEM SHALL BE REPORTED TO THE MINNESOTA DUTY OFFICER AT 1.800.422.0798,

EXTERNAL WASHING OF TRUCKS AND OTHER CONSTRUCTION VEHICLES AND ENGINE DEGREASING ARE PROHIBITED AT THE CONSTRUCTION SITE.

SWPPP SHEETS / ADDITIONAL INFORMATION:

THE SWPPP INCLUDES THE FOLLOWING PLAN SHEETS:
GENERAL SWPPP NOTES AND SHEETS - 20-21
EROSION AND SEDIMENT CONTROL SHEETS - 16-19
SWPPP DETAIL SHEETS - 23

THE SWPPP INCLUDES THE SPECIFICATION BID FORM & PROJECT MANUAL.

P:\F\J\JOCON\106141\50-Cad\dwg\Pinshis\lecon106141swppp.dwg 10/7/2014 2:05 PM rthoehn

DRAWN BY:	RVH			
DESIGNER:	GGK/RVH			
CHECKED BY:	JRL			
DESIGN TEAM				

NO.	BY	DATE	REVISIONS



I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

JEFFERY R. LEDIN, P.E.
Date: 10/17/2014 Lic. No. 25222



SPIRIT MOUNTAIN IMPROVEMENTS DULUTH, MINNESOTA

PHONE: 218.855.1700
416 S 6TH ST, STE 200
BRainerd, MN 56401-3540
www.sehinc.com

SWPP PLAN

FILE NO. C20
FOSJJ129137

30

PROJECT SPECIFIC INFORMATION:

TOTAL PROJECT AREA: 15.50 ACRES
 TOTAL LAND AREA TO BE DISTURBED: 5.50 ACRES
 PRE-CONSTRUCTION IMPERVIOUS AREA: 0 ACRES
 POST-CONSTRUCTION IMPERVIOUS AREA: 0 ACRES
 IMPERVIOUS AREA ADDED: 0 ACRES

RECEIVING WATERS WITHIN 1 MILE FROM PROJECT BOUNDARIES:

WATER BODY: ST. LOUIS RIVER
 TYPE: RIVER
 IMPAIRMENT: DDT, DIOXIN, MERCURY, PCB, TOXAPHENE
 SPECIAL WATER CLASSIFICATION: YES
 REQUIRED ADDITIONAL BMPs: YES—SOIL STABILIZATION WITHIN 7 DAYS,
 WATER QUALITY VOLUME 1”
 TMDL: NO
 REQUIRED TMDL ACTIONS: NONE

WATER BODY: KNOWLTON CREEK
 TYPE: CREEK
 IMPAIRMENT: NONE
 SPECIAL WATER CLASSIFICATION: YES
 REQUIRED ADDITIONAL BMPs: YES— SOIL STABILIZATION WITHIN 7 DAYS,
 WATER QUALITY VOLUME 1” WITH 1/2” INFILTRATION.
 TMDL: NO
 REQUIRED TMDL ACTIONS: NONE

THIS PROJECT IS NOT LOCATED IN A KARST AREA.
 THE PROJECT DOES NOT DISCHARGE TO A CALCAREOUS FEN.

SITE SOIL INFORMATION:

SOIL INFORMATION PROVIDED IS OBTAINED FROM THE USGS SOIL SURVEY INFORMATION AND IS FOR NPDES PERMIT INFORMATION ONLY. THE OPERATOR SHALL NOT RELY ON THIS SOIL INFORMATION

SOIL NAME	HYDROLOGIC CLASSIFICATION
MISKOKI-FLUVAQUENUTS, COMPLEX	D
BARTO, STONY GRESOLON-ROCK OUTCROP	D
HULLIGAN FINE SANDY LOAM	A/D
BOWSTRING AND FLUVAQUENTS, LOAMY	B/D

SEDIMENT CONTROL MEASURES AND TIMING:

THE CONTRACTOR IS RESPONSIBLE FOR ALL SEDIMENT CONTROL MEASURES FOR THE PROJECT. SEDIMENT CONTROL MEASURES INCLUDE BUT ARE NOT LIMITED TO THE FOLLOWING:

SEDIMENT CONTROL MEASURES SHALL BE ESTABLISHED ON ALL DOWN GRADIENT PERIMETERS BEFORE ANY UPGRADIENT LAND DISTURBING ACTIVITIES BEGIN. THESE MEASURES SHALL REMAIN IN PLACE UNTIL FINAL STABILIZATION HAS BEEN ESTABLISHED.

ON SLOPES WITH 3:1 OR STEEPER GRADES, THERE SHALL BE NO UNBROKEN SLOPE LENGTH GREATER THAN 75 FEET.

ALL STORM DRAIN INLETS AND CULVERT INLETS SHALL BE PROTECTED BY AN APPROPRIATE BMP DURING CONSTRUCTION UNTIL ALL SOURCES WITH POTENTIAL FOR DISCHARGING TO THE INLET HAS BEEN STABILIZED. INLET AND CULVERT PROTECTION SHALL CONFORM TO THE 2005 MNDOT SPECIFICATIONS 2573 AND 3891.

STOCK PILES SHALL BE PROVIDED WITH AN EFFECTIVE SEDIMENT PERIMETER CONTROL AND SHALL NOT BE PLACED IN ANY TYPE OF SURFACE WATER.

VEHICLE TRACKING SHALL BE MINIMIZED WITH EFFECTIVE BMPs. WHERE THE BMPs FAIL TO PREVENT SEDIMENT FROM TRACKING ONTO STREETS THE CONTRACTOR SHALL CONDUCT STREET SWEEPING TO REMOVE ALL TRACKED SEDIMENT.

TEMPORARY SEDIMENT BASINS:

THE CONTRACTOR SHALL INSTALL TEMPORARY SEDIMENT BASIN AS INDICATED IN THE PLANS OR AS REQUIRED BY THE NPDES CONSTRUCTION PERMIT.

TEMPORARY SEDIMENT BASINS SHALL BE CONSTRUCTED AND MADE OPERATIONAL CONCURRENT WITH THE START OF SOIL DISTURBANCE THAT IS UPGRADIENT AND CONTRIBUTES RUNOFF TO THE AREA

TEMPORARY SEDIMENT BASINS SHALL BE CONSTRUCTED TO PREVENT SHORT-CIRCUITING OF STORM WATER TREATMENT AND PREVENT DISCHARGE OF FLOATING DEBRIS.

TEMPORARY SEDIMENT BASINS SHALL BE PROVIDED WITH ENERGY DISSIPATION TO PREVENT SOIL EROSION.

EROSION PREVENTION MEASURES AND TIMING:

THE CONTRACTOR IS RESPONSIBLE FOR ALL EROSION PREVENTION MEASURES FOR THE PROJECT. EROSION PREVENTION MEASURES INCLUDE BUT ARE NOT LIMITED TO THE FOLLOWING:

THE CONTRACTOR SHALL PLAN AND IMPLEMENT APPROPRIATE CONSTRUCTION PRACTICES AND CONSTRUCTION PHASING TO MINIMIZE EROSION AND RETAIN VEGETATION WHENEVER POSSIBLE.

ALL AREAS NOT TO BE DISTURBED SHALL BE DELINEATED WITH FLAGS, STAKES, SIGNS, OR OTHER MEANS NECESSARY TO PROTECT THESE AREAS BEFORE CONSTRUCTION BEGINS ON THE SITE.

ALL DRAINAGE DITCHES AND/OR SWALES SHALL HAVE TEMPORARY OR PERMANENT STABILIZATION WITHIN 24 HOURS OF CONNECTING TO A SURFACE WATER OR 24 HOURS AFTER CONSTRUCTION ACTIVITY IN THE DITCH/SWALE HAS TEMPORARILY OR PERMANENTLY CEASED.

ALL PIPE OUTLETS SHALL HAVE TEMPORARY OR PERMANENT ENERGY DISSIPATION WITH 24 HOURS OF CONNECTING TO A SURFACE WATER.

ALL EXPOSED SOILS SHALL BE STABILIZED AS SOON AS POSSIBLE TO LIMIT SOIL EROSION. IN NO CASE SHALL UN-WORKED AREAS, INCLUDING STOCK PILES, HAVE EXPOSED SOILS FOR MORE THAN 7 DAYS WITHOUT PROVIDING TEMPORARY OR PERMANENT STABILIZATION.

DEWATERING AND BASIN DRAINING ACTIVITIES:

THE CONTRACTOR IS RESPONSIBLE FOR ADHERING TO ALL DEWATERING AND SURFACE DRAINAGE REGULATIONS, INCLUDING BUT NOT LIMITED TO THE FOLLOWING:

WHENEVER POSSIBLE WATER FROM DEWATERING ACTIVITIES SHALL DISCHARGE TO A TEMPORARY AND/OR PERMANENT SEDIMENT BASIN.

IF WATER CANNOT BE DISCHARGED TO A SEDIMENTATION BASIN, IT SHALL BE TREATED WITH THE OTHER APPROPRIATE BMPs, TO EFFECTIVELY REMOVE SEDIMENT.

ALL DISCHARGE POINTS SHALL BE PROTECTED FROM EROSION AND SCOUR.

DISCHARGE WATER SHALL BE DISPERSED OVER AN EFFECTIVE ENERGY DISSIPATION MEASURE.

ALL WATER FROM DEWATERING SHALL BE DISCHARGED IN A MANNER THAN DOES NOT CAUSE NUISANCE CONDITIONS, EROSION, OR INUNDATION OF WETLANDS.

FINAL STABILIZATION:

THE CONTRACTOR IS RESPONSIBLE FOR ENSUING FINAL STABILIZATION OF THE SITE. FINAL STABILIZATION INCLUDES BUT IS NOT LIMITED TO THE FOLLOWING:

ALL SOIL DISTURBING ACTIVITIES HAVE BEEN COMPLETED.

ALL EXPOSED SOILS HAVE BEEN UNIFORMLY STABILIZED WITH AT LEAST 70% VEGETATION COVERAGE.

ALL DRAINAGE DITCHES, PONDS AND ALL STORM WATER CONVEYANCE SYSTEMS HAVE BEEN CLEARED OF SEDIMENT AND STABILIZED TO PRECLUDE EROSION.

ALL TEMPORARY BMPs HAVE BEEN REMOVED AND PROPERLY DISPOSED OF.

FINAL STABILIZATION SHALL BE PERFORMED IN ACCORDANCE WITH MNDOT 2005 SPECIFICATION 2575.

PROJECT SPECIFIC NOTES:

1) EQUIPMENT SHALL BE PRESSURE WASHED BEFORE COMMENCING WORK

2) TEMPORARY IMPACTS WILL BE RESTORED APPROPRIATELY USING BEST MANAGEMENT PRACTICES (BMPs). SILT FENCE WILL BE INSTALLED ALONG THE CONSTRUCTION CORRIDORS TO DEFINE THE CONSTRUCTION LIMITS AND PROJECT ADJACENT WETLANDS. THIS FENCING WILL ALSO ENSURE THAT WORK WITHIN WETLANDS IS COMPLETED IN ONLY THOSE AREAS NECESSARY (AND AS PERMITTED) FOR INSTALLATION OF UTILITIES. THE EXCAVATED WETLAND SOIL WILL BE STOCKPILED SEPARATELY WITHIN THE CONSTRUCTION LIMITS OR COMPLETELY OUTSIDE OF WETLAND AREAS. EXCAVATED SOIL WILL NOT BE STOCKPILED IN ANY OTHER WETLAND AREAS THAT HAVE NOT BEEN PERMITTED FOR IMPACTS AS SUCH. THE EXCAVATED WETLAND SOIL WILL BE STRIPPED AND STOCKPILED PRIOR TO ANY EXCAVATION FOR THE UTILITY TRENCH. UPON COMPLETION OF THE UTILITY INSTALLATION, THE SOILS WILL BE REPLACED IN THE OPPOSITE ORDER THEY WERE EXCAVATED TO RESEMBLE THE PRE-CONSTRUCTION SOIL PROFILE. THIS WILL INSURE THAT THE EXCAVATED WETLAND TOPSOIL IS APPROPRIATELY PLACED AT THE SURFACE FOR RE-SEEDING NATIVE WETLAND VEGETATION.

General Note (GN1) To Address Temporary Wetland Impacts

Temporary impacts will be restored appropriately using best management practices (BMPs). Silt fence will be installed along the construction corridors to define the construction limits and protect adjacent wetlands. This fencing will also ensure that work within wetlands is completed in only those areas necessary (and as permitted) for installation of the utilities. The excavated wetland soil will be stockpiled separately within the construction limits or completely outside of wetland areas. Excavated soil will not be stockpiled in any other wetland areas that have not been permitted for impacts as such. The excavated wetland soil will be stripped and stockpiled prior to any excavation for the utility trench. Upon completion of the utility installation, the soils will be replaced in the opposite order they were excavated to resemble the pre-construction soil profile. This will insure that the excavated wetland topsoil is appropriately placed at the surface for re-seeding native wetland vegetation.

Location 1

- Mitigation: At this location GN1 will be applied. After removal of the wetland soils the pipe will be installed and the surface restored.
- Also a permanent retaining wall will be installed upland of wetland boundary to facilitate grading and prevent filling of wetland
- Avoidance: The pipeline route is generally perpendicular to the St Louis River and connects Spirit Mountain and the river. Upstream and downstream alignments were considered, however this location was selected to avoid other more significant wetland impacts.

Location 2

- This wetland is a drainage ditch parallel to railroad tracks
- Avoidance: The pipeline will be installed by jack/bore construction and no impacts will occur.

Location 3

- This area is converted to wetlands from prior grading and earthmoving
- Mitigation: At this location GN1 will be applied.
- Avoidance: The alignment in this reach of the pipeline was granted by the Developer of the property, and generally located at the top of the bluff area leading to Knowlton Creek. The location of the pipe is confined to the right-of-way corridor.

Location 4

- This area is a longitudinal drainage way and the same amount of impact would occur if the alignment were moved up or down the hill
- Mitigation: At this location GN1 will be applied.
- Avoidance: The alignment in this reach of the pipeline was granted by the Developer of the property, and generally located at the top of the bluff area leading to Knowlton Creek. The location of the pipe is confined to the right-of-way corridor.

Location 5

- Wetland is at toe of slope at Trail Grade
- Avoidance: Pipe will be installed by directional drilling under the trail and impact will be avoided.

Location 6

- This area is a drainage ditch bottoms adjacent to the recently constructed chalet
- Avoidance: If the alignment were shifted, additional clearing of trees would be needed and the drainage way would be crossed at a different location

Location 7

- This area is a drainage ditch bottoms adjacent to the recently constructed chalet.
- Avoidance: If the alignment were shifted, additional clearing of trees would be needed and the drainage way would be crossed at a different location

Location 8

- This wetland occurs at a natural low point in the grading.
- Mitigation: At this location GN1 will be applied.
- Avoidance: The alignment is necessarily dictated by connecting the low points to capture excess storm water runoff.

Location 9

- This wetland occurs at a natural low point in the grading.
- Mitigation: At this location GN1 will be applied
- Large open drainage swale will be constructed in this area and wetland will likely expand as a result of the change.

WETLAND AREAS	
LOCATION NO.	AREA (SQ FT)
1	5171
2	228
3	387
4	376
5	523
6	176
7	709
8	605
9	3228

P:\F\J\JOCON\106141\50-Cad-dwg\Pinshis\Jocon106141\swpp.dwg 10/7/2014 2:05 PM rthoehn

DRAWN BY: RVH				
DESIGNER: GJK/RVH				
CHECKED BY: JRL				
DESIGN TEAM	NO.	BY	DATE	REVISIONS



I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.
 Date: 10/17/2014
 Lic. No. 25222
 JEFFERY R. LEDIN, P.E.



SPIRIT MOUNTAIN IMPROVEMENTS DULUTH, MINNESOTA

SWPP PLAN


FILE NO. C21
 FOSJ129137
 30

DRAINAGE SUMMARY MAP

LEGEND

- PRE-CONSTRUCTION DRAINAGE DIVIDING LINE
- ← PRE-CONSTRUCTION DRAINAGE ARROW
- PRE-CONSTRUCTION IMPERVIOUS AREA
- POST-CONSTRUCTION DRAINAGE DIVIDING LINE
- ← POST-CONSTRUCTION DRAINAGE ARROW
- POST-CONSTRUCTION IMPERVIOUS AREA
- (X) RECEIVING WATER

RUNOFF COLLECTION SYSTEM AREA



P:\F\J\JOCON\06141\50-Cod\C3D\C122747ec.dwg 10/7/2014 2:05 PM rnoehh

DRAWN BY: RVH				
DESIGNER: GJK/RVH				
CHECKED BY: JRL				
DESIGN TEAM	NO.	BY	DATE	REVISIONS



I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

Jeffery R. Ledin
 JEFFERY R. LEDIN, P.E.
 Date: 10/17/2014 Lic. No. 25222




PHONE: 218.855.1700
 416 S 6TH ST, STE 200
 BRAINERD, MN 56401-3540
 www.sehinc.com

SPRIT MOUNTAIN IMPROVEMENTS DULUTH, MINNESOTA

SWPP PRE/POST CONSTRUCTION

FILE NO. C22
 FOSJJ129137

30




SILT FENCE BOX TO PROTECT DROP INLETS USE WHERE INLET DRAINS AN AREA WITH SLOPES AT 1:3 OR LESS (TYPE A. SPEC 3891)

NTS

INLET PROTECTION - TYPE A

Revised: Oct. 2011
SEH Plate No. ERO-01

① ALL GEOTEXTILE USED FOR INLET PROTECTION SHALL BE MONOFILAMENT IN BOTH DIRECTIONS, MEETING MN/DOT SPEC 3886 FOR MACHINED SLICED.




GEOTEXTILE FILTER AT STREET INLET WITH CURB BOX MN/DOT TYPE C SPEC. 3891

NTS

INLET PROTECTION - TYPE C

Revised: Oct. 2011
SEH Plate No. ERO-03



NOTES:

THE AMOUNT OF SILT FENCE ABOVE GROUND SHOULD BE 24" TO 28". WHEN SEDIMENT BUILD UP REACHES 8" TO 9", THE SEDIMENT MUST BE REMOVED.

SPACING BETWEEN EACH DITCH CHECK SHOULD BE DETERMINED FROM THE FOLLOWING SPACING FORMULA:

$$\text{SPACING (FT)} = \frac{\text{DITCH CHECK HEIGHT (FT)}}{\% \text{ CHANNEL SLOPE}}$$

POINT "A" LABELED ON DETAILS SHALL BE A MIN. OF 6" HIGHER THAN POINT "B" TO ENSURE THAT WATER FLOWS OVER THE DIKE AND NOT AROUND THE ENDS.


CHECK DAMS AND DIKES SHOULD BE LIMITED IN USE FOR DRAINAGE AREAS OF LESS THAN FIVE ACRES AND IN CHANNELS OF LESS THAN TEN PERCENT SLOPE.

IF IN SERIES, THE TOP OF THE DOWNSTREAM DAM OR DIKE SHOULD ALIGN WITH THE BOTTOM OF THE UPSTREAM.

NTS

SILT FENCE DITCH CHECK

Revised: Oct. 2011
SEH Plate No. ERO-08



NOTES:

-REFER TO SPECS FOR TYPE OF SILT CURTAIN (STILL OR MOVING WATER).


-DOUBLE SILT CURTAINS SHOULD BE SPACED 10' APART.

-CURTAIN LENGTH TO MATCH BOTTOM PROFILE AS CLOSELY AS POSSIBLE.

NTS

FLOTATION SILT CURTAIN

Revised: Oct. 2011
SEH Plate No. ERO-14



DESIGN GUIDELINES: (SEE MNDOT SPEC. 2573.3C AND 3886)


NTS

SILT FENCE

Revised: Jan. 2013
SEH Plate No. ERO-15

CLASS II RIPRAP REQUIREMENTS
12" TO 24" 4 CUBIC YARDS
27" TO 33" 8 CUBIC YARDS
36" TO 48" 12 CUBIC YARDS
(APPROX. 1.4 TONS PER CUBIC YARD)

CLASS III RIPRAP* REQUIREMENTS
12" TO 24" 6 CUBIC YARDS
27" TO 33" 12 CUBIC YARDS
36" TO 48" 18 CUBIC YARDS
(APPROX. 1.4 TONS PER CUBIC YARD)




NOTE: FILTER BLANKET REQUIRED UNDER RIPRAP OR 2 LAYERS OF 500X "MIRAFI" FABRIC OR EQUAL

* CLASS III RIPRAP, D50= 9 IN.

NTS

CLASS II AND III RIPRAP AT OUTLETS

Revised: Oct. 2011
SEH Plate No. ERO-23




① POINT "A" SHALL BE A MINIMUM OF 6" HIGHER THAN POINT "B" TO ENSURE THAT WATER FLOWS OVER THE DIKE AND NOT AROUND THE ENDS.

NTS

BIOROLL DITCH CHECK

Revised: Oct. 2011
SEH Plate No. ERO-05



NOTE:

TO PREVENT TRACKING OF MUD ONTO PAVED ROADS, INSTALL ADDITIONAL ROCK OR REMOVE AND REPLACE THE PAD AS REQUIRED

NTS

ROCK CONSTRUCTION ENTRANCE

Revised: Oct. 2011
SEH Plate No. ERO-35

P:\F\J\JOCON\06141\50-Cod\C3D\C122747ec.dwg 10/7/2014 2:05 PM rtoehr

DRAWN BY: RVH
DESIGNER: GKG/RVH
CHECKED BY: JRL

NO.	BY	DATE	REVISIONS



I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

JEFFERY R. LEDIN, P.E.
Lic. No. 25222

Date: 10/17/2014




PHONE: 218.855.1700
416 S 6TH ST, STE 200
BRAINERD, MN 56401-3540
www.sehinc.com



SWPP DETAILS

FILE NO. FOSJ129137

C23
30



STATEMENT OF ESTIMATED QUANTITIES CREEK RESTORATION			
ITEM DESCRIPTION	UNIT OF MEASUREMENT	QUANTITY	BASIS
REMOVE EX SILT FENCE	LF	300	
REMOVE EX RCP CULVERT	LF	160	DISPOSE OF OFF SITE
CLEAR & GRUB TREE	EA	4	DISPOSE OF OFF SITE
COMMON EXCAVATION	CY	875	
RIPRAP CL III	CY	25	
1.5" WASHED ROCK	CY	45	15' WIDE CREEK BOTTOM - REUSE EXISTING ROCKS AS WELL
TOPSOIL BORROW	CY	394	
EROSION CONTROL BLANKET	SY	2362	
SEEDING (INCL FERTILIZER)	AC	0.49	MN SEED MIX 36-311
INSTALL SILT FENCE	LF	400	

P:\FJ\JOCON\106141\50-Cad\extra work\Creek_regrading_TY.dwg 10/20/2014 4:06 PM rhoeht

DRAWN BY: RVH				
DESIGNER: RVH				
CHECKED BY: JRL				
DESIGN TEAM	NO.	BY	DATE	REVISIONS



I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A FULLY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

Jeffery R. Ledin
 JEFFERY R. LEDIN, P.E.
 Date: 10/17/2014 Lic. No. 25222



CREEK GRADING
 SPIRIT MOUNTAIN
 DULUTH, MN

TYPICAL SECTIONS
 SEQ / DETAILS

FILE NO. C24
 FOSJJ129137
 30


REMOVALS



GRADING



DIVERSION DITCH TYPICAL



SLOPE CORRECTION KNOWLTON CREEK

P:\F\J\JOCON\106141\50-Cad\extra work\Creek_regrading_Plan.dwg 10/13/2014 11:23 AM rhoeht

DRAWN BY:	RVH			
DESIGNER:	RVH			
CHECKED BY:	JRL			
DESIGN TEAM	NO.	BY	DATE	REVISIONS



I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A FULLY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.
 Date: 10/17/2014
 Lic. No. 25222




PHONE: 320.229.4300
 1200 25TH AVENUE SOUTH
 P.O. BOX 1717
 ST. CLOUD, MN 56302-1717
 www.sehinc.com

CREEK GRADING
 SPIRIT MOUNTAIN
 DULUTH, MN

NOTES, VIEWS

FILE NO.
 FOSJ129137


C25
 30



EXISTING ROCKS TO BE REMOVED
AND REPLACE WITH CLASS IV RIPRAP
TO PROVIDE 20' CHANNEL WIDTH



EXISTING ABUTMENT FILL MATERIAL TO BE
REMOVED AND REPLACED WITH CLASS IV RIPRAP



P:\F\J\JOCON\106141\50-Cad\extra work\SM125435BA2.dwg 10/22/2014 8:24 AM rhoehm

DRAWN BY:	ACO			
DESIGNER:	JRL			
CHECKED BY:	KLA			
DESIGN TEAM		NO.	BY	DATE
				REVISIONS



I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A FULLY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

Jeffery R. Ledin
JEFFERY R. LEDIN, P.E.
Date: 10/18/2014 Lic. No. 25222





DULUTH,
MINNESOTA





SPIRIT MOUNTAIN RECREATION AREA
KNOWLTON CREEK BRIDGE
EXISTING CONDITIONS

FILE NO.
FOSJJ129137

B1
30



- NOTES:**
- THIS DRAWING ASSUMES PILING DRIVEN FIRST. THEN ADJUST DIMENSIONS AS REQUIRED FOR IN-PLACE PILE LOCATIONS.
 - CONTRACTOR SHALL ENGAGE A GEOTECHNICAL ENGINEER TO TAKE A SOIL BORING AT THE LOCATION OF THIS PLATFORM FROM CONTRACTOR'S BARGE, TAKEN TO A MINIMUM DEPTH OF 75 FEET BELOW RIVERBED, TO GAIN INFORMATION NECESSARY FOR GEOTECHNICAL ENGINEER TO DESIGN PILE LENGTHS TO CARRY A SERVICE LOAD OF 15 TONS. FOR BIDDING PURPOSES, CONTRACTOR SHALL ASSUME PILE LENGTH OF 50 FEET AFTER FILLING AND CUTOFF, INCLUDING SPLICES AS REQUIRED. (FILLING IS DONE WITH PILE HEAD ABOVE WATER BEFORE CUTOFF.) CONTRACTOR SHALL PROVIDE UNIT COST PER FOOT OF ADDITIONAL PILE LENGTH. CONTRACTOR'S GEOTECHNICAL ENGINEER SHALL USE SOIL INFORMATION THUS GAINED IN THE USE OF PILE DRIVING ANALYZER PER ASTM D4945 TO CONFIRM DESIGNED LENGTH DURING DRIVING. SEE SPECIFICATION SECTION 01 45 29.



S:\F\FOSS\J129137\5-final-dsgn\51-const.dwg-CAD\20-Struct\Contract A S1-S2.dwg 10/15/2014 2:42 PM jburns

DRAWN BY: JMB				
DESIGNER: JMB				
CHECKED BY: MLH				
DESIGN TEAM	NO.	BY	DATE	REVISIONS



I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

Michael L. Hemstad
MICHAEL L. HEMSTAD, PE
Date: OCTOBER 17, 2014 Lic. No. 19165




PLATFORM PLANS
CONTRACT 'A'
SPIRIT MOUNTAIN
DULUTH, MN

STRUCTURAL PLAN AND SECTIONS


FILE NO.
FOSJJ129137

S1
30


S:\F\FOSS\J129137\5-fin-dgn\51-const.dwg-CAD\20-Struct\Contract A S1-S2.dwg 10/15/2014 2:42 PM jburris




A PICK-UP POINT BEAM DETAIL
S2 SCALE: NONE




B SIDE EDGE BEAM DETAIL
S2 SCALE: NONE




C FRONT EDGE BEAM DETAIL
S2 SCALE: NONE




D WALL DETAIL
S2 SCALE: NONE




E SLAB DETAIL
S2 SCALE: NONE




F OPENING REINFORCEMENT DETAIL
S2 NOT TO SCALE



G WALL CORNER REINFORCEMENT DETAIL
S2 NOT TO SCALE



H PILE HANGER DETAILS
S2 SCALE: NONE



I SADDLE DETAIL
S2 SCALE: NONE

- SAND w/ NOT MORE THAN 8% PASSING #200 SIEVE COMPACT IN 8" LOOSE LIFTS TO 95% OF THE STANDARD MAXIMUM DRY UNIT WEIGHT PER ASTM D698 (STANDARD PROCTOR TEST)
- SELECT GRANULAR BORROW COMPACT TO 98% OF THE STANDARD MAXIMUM DRY UNIT WEIGHT PER ASTM D698 (STANDARD PROCTOR TEST)
- COURSE FILTER AGGREGATE WRAPPED IN GEOTEXTILE SEPARATION FABRIC

J SOIL CORRECTION FOR WET WELL DIAGRAM
S2

DRAWN BY:	JMB			
DESIGNER:	JMB			
CHECKED BY:	MLH			
DESIGN TEAM	NO.	BY	DATE	REVISIONS



I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.
Michael L. Hemstad
 MICHAEL L. HEMSTAD, PE
 Date: OCTOBER 17, 2014 Lic. No. 19165

SEH
 PHONE: 320.229.4300
 1200 25TH AVENUE SOUTH
 P.O. BOX 1717
 ST. CLOUD, MN 56302-1717
 www.sehinc.com

PLATFORM PLANS
 CONTRACT 'A'
 SPIRIT MOUNTAIN
 DULUTH, MN

STRUCTURAL DETAILS

FILE NO.
 FOSJJ129137
S2
30

GENERAL STRUCTURAL NOTES

THESE NOTES DO NOT REPLACE THE SPECIFICATIONS BUT ARE TO BE READ IN CONJUNCTION WITH THEM. ANY DISCREPANCIES OR CONFLICTS BETWEEN THE TWO SHALL BE BROUGHT TO THE ATTENTION OF THE SER FOR RESOLUTION.

GOVERNING BUILDING CODE:

- 1. 2007 MINNESOTA STATE BUILDING CODE.
2. 2006 INTERNATIONAL BUILDING CODE AS ADOPTED AND AMENDED BY THE STATE BUILDING CODE
3. ACI - 318
4. AISC - 360, 303

DESIGN LOADS

- 1. LIVE LOAD: NOT APPLICABLE
2. SNOW LOADS: NOT APPLICABLE
3. WIND LOADS: NOT APPLICABLE
4. SEISMIC LOADS: NOT APPLICABLE
5. SOIL CRITERIA:

APPROX. WATER ELEVATION 602.0

Table with 2 columns: Property (ALLUVIAL BACKFILL, WET UNIT WEIGHT, FRICTION ANGLE, AT-REST PRESSURE) and Value (115 PCF, 30 DEGREES, 55 PCF).

DESIGN / CONSTRUCTION CRITERIA

- 1. DESIGN OF PLATFORM ASSUMES DRIVING PILING, FILLING WITH CONCRETE TO CUTOFF ELEVATION, CUTTING OFF, THEN ADJUSTING DIMENSIONS OF PLATFORM TO SUIT FINAL SURVEYED PILE LOCATIONS.
2. THE CONTRACTOR SHALL VERIFY DIMENSIONS AND CONDITIONS BEFORE CONSTRUCTION AND NOTIFY THE ENGINEER OF ANY DISCREPANCIES, INCONSISTENCIES, OR DIFFICULTIES AFFECTING THE WORK BEFORE PROCEEDING.
3. ALL MATERIAL, WORKMANSHIP, AND DETAILS SHALL BE IN ACCORDANCE WITH TYPICAL COMPETENT CONSTRUCTION PRACTICES...

FOUNDATIONS

- 1. CAUTION: EXISTING UNDERGROUND UTILITIES MAY EXIST ANYWHERE ON THE SITE. NOTIFY GOPHER ONE-CALL (800) 252-1166 PRIOR TO DISTURBING ANY GRADE OR EXCAVATION.
2. STRUCTURAL FOUNDATIONS CONSIST OF 12 INCH DIAMETER CAST IN PLACE PILING DRIVEN TO A SAFE WORKING CAPACITY OF 15 TONS...

DRIVEN PILES

- 1. THE FOUNDATION SYSTEM SHALL BE SUPPORTED BY CLOSED END DRIVEN STEEL PIPE PILING BASED ON THE RECOMMENDATIONS OF THE CONTRACTOR'S GEOTECHNICAL ENGINEER.
2. PILES ARE DESIGNED FOR A MAXIMUM NET CAPACITY OF 15 TONS PER PILE (WORKING LOAD). MAXIMUM NET CAPACITIES SHALL HAVE A MINIMUM FACTOR OF SAFETY OF 2.0.
3. PILES ARE NOT DESIGNED FOR UPLIFT LOAD.

CONCRETE

- 1. CONCRETE AND ITS PLACEMENT SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE FOLLOWING: ACI 318 BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE
2. AN INDEPENDENT TESTING AGENCY SHALL CAST 4 TEST CYLINDERS FOR EACH 50 CUBIC YARDS OF EACH CONCRETE MIX PLACED OR FOR EACH DAY'S OPERATION, WHICH EVER IS THE LESSER AMOUNT.
3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DESIGN OF FORM WORK TO COMPLY WITH THE DIMENSIONS INDICATED ON THE PLANS...

- 9. WET POLY CURE CONCRETE MINIMUM 5 DAYS FROM SLAB CONCRETE PLACEMENT AND ASSURE MINIMUM STRENGTH OF 3500 PSI BEFORE LIFTING.
10. CEMENTITIOUS GROUT SHALL BE NON-SHRINK AND NON-METALLIC GROUT. PLACE ACCORDING TO MANUFACTURER'S RECOMMENDATIONS AND TRIM NEATLY WHERE VISIBLE.
11. COORDINATE WITH OTHER TRADES FOR SLEEVES, ANCHOR BOLTS, INSERTS, PIPING, AND OTHER ITEMS TO BE EMBEDDED INTO CONCRETE...

REINFORCING STEEL

- 1. ALL REINFORCING STEEL SHALL BE DETAILED, FABRICATED, AND INSTALLED IN ACCORDANCE WITH THE FOLLOWING STANDARDS AND CODES: ACI 315 "DETAILS AND DETAILING OF CONCRETE REINFORCING"
2. ALL CONCRETE IS REINFORCED CONCRETE UNLESS SPECIFICALLY CALLED OUT AS UNREINFORCED. REINFORCE ALL CONCRETE NOT OTHERWISE SHOWN WITH SAME STEEL AS IN SIMILAR SECTIONS OR AREAS.
3. ALL REINFORCING STEEL SHALL CONFORM TO THE REQUIREMENTS OF ASTM A615 OR A706 GRADE 60 STEEL...

Table with 6 columns: REINF. BAR SIZE, WALL, COLUMN OR SLAB, BEAMS (BAR LAP, *TOP BAR), 90 DEGREE END HOOK. Rows #3 to #11.

- 7. BARS MARKED CONTINUOUS, CORNER BARS, AND ALL VERTICAL STEEL SHALL BE LAPPED IN ACCORDANCE WITH TABLE ABOVE AT SPLICES AND EMBEDMENTS.
8. BAR SUPPORT ACCESSORIES SHALL BE AS SPECIFIED IN LATEST EDITION OF THE ACI DETAILING HANDBOOK AND THE CONCRETE REINFORCING STEEL INSTITUTE DESIGN HANDBOOK.

CONCRETE REPAIR (FOR AREAS DAMAGED OR INADEQUATELY CONSOLIDATED)

- 1. LOCATE AND REMOVE AREAS OF LOOSE, DELAMINATED, OR DAMAGED CONCRETE. SAWCUT OUTSIDE PERIMETER OF DAMAGED AREAS TO A MINIMUM DEPTH OF APPROXIMATELY 3/4 INCH.
2. WHERE HALF OR MORE OF THE PERIMETER OF REINFORCING BAR IS EXPOSED, BOND BETWEEN REINFORCING BAR AND SURROUNDING CONCRETE IS BROKEN, OR REINFORCING BAR IS CORRODED, REMOVE CONCRETE FROM ENTIRE PERIMETER OF BAR TO PROVIDE MINIMUM 3/4 INCH CLEARANCE BEHIND BAR.
3. DAMPEN PATCH AREA AND APPLY MORTAR SCRUB COAT, KEEPING MOIST UNTIL PATCH IS APPLIED.

POST INSTALLED ANCHOR RODS AND DOWELS

- 1. UNLESS NOTED OTHERWISE, ANCHORS AND REINFORCING DOWELS INSTALLED IN CONCRETE OR CONCRETE MASONRY SHALL BE AS NOTED BELOW. ANCHORS NOT SHOWN OR NOTED ON THE DRAWINGS, THOSE REQUIRED BY THE CONTRACTOR SOLELY FOR HIS MEANS AND METHODS, OR THOSE REQUIRED BY MECHANICAL/ELECTRICAL AND CARRYING LESS THAN 100 POUNDS, DO NOT REQUIRE SPECIAL INSPECTION.
2. APPROVED MANUFACTURERS ARE: HILTI, ITW/REDHEAD, SIMPSON, AND POWERS/RAWL.
3. PERMANENT ANCHORS EXPOSED TO EARTH, WEATHER, OR CORROSIVE ENVIRONMENTS, INCLUDING ALL ANCHORS IN WWTP AND WATER TREATMENT PLANT WORK, SHALL BE STAINLESS STEEL TYPE 304 OR 316...

INCHES) AS RECOMMENDED BY MANUFACTURER UNLESS SPECIFICALLY NOTED OTHERWISE IN THE DRAWINGS.

- 8. UNLESS NOTED OTHERWISE, ANCHORS SHALL BE INSTALLED TO THE FOLLOWING EMBEDMENTS:

Table with 4 columns: EXPANSION/SCREW, DIAMETER, CIP CONCRETE, GROUTED CMU. Rows for 1/2 INCH, 5/8 INCH, 3/4 INCH.

Table with 4 columns: ADHESIVE, DIAMETER, CIP CONCRETE, GROUTED CMU. Rows for 1/2 INCH, 5/8 INCH, 3/4 INCH.

- 9. EXCEPT AS NOTED, ALL ANCHORS SHALL HAVE INTERMITTENT SPECIAL STRUCTURAL INSPECTION BY ONE OF THE FOLLOWING. LOAD TESTS SHALL BE TO 150 PERCENT OF SERVICE CAPACITY OR 50 PERCENT OF ULTIMATE STRENGTH, WITH NO APPRECIABLE SLIP OR PERMANENT DEFORMATION.
EXPANSION AND SCREW ANCHORS:
- WITNESS INSTALLATION WITH TORQUE WRENCH ACCORDING TO MANUFACTURER'S RECOMMENDATIONS AND REQUIREMENTS OF ICC REPORT
- TEST WITH TORQUE WRENCH AFTER INSTALLATION (INCLUDING LOAD TEST OF 5 PERCENT OF INSTALLED ANCHORS)
- LOAD TEST OF 10 PERCENT OF INSTALLED ANCHORS BY SUPPLIER OR THIRD PARTY INSPECTOR

ALL ADHESIVE ANCHOR RODS AND DOWELS SHALL HAVE SPECIAL STRUCTURAL INSPECTION (INTERMITTENT EXCEPT AS NOTED FOR OVERHEAD INSTALLATION) BY ONE OF THE FOLLOWING:

- WITNESS INSTALLATION ACCORDING TO MANUFACTURER'S RECOMMENDATIONS AND REQUIREMENTS OF ICC REPORT
- LOAD TEST OF 10 PERCENT OF INSTALLED ANCHORS BY SUPPLIER OR THIRD PARTY INSPECTOR

SHOP DRAWING REVIEW

- 1. SHORT ELLIOTT HENDRICKSON INC. (SEH) WILL REVIEW THE GENERAL CONTRACTOR'S (GC) SHOP DRAWINGS AND RELATED SUBMITTALS (AS INDICATED BELOW) WITH RESPECT TO THE ABILITY OF THE DETAILED WORK, WHEN COMPLETE, TO BE A PROPERLY FUNCTIONING INTEGRAL ELEMENT OF THE OVERALL STRUCTURAL SYSTEM DESIGNED BY SEH.
2. PRIOR TO SUBMITTAL OF A SHOP DRAWING OR ANY RELATED MATERIAL TO SEH, THE GC SHALL:
- REVIEW EACH SUBMISSION FOR CONFORMANCE WITH THE MEANS, METHODS, TECHNIQUES, SEQUENCES AND OPERATIONS OF CONSTRUCTION AND SAFETY PRECAUTIONS AND PROGRAMS INCIDENTAL THERETO, ALL OF WHICH ARE THE SOLE RESPONSIBILITY OF THE GC.
- REVIEW AND APPROVE EACH SUBMISSION.
- STAMP EACH SUBMISSION AS APPROVED.
3. SEH SHALL ASSUME THAT NO SUBMISSION COMPRISES A VARIATION FROM THE CONTRACT DOCUMENTS UNLESS THE GC ADVISES SEH WITH WRITTEN DOCUMENTATION. SHOP DRAWINGS AND RELATED MATERIAL (IF ANY) REQUIRED ARE INDICATED BELOW. SHOULD SEH REQUIRE MORE THAN TEN (10) WORKING DAYS TO PERFORM THE REVIEW, SEH SHALL SO NOTIFY THE GC. SUBMITTALS SHALL INCLUDE:
- CONCRETE MIX DESIGNS AND MATERIAL CERTIFICATES INCLUDING ADMIXTURES AND COMPOUNDS APPLIED TO THE CONCRETE AFTER PLACEMENT.
- AGGREGATE TESTS AND CONCRETE TEST HISTORY FOR EACH MIX DESIGN, WITH THE SUBMISSION OF CONCRETE MIX DESIGNS.
- REINFORCING STEEL SHOP DRAWINGS INCLUDING ERECTION DRAWINGS AND BENDING DETAILS. BAR LIST WILL NOT BE REVIEWED FOR CORRECT QUANTITIES.
- ELEVATIONS OF ALL REINFORCED CONCRETE MASONRY WALLS AND ALL CONCRETE WALLS WITH FOOTING STEPS OR OTHER ELEVATION CHANGES, AT A SCALE NO SMALLER THAN 1/8" = 1'-0" SHOWING ALL REQUIRED REINFORCING.
- PILE LENGTH DESIGN.
- SEH SHALL REVIEW SHOP DRAWINGS AND RELATED MATERIALS WITH COMMENTS PROVIDED THAT EACH SUBMISSION HAS MET THE ABOVE REQUIREMENTS. SEH SHALL RETURN WITHOUT COMMENT UNREQUIRED MATERIAL OR SUBMISSIONS WITHOUT GC APPROVAL STAMP.

SPECIAL INSPECTION

Table with 5 columns: DESCRIPTION, TESTING (YES, NO), INSPECTING (YES, NO), NA. Rows for METAL CONSTRUCTION, CONCRETE CONSTRUCTION, MASONRY CONSTRUCTION, WOOD CONSTRUCTION, GRADING, EXCAVATION AND FILLING, PILING, PIERS AND CAISSONS.

- A. SPECIAL INSPECTIONS IN ACCORDANCE WITH IBC CHAPTER 17 SHALL BE PERFORMED.

ABBREVIATIONS

Table with 2 columns: ABBREVIATIONS, ABBREVIATIONS. Rows: ADDL, ADH, ADJ, AL, APPROX.

Table with 2 columns: ABBREVIATIONS, ABBREVIATIONS. Rows: B/, BLDG, BOT, BRG, BTWN.

Table with 2 columns: ABBREVIATIONS, ABBREVIATIONS. Rows: CJ, CL, CLR, CMU, COL.

Table with 2 columns: ABBREVIATIONS, ABBREVIATIONS. Rows: CONC., CONSTR., CONT., CTR, DEG.

Table with 2 columns: ABBREVIATIONS, ABBREVIATIONS. Rows: DIA, DWG, DWL, E, EF.

Table with 2 columns: ABBREVIATIONS, ABBREVIATIONS. Rows: EL, ENCL., EQ. SP., EQUIP., EQW.

Table with 2 columns: ABBREVIATIONS, ABBREVIATIONS. Rows: EX., EXP., F.F., FFE, F.D.

Table with 2 columns: ABBREVIATIONS, ABBREVIATIONS. Rows: FRP, FT, FIG, GALV., GND.

Table with 2 columns: ABBREVIATIONS, ABBREVIATIONS. Rows: H.C., HGT, HORIZ., H.P., I.D.

ABBREVIATIONS

Table with 2 columns: ABBREVIATIONS, ABBREVIATIONS. Rows: INV. EL., ISF, LB, L.P., LVL.

Table with 2 columns: ABBREVIATIONS, ABBREVIATIONS. Rows: LVR, MATL, MAX., MECH., MIN.

Table with 2 columns: ABBREVIATIONS, ABBREVIATIONS. Rows: N, N/A, N.T.S., O.C., O.D.

Table with 2 columns: ABBREVIATIONS, ABBREVIATIONS. Rows: OPNG, OSF, PL, PSF, REINF.

Table with 2 columns: ABBREVIATIONS, ABBREVIATIONS. Rows: S, SER, SIM., SPEC., SQ, S.S.

Table with 2 columns: ABBREVIATIONS, ABBREVIATIONS. Rows: STD, STL, STRUCT, T&B, T.O.

Table with 2 columns: ABBREVIATIONS, ABBREVIATIONS. Rows: TYP., U.N.O., VERT., W, W/.

Table with 2 columns: ABBREVIATIONS, ABBREVIATIONS. Rows: W/O, WS.

S:\FV\F05\JL12912917-5-fmrd-dwg-51-const-dwg-CAD\20-Struct\Contract A 33.dwg 10/15/2014 9:11 Am jlburns

Table with 4 columns: DRAWN BY, DESIGNER, CHECKED BY, DESIGN TEAM. Rows: JMB, JMB, MLH, DESIGN TEAM.



I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.
Michael L. Hemstad
MICHAEL L. HEMSTAD, PE
Date: OCTOBER 17, 2014 Lic. No. 19165



PLATFORM PLANS
CONTRACT 'A'
SPIRIT MOUNTAIN
DULUTH, MN

GENERAL STRUCTURAL NOTES

Table with 2 columns: FILE NO., S3, 30. Rows: FOSJJ129137, S3, 30.