PLAN LEGEND RIGHT OF WAY LINE DITCH CENTERLINE FENCE LINE RETAINING WALL GRAVEL LINE GUARD RAIL LINE ROAD CENTERLINE TREE LINE STREAM LINE WETLAND LINE EX SANITARY LINE PR SANITARY LINE AB SANITARY LINE EX FORCEMAIN LINE PR FORCEMAIN LINE AB FORCEMAIN LINE EX STORM LINE PR STORM LINE AB STORM LINE EX WATER LINE PR WATER LINE AB WATER LINE EX GAS LINE PR GAS LINE AB GAS LINE EX STEAM LINE EX STEAM LINE UG CABLE TV LINE AB CABLE TV LINE UG ELECTRIC LINE AB ELECTRIC LINE UG FIBEROPTIC LINE AB FIBEROPTIC LINE UG TELEPHONE LINE AB TELEPHONE LINE OH ELECTRIC LINE OH TELEPHONE LINE OH CABLE TV LINE

SYMBOLS

EX SANITARY MANHOLE
EX SANITARY CLEANOUT
EX STORM MANHOLE
EX STORM CATCHBASIN
EX. WATER MANHOLE
EX. WATER WALVE
EX. WATER HYDRANT
EX. WATER SHUTOFF
EX. WATER & GAS MH
EX. GAS MANHOLE
EX. GAS WALVE
EX. GAS SHUTOFF

EX. STEAM MANHOLE
EX. TELEPHONE MANHOLE
EX. ELECTRIC MANHOLE
EX. POWERPOLE
EX. LIGHT POLE

EX. ELECTRIC VAULT
EX. ANCHOR
EX. ELECTRIC TRANSFORMER
EX. STREET LIGHT
EX. SIGNAL W/ STREET LIGHT

EX. SIGNAL W/ STREET LIGHT
EX. HANDHOLE
EX. HANDHOLE
EX. TELEPHONE PEDESTAL

EX. TELEPHONE PEDESTA
EX. WELL
BENCHMARK
FOUND CI MONUMENT

EX. SIGN CONTROL POINT EX DECIDUOUS TREE

EX DECIDUOUS TREE
EX CONIFEROUS TREE
EX. PARKING METER

EX. SOIL BORING

 \Rightarrow

SB#: ??

PROJECT LOCATION

SEC. 1 T50N R15W &

SEC. 12 T50N R15W

ST. LOUIS COUNTY


CITY OF DUILLITH

CITY OF DULUTH

DEPARTMENT OF PUBLIC WORKS AND UTILITIES ENGINEERING DIVISION

CONSTRUCTION PLANS FOR:

GAS MAIN INSTALLATION FOR CIRRUS EXPANSION



GOVERNING SPECIFICATIONS

THE 2016 EDITION OF THE MINNESOTA DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR CONSTRUCTION" SHALL GOVERN. AVAILABLE AT: http://www.dot.state.mn.us/pre-letting/spec/index.html

THE 2016 EDITION OF THE CITY OF DULUTH PUBLIC WORKS AND UTILITIES DEPARTMENT CONSTRUCTION STANDARDS AND SUPPLEMENTS OR ADDENDUMS SHALL APPLY.

AVAILABLE AT:

http://www.duluthmn.gov/engineering/standard-construction-specifications/

THE SUBSURFACE UTILITY INFORMATION IN THIS PLAN IS UTILITY LEVEL D.
THIS QUALITY LEVEL WAS DETERMINED ACCORDING TO THE GUIDELINES OF CI/ASCE
38-02, ENTITLED "STANDARD GUIDELINES FOR THE COLLECTION AND DEPICTION OF
EXISTING SUBSURFACE UTILITY DATA".

WARNING:

LOCATION OF UNDERGROUND UTILITIES TO BE VERIFIED BY CONTRACTOR. CALL BEFORE DIGGING. GOPHER STATE ONE CALL 1-800-252-1166 REQUIRED BY LAW

<u>INDEX</u>

1 TITLE SHEET 2-4 SWPPP 5-7 EROSION CONTROL PLAN SHEETS 8 TRAFFIC CONTROL 9 PLAN & PROFILE SHEET LAYOUT OVERVIEW 10-11 CONSTRUCTION DETAILS 12 GAS CONNECTION DETAILS 13-26 PLAN & PROFILE SHEETS	SHEET NO.	DESCRIPTION	
	5-7 8 9 10-11 12	SWPPP EROSION CONTROL PLAN SHEETS TRAFFIC CONTROL PLAN & PROFILE SHEET LAYOUT OVERVIEW CONSTRUCTION DETAILS GAS CONNECTION DETAILS	

THIS PLAN CONTAINS 26 SHEETS

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

TIM A. SANDERS, P.E.

PROJECT ENGINEER (TYPED OR PRINTED NAME)

Tim A Sandwe 7/8/16 50401
PROJECT ENGINEER DATE LIC. NO.

CITY APPROVAL

APPROVED CHIEF ENGINEER OF TRANSPORTATION DATE

APPROVED CHIEF ENGINEER OF UTILITIES DATE

APPROVED CHIEF ENGINEER OF UTILITIES

APPROVED SHENGINES

7-8-16

CITY OF DULUTH PROJECT NO.

. 1551

DRAWN BY: KLM

SHEET NO. 1

OF **26**

EROSION CONTROL NOTES

- MNDOT STANDARD SPECIFICATIONS FOR CONSTRUCTION SHALL APPLY. ALONG WITH THE (A.) CITY OF DULUTH OR (B.) DEVELOPER, THE CONTRACTOR WILL BE CO-PERMITEE FOR THE MPCA NPDES STORM WATER CONSTRUCTION PERMIT FOR THIS PROJECT - CONTRACTORS SIGNATURE ON PERMIT IS REQUIRED.
- SUBMIT INITIAL EROSION CONTROL (EC) SCHEDULE AT OR BEFORE THE PRECONSTRUCTION CONFERENCE.
- SUBMIT EC SCHEDULE ALTERATIONS/ADJUSTMENTS WEEKLY THEREAFTER FOR ENGINEER'S APPROVAL.
- 2. THE CONTRACTOR IS RESPONSIBLE FOR EROSION CONTROL QUALITY CONTROL (WC) ON THIS PROJECT. CONTRACTOR SHALL PHASE/SEQUENCE THE PROJECT TO MINIMIZE EXPOSURE TO EROSION. CONTRACTOR SHALL PLACE OR OTHERWISE CONSTRUCT EROSION CONTROL AND SEDIMENT CONTAINMENT DEVICES TO MINIMIZE THE RUNOFF, TRACKING, AND SEDIMENT LOSS FROM DISTURBED AREAS OF THE PROJECT SITE.
- DISTURBED SLOPES NOT ACTIVELY WORKED SHALL BE PROTECTED FROM SOIL EROSION WITH TEMPORARY OR PERMANENT COVER WITHIN 3 DAYS OF BEING WORKED. EROSION CONTROL BLANKET AND SOIL STAPLES SHALL BE USED.
- AT MINIMUM, THE FOLLOWING CONTROLS WILL BE IMPLEMENTED AT THE CONSTRUCTION SITE:
- EROSION CONTROL BLANKETS SHALL BE USED ON ALL SLOPES 1:3 OR STEEPER
- SILT FENCES SHALL BE USED IN CONJUNCTION WITH OTHER EROSION BMPS
- ROCK DITCH CHECKS OR APPROVED EQUAL ARE TO BE USED TO REDUCE DITCH VELOCITIES AND REDUCE EROSION
- STORM INLET AND OUTLET AREAS SHALL BE CONTINUOUSLY PROTECTED WITH MNDOT APPROVED DEVICES/METHODS
- STABILIZED CONSTRUCTION ENTRANCE, OR REUSABLE MUD MAT SHALL BE USED TO REDUCE SEDIMENT TRACKING
- 4.6. PERMANENT VEGETATION WILL BE ESTABLISHED RIGHT AFTER TOPSOIL IS SPREAD
- CONTROL ALL SITE SOLID WASTE, DEBRIS, MATERIAL STORAGE AND CONCRETE WASHOUT ON SITE. NO MIGRATION OFFSITE OR INTO DITCHES/STORM SYSTEMS PERMITTED
- ALL SLOPES AND DITCHES SHALL BE STABILIZED PRIOR TO OPENING NEW CULVERTS INTO EXISTING DRAINAGE WAYS.

 IF ANY STOCKPILE IS TO REMAIN IN PLACE FOR MORE THAN 3 DAYS SEDIMENT AND EROSION CONTROL DEVICES SHALL BE
- WATER PUMPED OR OTHERWISE DISCHARGED FROM THE SITE DURING CONSTRUCTION DEWATERING SHALL BE DIRECTED THROUGH EFFECTIVE FILTERING DEVICE(S) IN ACCORDANCE WITH MNDOT SPECIFICATION 2573. USE OF APPROVED FLOCCULANT MAY BE NECESSARY.
- THE CONTRACTOR SHALL TAKE ALL POSSIBLE PRECAUTIONS TO PREVENT APPRECIABLE SOIL TRACKING ONTO ROADWAYS. APPRECIABLE SOIL, MUD, OR DEBRIS WASHED, TRACKED, OR DEPOSITED ONTO PAVED SURFACES SHALL BE REMOVED PRIOR TO THE END OF EACH WORK DAY
- STABILIZED CONSTRUCTION ENTRANCE(S) SHALL BE REMOVED AND AREA RESTORED AFTER GRADING IS COMPLETE.
- THE CONTRACTOR QC PROGRAM SHALL ENSURE THAT A COMPETENT INDIVIDUAL SHALL INSPECT EROSION AND SEDIMENT CONTROL DEVICES WEEKLY AND AFTER EACH RAIN EVENT. ALL NONFUNCTIONAL DEVICES SHALL BE REPAIRED/REPLACED/CLEANED. MAINTAIN WRITTEN LOG OF ALL WEEKLY AND RAIN EVENT INSPECTIONS — INCLUDE THE CORRECTIVE ACTIONS THAT WERE TAKEN.
- 11. THE CONTRACTOR SHALL MAINTAIN THE CAPABILITY TO IMPLEMENT RAPID STABILIZATION METHOD 4 (MNDOT 2573.4) AT ALL TIMES. INCLUDES CAT III EROSION CONTROL BLANKED (ECB) [N. AMERICAN GREEN \$150 OR APPROVED EQUAL] ALONG WITH SEED MIXTURE, FERTILIZER, AND SOIL STAPLES PER 2573-3. THE UPGRADE END OF EACH BLANKET STRÍP SHALL BE BURIED AT LEAST 6 INCHES IN A VERTICAL CHECK SLOT. STAPLES SHALL BE PLACED AT SEAMS AND THROUGHOUT THE BLANKET AT A MAXIMUM SPACING IN ALL DIRECTIONS OF 2 FEET. PAYMENT ALLOWED SHALL BE PER CONTRACT OR IN ABSENCE OF CONTRACT BID PRICE IN ACCORDANCE WITH MNDOT SPECIFICATION 2575.5
- THE CONTRACTOR SHALL BE PROACTIVE IN THEIR APPROACH TO MINIMIZING SOIL EROSION AND SEDIMENT TRANSPORT FROM THE SITE. CURRENT TECHNOLOGY FOR WEATHER FORECASTING AND WEATHER RADAR ALLOWS FOR THE CONTRACTOR TO HAVE EROSION CONTROL BMPS INSTALLED AND FUNCTIONING FOR A RAIN EVENT. ALL CONSTRUCTION SITES SHALL BE PREPARED FOR A RAIN EVENT DURING NON-WORK TIMES, I.E. WEEK NIGHTS AND WEEKENDS.
- AS SITE CONDITIONS CHANGE, THE WORK PROGRESSES AND WEATHER CONDITIONS VARY, THE CONTRACTOR SHALL BE REACTIVE TO THESE CHANGING VARIABLES.. THEREFORE BMP INSTALLATION, CLEANING AND RELOCATION SHOULD BE ANTICIPATED IN MOST CONSTRUCTION ACTIVITIES.

CONSTRUCTION PRACTICES TO MINIMIZE STORM WATER CONTAMINATION

TO PREVENT STORM WATER CONTAMINATION FROM OCCURRING, THE FOLLOWING BMPS WILL BE IMPLEMENTED:

- ALL AREAS THAT ARE ROUGH GRADED MUST BE KEPT IN A SMOOTH CONDITION TO ALLOW SHEET FLOW OF STORM WATER WHEREVER PRACTICAL AND ALWAYS READY FOR SURFACE APPLICATION OF DEGRADABLE OR NON-DEGRADABLE BLANKETS, MULCH, OR OTHER PROTECTIVE COVERS.
- 2. A STABILIZED CONSTRUCTION ENTRANCE/EXIT WILL BE CONSTRUCTED TO REDUCE VEHICLE TRACKING OF SEDIMENTS OFF THE PROJECT RIGHT OF WAY.
- ALL SOLID WASTE MATERIALS WILL BE COLLECTED AND STORED IN A SECURELY LIDDED METAL DUMPSTER OR OTHER APPROVED CONTAINMENT METHOD AT THE END OF EACH DAY. ANY ALTERNATIVE TO A METAL DUMPSTER MUST BE SUBMITTED IN WRITING FOR APPROVAL BY THE PROJECT ENGINEER. ALL TRASH AND CONSTRUCTION DEBRIS FROM THE SITE WILL BE DEPOSITED IN THE DUMPSTER. THE DUMPSTER WILL BE EMPTIED AS NECESSARY TO FUNCTION AS INTENDED FOR DEBRIS COLLECTION. NO CONSTRUCTION MATERIALS WILL BE BURIED ON-SITE. THE CONTRACTOR'S EROSION CONTROL SUPERVISOR WILL INSTRUCT ALL PERSONNEL REGARDING THE CORRECT PROCEDURE FOR DISPOSAL.
- RECYCLABLE MATERIALS MUST BE SEPARATED ON-SITE AND SEGREGATED IN DESIGNATED CONTAINERS.
- A LICENSED SANITARY WASTE MANAGEMENT CONTRACTOR WILL COLLECT ALL SANITARY WASTE FROM THE PORTABLE UNITS AT A RATE NECESSARY TO MAINTAIN DESIGNED FUNCTION.
- ALL VEHICLES ON SITE WILL BE MONITORED FOR LEAKS AND RECEIVE REGULAR PREVENTIVE MAINTENANCE TO REDUCE THE CHANCE OF LEAKAGE.
- FERTILIZERS WILL BE STORED IN A COVERED SHED AND PARTIALLY USED BAGS WILL BE TRANSFERRED TO A SEALABLE BIN TO REDUCE THE CHANCE OF SPILLAGE.
- PETROLEUM PRODUCTS WILL BE STORED IN TIGHTLY SEALED CONTAINERS, WHICH ARE CLEARLY LABELED.
- SPILL KITS WILL BE INCLUDED WITH ALL FUELING SOURCES AND MAINTENANCE ACTIVITIES. SECONDARY CONTAINMENT MEASURES WILL BE INSTALLED AND MAINTAINED BY THE CONTRACTOR.
- 10. ANY ASPHALT SUBSTANCES USED ON SITE WILL BE APPLIED IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS.
- ALL PAINT CONTAINERS AND CURING COMPOUNDS WILL BE TIGHTLY SEALED AND STORED WHEN NOT REQUIRED FOR USE. EXCESS PAINT WILL NOT BE DISCHARGED TO THE STORM WATER SYSTEM BUT WILL BE PROPERLY DISPOSED OF ACCORDING TO MANUFACTURER'S INSTRUCTION.
- 12. MATERIALS AND EQUIPMENT NECESSARY FOR SPILL CLEAN-UP SHALL BE READILY AVAILABLE AND BE KEPT IN AN ENCLOSED TRAILER OR SHED ON SITE. EQUIPMENT WILL INCLUDE, BUT NOT LIMITED TO, BROOMS, MOPS, DUST PANS, RAGS, GLOVES, GOGGLES, ABSORBENT (KITTY LITTER, OIL ABSORBENT BOOMS AND DIAPERS) AND BUCKETS.
- 13. ALL SPILLS WILL BE CONTAINED AND CLEANED UP IMMEDIATELY UPON DISCOVERY. SPILLS LARGE ENOUGH TO REACH THE STORM WATER CONVEYANCE SYSTEM WILL BE REPORTED TO THE MINNESOTA DUTY OFFICER AT 1-800-422-0798.
- 14. CONCRETE TRUCKS WILL NOT BE ALLOWED TO WASH OUT OR DISCHARGE SURPLUS CONCRETE OR DRUM WASH WATER THE SITE UNLESS DONE IN AN ENGINEERED CONTAINMENT SYSTEM. THE ENGINEERED SYSTEM MUST INCLUDE SITE DRAWINGS FOR THE PROJECT FILE AND WRITTEN ASSURANCE THAT THE SYSTEM WILL WORK AS DESIGNED AND LEAVE NO DISCHARGE OF CONCRETE OR CONCRETE RESIDUE POTENTIAL TO ENTER WATERS OF THE STATE.
- 15. FORM RELEASE OIL USED FOR CONCRETE WORK MUST BE APPLIED OVER A PALLET CONTAINING ABSORBENT TO COLLECT EXCESS LIQUID. THE ABSORBENT MATERIAL WILL BE REPLACED AND PROPERLY DISPOSED OF WHEN SATURATED.
- 16. DISCHARGES FROM BASIN DEWATERING OPERATIONS THAT ARE TURBID OR SEDIMENT LADEN SHALL BE DISCHARGED TO TEMPORARY SEDIMENT BASINS CONSTRUCTED ON THE SITE TO PROVIDE TREATMENT PRIOR TO DISCHARGE TO A WATER OF THE STATE.

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

DATE: JULY 8, 2016

DULUTH

CITY OF DULUTH **ENGINEERING DIVISION** 411 W. 1ST ST. STE. 211 DULUTH, MN 55802

GAS MAIN INSTALLATION FOR CIRRUS EXPANSION CITY PROJECT NO .:

STATE AID PROJECT NO .:

N/A

DRAWN BY: KLM **SWPPP**

SHEET NO. 2 OF

TIM A. SANDERS, P.E. LIC. NO:___ TYPE NAME

NPDES STORM WATER POLLUTION PREVENTION PLAN (SWPPP)

THE PROJECT WILL RECONSTRUCT EXISTING CITY STREETS AND ASSOCIATED INFRASTRUCTURE INCLUDING:

1.1. GRADING AND EXCAVATION

1.2. TRENCHING FOR NEW AND RECONSTRUCTED UTILITIES

1.3. NEW CURB AND GUTTER

1.4. NEW BITUMINOUS AND CONCRETE PAVEMENT

1.5. TURF ESTABLISHMENT.

2. THE TOTAL LAND AREA ANTICIPATED TO BE DISTURBED BY THE PROJECT (EXCLUSIVE OF BORROW AND DISPOSAL AREAS) IS 0.1 ACRES.

CONSTRUCTION DATES ARE ESTIMATED TO BE FROM JUNE 29, 2015 TO NOVEMBER 1, 2015.

- 4. THE RECEIVING WATER FOR STORM WATER FROM THE PROJECT INCLUDES EXISTING STORM SEWER SYSTEMS LEADING TO MILLER CREEK AND LAKE SUPERIOR.
- CITY OF DULUTH MAINTENANCE IS RESPONSIBLE FOR LONG TERM OPERATION AND MAINTENANCE OF THE STORM WATER SYSTEM.

6. CONTACTS:

OWNER & RECORDS RETENTION: CITY OF DULUTH ENGINEERING DEPARTMENT 211 CITY HALL DULUTH, MN 55802

THE CITY OF DULUTH PROJECT ENGINEER IS: TIM A. SANDERS

PROJECT ENGINEER
211 CITY HALL
DULUTH, MN 55802
(218) 730-5066
tsanders@duluthmn.gov

TIMING OF BMP INSTALLATION

(218) 730-5200

- 1. THE EROSION AND SEDIMENTATION CONTROL BMPS SHALL BE INSTALLED AS NECESSARY TO MINIMIZE EROSION FROM DISTURBED SURFACES AND CAPTURE SEDIMENT ON SITE, AND SHALL MEET THE NPDES PERMIT PART IV CONSTRUCTION ACTIVITY REQUIREMENTS.
- 2. TEMPORARY PERIMETER CONTROL BMPs WILL BE INSTALLED BEFORE ANY UP GRADIENT SOIL DISTURBANCE OCCURS.
- PERMANENT AND TEMPORARY SEDIMENT TRAPS AND BASINS (IF APPLICABLE) WILL BE CONSTRUCTED BEFORE ANY CONVEYANCE OR DEWATERING OCCURS.
- 4. TOPSOIL AND TEMPORARY EROSION CONTROL BMPs SHALL BE PLACED WITHIN 3 DAYS OF COMPLETION OF EMBANKMENT
- 5. PLACEMENT OF RIPRAP SHALL BE COMPLETED WITHIN 24 HOURS OF CULVERT PLACEMENTS AND DONE IN ONE CONTINUOUS OPERATION.
- ONCE CONSTRUCTION ACTIVITY CEASES FOR <u>3</u> DAYS OR MORE IN AN AREA, THAT AREA WILL BE STABILIZED WITH TEMPORARY OR PERMANENT BMPS FOR EROSION.

CALCULATIONS

TOTAL PROJECT AREA = 1.0 ACRES

DISTURBED AREA = 0.1 ACRES

POST CONSTRUCTION IMPERVIOUS AREA = 0.01 ACRES

EXISTING IMPERVIOUS AREA = 0.01 ACRES

IMPERVIOUS NET = 0.0 ACRES (INCREASE/DECREASE)
SOILS INFORMATION: N/A

CONSTRUCTION NOTES

- CONSTRUCTION SHALL BE GOVERNED BY THE MNDOT STANDARD SPECIFICATIONS, CITY OF DULUTH STANDARD CONSTRUCTION SPECIFICATIONS AND SPECIAL PROVISIONS.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR IMPLEMENTATION OF THE SWPPP AND THE INSTALLATION, INSPECTION, AND
 MAINTENANCE OF THE EROSION AND SEDIMENT CONTROL BMPS BEFORE AND DURING CONSTRUCTION.
- THE CONTRACTOR SHALL KEEP WRITTEN INSPECTION AND MAINTENANCE LOGS (INCLUDING ALL CLEAN OUT AND CORRECTIVE ACTIONS) IN ACCORDANCE WITH THIS SWPPP AND ALL PERMITS.

TMDL IMPLEMENTATION PLANS CONTAINING STORM WATER REQUIREMENTS

NO TMDL IMPLEMENTATION PLANS CURRENTLY EXIST FOR THE RECEIVING WATERS ON THIS PROJECT.
THE ST. LOUIS RIVER IS LOCATED ?? MILES FROM THE PROJECT AND IS AN MPCA LISTED IMPAIRED WATER.

LOCATION OF SWPPP REQUIREM	FNTS IN PROJECT	ΓΡΙΔΝ	
Land Control of Contro			
DESCRIPTION	TITLE	LOCATION	
SUMMERY OF PERVIOUS & IMPERVIOUS	SWPPP	SHEET 3	
DIRECTION OF FLOW/DRAINAGE AREA	N/A	N/A	
RECEIVING SURFACE WATERS	SWPPP	SHEET 3	
NO DISTURBANCE AREAS & AREAS OF CONSTRUCTION	SWPPP	SHEET 3	
DRAINAGE STRUCTURES	EROSION CONTROL	SHEETS 5-7	
DRAINAGE TABULATIONS	N/A	N/A	
EROSION CONTROL TABULATIONS	N/A	N/A	
EROSION CONTROL SHEETS	EROSION CONTROL	SHEETS 5-6	
EROSION CONTROL DETAILS	EROSION CONTROL	SHEET 7	
SEDIMENT CONTROL PRACTICES	SWPPP	SHEETS 2-3	
FINAL STABILIZATION	N/A	N/A	
SEDIMENT BASIN (POND) TABULATIONS	N/A	N/A	
POND SHEETS (SEDIMENT BASINS)	N/A	N/A	
LOCATION OF PONDS	N/A	N/A	

SWPPP IMPLEMENTATION CONTACTS								
AGENCY	PERMIT	NAME	PHONE/E-MAIL					
CONTRACTOR'S EROSION CONTROL SUPERVISOR		TO BE DETERMINED	TBD					
MPCA	NPDES	JIM DEXTER	(218)529-6253 james.dexter@pcs.state.mn.us					
SWCD	WCA	RC BOHEIM	(218)723-4629 RC.Boheim@southstlouisswcd.org					
MNDNR WATERS AREA HYDROLOGIST	N/A	PATRICIA FOWLER	(218)834-6621 patricia.fowler@dnr.state.mn.us					
CORPS OF ENGINEERS	SECTION 404	DARYL WIERZBINSKI	218-834-6630 daryl.w.wierzbinski@mvp02.usa.ce.army.mil					
STATE DUTY OFFICER	N/A	MPCA	800-422-0798					
CITY REVIEW	N/A	TOM JOHNSON	(218) 730-5103 tajohnson@duluthmn.gov					
LGU-CITY OF DULUTH	N/A	KYLE DEMING	(218)730-5580 kdeming@duluthmn.gov					
CITY OF DULUTH SOLID WASTE OFFICER	N/A	KAREN ODONNELL	(218)730-5148 kodennell@duluthmn.gov					

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.


SIGNATURE: Tim A. Sandur

TIM A. SANDERS, P.E.
TYPE NAME


DATE: <u>JULY 8, 2016</u> LIC. NO: 50401 DULUT)

CITY OF DULUTH ENGINEERING DIVISION 411 W. 1ST ST. STE. 211 DULUTH, MN 55802

	CAS MAIN INSTALLA	TION FOR CIRRUS EXPANSION		DRAWN BY:	KLM	
	OAS MAIN INSTALLA	TION TON CIRROS EXPANSION		SWPPP		
CITY PROJECT NO.:	1551	STATE AID PROJECT NO.:	N/A	SHEET NO. 3	OF 26	



DISTRURBED SOIL, WORK AREA DRAINS TO STREAM





MAINTENANCE REQUIRED: FOLLOWING EACH RUNOFF EVENT, MONITOR AND. IF NECESSARY, REMOVE ALL ACCUMULATED SEDIMENT & DEBRIS FROM THE UNIT AFTER THE HEIGHT OF THE ACCUMULATED MATERIAL REACHES 1/3 OF THE HEIGHT OF THE SEDIMENT BAG.


INLET PROTECTION CATCH BASIN SEDIMENT BAG INSERT TYPE DETAIL

NO SCALE


I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.	DATE:JULY 8, 2016	CITY OF DULUTH		GAS MAIN INSTALL	ATION FOR CIRRUS EXPANSION		DRAWN BY: KLM
SIGNATURE: TIM A. SANDERS, P.E.	LIC. NO: 50401	THE CITY OF ALL W ACT CT CTE 214		OAS MAIN INSTALL	ATION FOR CIRROS EXPANSION		SWPPP
TYPE NAME	LIC. NO	DULUTH DULUTH, MN 55802	CITY PROJECT NO.:	1551	STATE AID PROJECT NO:	N/A	SHFFT NO. 4 OF 26










SHEET NO. 7 OF







- ENCASEMENT ZONE MATERIAL SHALL BE COMPACTED TO 95% OF MAXIMUM STANDARD PROCTOR DENSITY.
- BACKFILL SHALL BE SELECT GRADING MATERIAL FOUND ON-SITE WHEN DEEMED SUITABLE BY THE ENGINEER OR AS OTHERWISE DEFINED IN THE PROJECT SPECIAL PROVISIONS. WHEN ON-SITE MATERIAL IS NOT SUITABLE AND WHEN BACKFILL MATERIAL IS NOT SPECIFIED, IMPORTED MATERIAL MEETING MN/DOT 3149.2.D.1 GRANULAR BACKFILL SHALL BE PROVIDED. USE OF NATIVE ON-SITE MATERIAL IS INCIDENTAL.
- COMPACT BACKFILL MATERIALS TO 100% OF MAXIMUM STANDARD PROCTOR DENSITY FOR THE UPPER 3' BELOW THE SUBGRADE, AND TO 95% OF MAXIMUM STANDARD PROCTOR DENSITY BELOW THE UPPER 3'.



ALL	STEEL	&	4"	AND	LARGER	PE	GAS	MAIN	BEDDING	DETAIL
ALL	JILLL	<u> </u>	Т.	AND	DAINOLIN		0/13	IAIN VILLA	DEDDINO	DEIAIL

REVISED/APPROVED 1/8/2016

CITY OF DULUTH STANDARD DETAIL DEPT. OF PUBLIC WORKS AND UTILITIES

NO SCALE

REVISED/APPROVED 1/8/2016

CITY OF DULUTH STANDARD DETAIL DEPT. OF PUBLIC WORKS AND UTILITIES

NO SCALE

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER_UNDER THE LAWS OF THE STATE OF MINNESOTA. SIGNATURE: Tim A. Scholie

TIM A. SANDERS, P.E. TYPE NAME

LIC. NO: 50401

DATE: <u>JULY 8, 2016</u>

DULUTH

CITY OF DULUTH **ENGINEERING DIVISION** 411 W. 1ST ST. STE. 211 DULUTH, MN 55802

GAS MAIN INSTALLATION FOR CIRRUS EXPANSION CITY PROJECT NO .:


DRAWN BY: KLM CONSTRUCTION DETAILS

1551 STATE AID PROJECT NO .: N/A

STREET RESTORATION OVER TRENCH

SHEET NO. 10 OF

TYPICAL SECTION HAINES ROAD



ALL DITCH BOTTOMS AND TOPS OF BACKSLOPES ARE TO BE ROUNDED.

STATE AID PROJECT NO.:

TIM A. SANDERS, P.E.
TYPE NAME

DATE: __JULY 8, 2016

CITY OF DULUTH ENGINEERING DIVISION 411 W. 1ST ST. STE. 211 DULUTH, MN 55802

GAS MAIN INSTALLATION FOR CIRRUS EXPANSION CITY PROJECT NO .: 1551

CONSTRUCTION DETAILS N/A SHEET NO. 11 OF

DRAWN BY:

KLM

