



ADDENDUM #2

PHASE II of CITY STEAM TUNNEL INFRSTRUCTURE 092B  
PROJECT NUMBER 10-26B  
BID NUMBER 10-0154

The following addendum shall become part of the construction documents for the construction of the above referenced project. This addendum supersedes and supplements all previous reference to similar items.

CITY OF DULUTH PROJECT REQUIREMENTS

Add the following:

- A separate abatement contract will include removal of existing ACM-covered steam & condensate piping. This Contractor does not have to include removal of existing insulated steam & condensate piping. The abatement will leave the risers through the slab above in place, including the last fitting below the floor slab. All ACM covering will be removed.
- The following manufacturers and their products have been approved for substitution; however, such prior approval in no way relieves the supplier from complying in every respect with the requirements of the Bidding Documents:

Expansion Joints - Adsko

END OF ADDENDUM #2