



Purchasing Division
Finance Department
Room 120
411 West First Street
Duluth, Minnesota 55802

218-730-5340
purchasing@duluthmn.gov

Addendum 1
Solicitation 23-99392
2023 Street Preservation Project

This addendum serves to notify all bidders of the following changes to the solicitation documents:

1. CHANGES TO SPECIAL PROVISIONS:
 - a. Add SP-33 to project Special Provisions.

SP-33 (2301) DRILL AND GROUT REINFORCEMENT BAR (EPOXY COATED)

This work shall consist of drilling, grouting, and inserting No. 4 epoxy coated reinforcement bars as shown on the details in the Plan, on MnDOT Standard Plans 5-297.221, 5-297.250 and 5-297.254 included in plans and in accordance with the provisions of MnDOT 2301 and the following:

Furnish and install epoxy coated reinforcement bars. Anchor the reinforcement bars to the in-place concrete by utilizing either a non-shrink grout or epoxy adhesive from the approved products list.

MEASUREMENT AND PAYMENT

No Payment will be made for Item 2301.602 (Drill and Grout Reinforcement Bar (Epoxy Coated)). All costs will be incidental to each Pay Item where reinforcement bars are required.

See also page 5, line 15 of General Notes.

2. CHANGES TO DRAWINGS:
 - a. Sheet 5, line 20 Add to General Notes:

Contractor shall use Vac truck to clean all structures and pipes of eroded material and construction debris at end of the completion of each street. Visual inspection must be coordinated with Project Engineer or City Project Inspector before payment.

- b. Sheet 103 is deleted and replaced with sheet 103-REV 1. 103-REV 1 includes missing tab B-Excavating and Grading.

Please acknowledge receipt of this Addendum by checking the acknowledgment box within the www.bidexpress.com solicitation. Failure to acknowledge this addendum may disqualify your bid.

Posted: **May 5, 2023**

EXCAVATION AND GRADING				B
STATION TO STATION	LT / RT	SPEC. 2105	SPEC. 2118	REMARKS
		COMMON EXCAVATION	AGGREGATE SURFACING (CV) CLASS 5	
		CU YD	CU YD	
E. 4TH STREET				
107+91 TO 110+35	RT	35	26	SIDEWALK SHIFT
117+88 TO 119+88	LT	212		8" PERFORATED PIPE
SECTION SUBTOTAL		247	26	
36TH AVE E.				
202+63 TO 203+12	LT	8		5' X 4" CONC WALK
SECTION SUBTOTAL		8		
TOTAL		255	26	

MILLING & RECLAMATION								C
STATION TO STATION	LT / RT	SPEC. 2131	SPEC. 2215	SPEC. 2215	SPEC. 2232	SPEC. 2232	SPEC. 2232	REMARKS
		CALCIUM CHLORIDE SOLUTION	FULL DEPTH RECLAMATION	HAUL FULL DEPTH RECLAMATION (LV)	MILL BITUMINOUS SURFACE (1")	MILL BITUMINOUS SURFACE (2")	MILL BITUMINOUS SURFACE (4")	
		CU YD	SQ YD	CU YD	SQ YD	SQ YD	SQ YD	
E. 4TH STREET								
103+83 TO 107+05.7	C/L	324	1,201	50	1,201			RECLAMATION
107+65.7 TO 113+27	C/L						2,503	MILL
113+27 TO 120+60	C/L	924	3,421	30		3,421		RECLAMATION
120+60 TO 123+85	C/L	239	887	80				RECLAMATION
SECTION SUBTOTAL		1,487	5,509	160	1,201	3,421	2,503	
OLD HOWARD MILL RD								
123+85 TO 131+77	C/L	638	2,362	170				RECLAMATION
SECTION SUBTOTAL		638	2,362	170				
36TH AVE. E								
200+30 TO 204+09	C/L	186	690	60				RECLAMATION
SECTION SUBTOTAL		186	690	60				
TOTAL		2,311	8,561	390	1,201	3,421	2,503	

BITUMINOUS PAVEMENT					D
STATION TO STATION	LT / RT	SPEC. 2357	SPEC. 2360	SPEC. 2360	REMARKS
		BITUMINOUS MATERIAL FOR TACK COAT	TYPE SP 9.5 WEARING COURSE MIXTURE (3,B)	TYPE SP 9.5 WEARING COURSE MIXTURE (3,C)	
		GAL	TON	TON	
E. 4TH STREET					
103+83 TO 107+05.7	C/L	60		252	
107+65.7 TO 113+27	C/L	175	375		
113+27 TO 120+60	C/L	308		1026	
120+60 TO 123+85	C/L	44		186	
SECTION SUBTOTAL		587	375	1,464	
OLD HOWARD MILL RD					
123+85 TO 131+77	C/L	118		496	
SECTION SUBTOTAL		118		496	
36TH AVE. E					
200+30 TO 204+09	C/L	72		153	
SECTION SUBTOTAL		72		153	
TOTAL		777	375	2,113	

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

SIGNATURE: Patrick Loomis

PATRICK F. LOOMIS
TYPE NAME

DATE: 04/20/2023

LIC. NO: 49099



CITY OF DULUTH
ENGINEERING DIVISION
411 W. 1ST ST. STE. 240
DULUTH, MN 55802

2023 STREET PRESERVATION PROJECT

CITY PROJECT NO.: 2016

STATE AID PROJECT NO.: N/A

DRAWN BY: ZAE/DJK/SCA/NML

CONGDON PARK - TABULATIONS

SHEET NO 103-REV 1 OF 125