



Purchasing Division
Finance Department
Room 120
411 West First Street
Duluth, Minnesota 55802

218-730-5340
purchasing@duluthmn.gov

Addendum 1
Solicitation 23-99547
Canal Beach 2022 Storm Repairs

This addendum serves to notify all bidders of the following changes to the solicitation documents:

- The pre-bid meeting minutes are attached
- Questions for this project are due Tuesday, August 22nd with answers posted by Addendum no later than Thursday, August 24th.
- Bidders will need to be aware of scheduled Lakewalk events and will need to work around these dates
 - 9/16/23: Walk for Recover – Lakewalk from Leif to Canal Pier
 - 9/23/23: Heart Walk – Lakewalk from Leif to Canal Pier
 - 9/30/23: Grand Traverse – Lakewalk from Endion to Fitger's
 - 10/6/23: GIS Consortium Fun Run – Lakewalk from Endion to Fitger's
 - 11/11/23: Girls on the Run – Lakewalk from Leif to Canal Pier
- Revetment should follow the natural contour of eroded bank.
- Barrier stones next to the outfall will need to be adjusted, marked and placed in the same order as they are right now.

Please acknowledge receipt of this Addendum by checking the acknowledgment box within the www.bidexpress.com solicitation.

Posted: **August 21, 2023**



Consulting Engineers P.A.

August 15, 2023

Re: Canal Park State Disaster Area: Pre-Bid Meeting Minutes

AMI Project # 231016

Participants:

AMI – Ryan Dagger

City of Duluth – Lisa MacManus, Jim Shoberg, and Ted Blenkush

Veit – Jon Brostouitz and Andy Dammer

Northland Construction – David Eckstrom

Rachel Contracting – Mike Friend and Charles Belanger

Stack Brothers – Sam Boustead and Willie Stack

Meeting started at 10:00 am

Discussion Topics

- Construction Access
 - Land access will require use of the carriage path
 - AMI will submit the previous specifications for the gravel material, in the first addendum
- Beach Clean Up
 - The boundaries for the beach cleaning will be extended down to the revetment
 - Contractor must remove any blast rock, concrete, metal, geotextile fabric or misc. debris, 2 feet below grade, greater than 6-inches
 - Contractor must remove any non-native material greater than 6-inches discovered during the toe stone excavation
 - Contractor shall, to the best of their ability, remove small pieces of metal found along the beach during the duration of the project.
 - All stone removed from site becomes the responsibility of the contractor
- Due date for questions is the 22nd of August and answers are expected by August 24th
- All wood debris is to remain
- Contractor shall submit fencing layout for approval
- Contractor shall reinstall any of MnDOT's stones removed during the construction process
 - Stones must be placed back with three points of contact

Meeting ended at 10:45 am

This concludes my understanding of the items discussed during the meeting. If you have any questions or comments please contact AMI at (715) 718-5722.

Respectfully Submitted,

Ryan Dagger
Assistant Coastal Department Manager