

Bid # 10-0293

Project # 0838GS

8" Gas Main Replacement on Third Street from 8th Avenue E. to Lake Avenue
and on Mesaba Avenue from W. Third Street to W. First Street

Initial

EXHIBIT A - ADDENDUM NO. 1

Item No.	Spec. No.	Description	Unit	Est. Qty	Unit Price	Total Price
1	2021.501	MOBILIZATION	LUMP SUM	1		
2	2104.501	REMOVE CURB AND GUTTER	LIN FT	408		
3	2104.503	REMOVE 4" CONCRETE SIDEWALK	SQ FT	8395		
4	2104.503	REMOVE CONCRETE PAVEMENT/DRIVEWAY	SQ FT	540		
5	2104.505	REMOVE BITUMINOUS PAVEMENT	SQ YD	209		
6	2104.511	SAW CONCRETE - 4" DEPTH	LIN FT	204		
7	2104.511	SAW CONCRETE - FULL DEPTH	LIN FT	757		
8	2104.513	SAW BITUMINOUS PAVEMENT - 4" DEPTH	LIN FT	672		
9	2201.503	CONCRETE BASE , IRREGULAR WIDTH 8"	SQ YD	209		
10	2211.502	AGGREGATE BASE , CLASS 5 (LV)	CU YD	157		
11	2360.501	TYPE SP 9.5 WEARING COURSE MIXTURE (3.C)	TON	31		
12	2360.502	TYPE SP 12.5 NON-WEARING COURSE MIXTURE (3.C)	TON	42		
13	2451.503	GRANULAR BACKFILL (LV)	CU YD	125		
14	2105.503	BOULDER EXCAVATION (TRENCH)	CU YD	60		
15	2105.503	ROCK EXCAVATION (TRENCH)	CU YD	155		
16	2505.602	EXCAVATE AND INSULATE 6" P.E. GAS 8' LONG @ STEAM CROSSING	EACH	10		
17	2505.602	EXCAVATE AND INSULATE 8" P.E. GAS 8' LONG @ STEAM CROSSING	EACH	2		
18	2505.602	FURNISH & INSTALL 8" PE VALVE AND VALVE BOX	EACH	6		
19	2505.602	FURNISH & INSTALL 6" PE VALVE AND VALVE BOX	EACH	1		

20	2505.602	FURNISH & INSTALL 3" PE VALVE AND VALVE BOX	EACH	3		
21	2505.602	FURNISH & INSTALL 2" PE VALVE AND VALVE BOX	EACH	5		
22	2505.602	FURNISH & INSTALL 1" PE VALVE AND VALVE BOX	EACH	5		
23	2505.602	RECONNECT EXISTING 1/2" PE SERVICES TO NEW MAIN	EACH	9		
24	2505.602	RECONNECT EXISTING 1" PE SERVICES TO NEW MAIN	EACH	5		
25	2505.602	RECONNECT EXISTING 2" PE SERVICES TO NEW MAIN	EACH	2		
26	2505.602	EXCAVATION FOR CONNECTING NEW HP GAS SERVICE TO GAS MAIN	EACH	2		
27	2505.602	EXCAVATION FOR CONNECTING NEW HP GAS MAIN TO EXISTING GAS MAIN (W/O VALVE)	EACH	11		
28	2505.603	FURNISH & INSTALL 6" PE GAS MAIN WITH GRANULAR ENCASEMENT	LIN FT	85		
29	2505.603	FURNISH & INSTALL 6" PE GAS MAIN BY HORIZONTAL DIRECTIONAL DRILL	LIN FT	230		
30	2505.603	FURNISH & INSTALL 3" PE GAS MAIN OR SERVICE	LIN FT	30		
31	2505.603	FURNISH & INSTALL 2" PE GAS MAIN OR SERVICE	LIN FT	50		
32	2505.603	FURNISH & INSTALL 1" PE GAS MAIN OR SERVICE	LIN FT	80		
33	2505.603	FURNISH & INSTALL 1/2" PE GAS SERVICE	LIN FT	90		
34	2505.603	FURNISH & INSTALL 8" PE GAS MAIN BY HORIZONTAL DIRECTIONAL DRILL	LIN FT	2805		
35	2505.603	FURNISH & INSTALL 8" PE GAS MAIN WITH GRANULAR ENCASEMENT	LIN FT	1990		
36	2521.501	4" CONCRETE WALK (INCLUDES 4" C-5 BASE)	SQ FT	8395		
37	2521.501	6" CONCRETE WALK (INCLUDES 4" C-5 BASE)	SQ FT	1579		
38	2531.507	7" CONCRETE WALK (INCLUDES 12" C-5 BASE)	SQ FT	540		
39	2531.501	CONCRETE CURB AND GUTTER DESIGN B624	LIN FT	408		
40	2531.618	TRUNCATED DOMES	SQ FT	256		
41	2563.601	TRAFFIC CONTROL	LUMP SUM	1		
42	2575.505	SODDING TYPE LAWN	SQ YD	100		

GRAND TOTAL:

Initial