

## ITEM P-102 SAFETY AND SECURITY

### GENERAL

**102-1.1** The provisions of this safety and security plan and associated procedures are applicable within the boundaries of the **Duluth International Airport**. A complete understanding of all procedures and requirements contained herein is required to ensure safety during construction. This safety plan is a part of this Contract and deviations from the requirements established herein will be sufficient cause for Contract termination.

Required reference material associated with this safety plan includes:

FAA AC 150/5200-18[C], Airport Safety Self-Inspection  
FAA AC 150/5210-5 [C], Painting, Marking and Lighting of Vehicles Used on an Airport  
FAA AC 150/5370-2 [E], Operational Safety on Airports During Construction  
FAA AC 150/5370-12[A] Quality control of Construction for Airport Grant Projects

Copies of these documents are included in the specifications.

### CONTRACTOR SAFETY AND SECURITY OFFICER

**102-2.1 CONTRACTOR SAFETY AND SECURITY OFFICER (CSSO).** The Contractor shall appoint its on-site Construction Superintendent or other qualified individual(s) as its duly authorized representative to serve as Contractor Safety and Security Officer (CSSO) for the duration of the Contract. The CSSO shall thoroughly understand the safety and security requirements of the Contract, the necessity for them and shall have sufficient authority to implement its provisions without significant deviation. The Contractor shall notify the Engineer in writing of the name of the individual(s) selected for the assignment.

The CSSO shall represent the Contractor on safety and security requirements compliance. The CSSO shall be especially knowledgeable regarding the requirements of FAA AC's 150/5200-18, Airport Self Inspection Guide and 150/5370-2 Operational Safety on Airports During Construction, latest edition.

**102-2.2 RESPONSIBILITIES OF THE CONTRACTOR SAFETY AND SECURITY OFFICER.** Prior to the desired date for commencement of any work on the project, the CSSO shall accomplish the following:

**a.** Develop and submit in writing a detailed work sequence schedule with dates and times specified for all milestone events. This sequence schedule shall conform, as a minimum, to the events specified in Section 3.1, Construction Sequence, and shall be subject to the approval of the Engineer. To assure adequate time for coordination, this document shall be submitted at least one week prior to the date of the Preconstruction Conference.

**b.** Develop and submit in writing a detailed outline of the procedures to be followed to maintain safety and security of both Contractor operations and the integrity of airport landside and airside operations during the prosecution of contract work. This plan shall detail, in addition, the procedures to be followed in the event of an accident or fire involving Contractor personnel and the Contractor's efforts to maintain fire protection and security. These procedures shall be subject to the approval of the Engineer and reflect any change as may be deemed necessary.

**c.** Conduct at least one meeting of all Contractor supervisory personnel prior to the start of contract work. The purpose of this meeting is to review the approved Work sequence schedule and safety and security procedures. Attendance at this meeting by the CSSO, all Contractor supervisory personnel and the Engineer is mandatory. This meeting shall also be open to other employees of the Contractor and others as the Engineer may deem appropriate. Minutes of this meeting shall be taken by the CSSO, copies provided to each supervisor and kept on file in the Contractor's construction office for

periodic review and updating.

d. Develop a safety and security orientation program and provide a briefing for all employees of the Contractor and subcontractors that will be used on the project. A similar briefing will be given to new employees prior to their use on contract work. In addition, the CSSO shall be responsible for briefing, from time to time, all Contractor personnel on any changes to safety and security measures deemed necessary.

## CONSTRUCTION SEQUENCING

**102-3.1 CONSTRUCTION SEQUENCE.** The Contractor shall prepare a construction schedule and submit to the Engineer at least one week prior to the pre-construction conference.

**102-3.2 CLOSING RUNWAYS.** The Contractor shall acquaint his supervisors and employees with the sequence of construction and its relationship to airport activity and aircraft operations that are inherent to this airport. No runway, taxiway, apron or airport roadway shall be closed without the written approval of the Owner, to enable necessary NOTAMS and/or advisories to airport fixed based operators (FBOs), tenants and users.

The Contractor shall contact the Engineer a minimum of ten (10) days prior to any requested closing.

Any construction activity within **[200]** feet of the centerline of an active runway or within **[85]** feet of the centerline of an active taxiway or apron requires the closure of the affected area. These safety areas are shown on the phasing plan.

The Engineer will arrange for an inspection prior to return to service of any facility, that has been closed for work, on or adjacent thereto, or that has been used for a crossing point or haul route by the Contractor.

## MARKING AND LIGHTING

**102-4.1** Proper marking and lighting of areas on the airfield associated with the construction shall be the responsibility of the Contractor. This will include properly marking and lighting closed runways, taxiways, taxilanes, and aprons, the limits of construction, material storage areas, equipment storage areas, haul routes, parking areas and other areas defined as required for the Contractor's exclusive use. The Contractor shall erect and maintain around the perimeter of these areas suitable marking and warning devices visible for day and night use. Temporary barricades, flagging, and flashing warning lights shall be required at critical access points. The type and location of marking and warning devices will be approved by the Engineer.

Special emphasis shall be given to open trenches, excavations, heavy equipment marshalling areas, and stockpiled material located in the airport operations area, which shall be predominantly marked by the Contractor with flags and lighted by approved light units during hours of restricted visibility and darkness. All marking shall be in accordance with FAA Advisory Circular (AC) 150/5340-1J or latest edition.

## TRAFFIC CONTROL

**102-5.1 VEHICLE IDENTIFICATION.** The Contractor shall establish and maintain a list of Contractor and subcontractor vehicles authorized to operate on the site. Contractor employee vehicles shall be restricted to the Contractor's staging area and are not allowed in the Airport Operations Area (AOA) at any time. To be authorized to operate on the airport, each Contractor or subcontractor's vehicle shall:

- a. be marked/flagged for high daytime visibility and lighted for nighttime operations. Vehicles

that are not marked and/or lighted shall be escorted by a vehicle appropriately marked and/or lighted. Vehicles requiring escort shall be identified on the list.

b. be identified with the name and/or logo of the Contractor and be of sufficient size to be identified at a distance. Vehicles needing intermittent identification could be marked with tape or with commercially available magnetically attached markers. Vehicles that are not appropriately identified shall be escorted by a vehicle that conforms to this requirement. Vehicles requiring escort shall be identified on the list.

c. be operated in a manner that does not compromise the safety of either landside or airside airport operations. If, in the opinion of the Engineer, any vehicle is operated in a manner not fully consistent with this requirement, the Engineer has the right to restrict operation of the vehicle or prohibit its use on the airport.

**102-5.2 ACCESS TO THE SITE OF CONSTRUCTION.** The Contractor's access to the site shall be as shown on the Contract Layout Plan. No other access points shall be allowed unless approved by the Engineer. All Contractor traffic authorized to enter the site shall be experienced in the route or guided by Contractor personnel. The Contractor shall be responsible for traffic control to and from the various construction areas on the site, and for the operation and security of the access gate to the site. A Contractor's flagman or traffic control person shall monitor and coordinate all Contractor traffic at the access gate with Airport Security. The Contractor shall not permit any unauthorized construction personnel or traffic on the site. Access gates to the site shall be locked and secured at all times when not attended by the Contractor. If the Contractor chooses to leave any access gate open, it shall be attended by Contractor personnel who are familiar with the requirements of the Airport Security Program. The Contractor is responsible for the immediate cleanup of any debris deposited along the access route as a result of his construction traffic. Directional signing from the access gate along the delivery route to the storage area, plant site or work site shall be as directed by the Engineer. In addition, the following requirements are applicable:

a. All Contractor traffic authorized to travel on the airport shall have been briefed as part of the Contractor's construction safety and security orientation program, be thoroughly familiar with the access procedures and route for travel or be escorted by personnel authorized by the Contractor Safety and Security Officer (CSSO).

b. The Contractor shall install work site identification signs at the authorized access point(s). If, in the opinion of the Engineer, directional signs are needed for clarity, they shall be installed along the route authorized for access to each construction site.

c. Under no circumstance will Contractor personnel be permitted to drive their individually owned vehicles to any construction site on the airport. All vehicles must be parked in the area designated for employee parking and out of secured airport property.

d. In addition to the inspection and cleanup required at the end of each shift, the Contractor is responsible for the immediate cleanup of any debris generated along the construction site access route(s) as a result of construction related traffic or operations whether or not created by Contractor personnel.

e. The Contractor shall employ a bonded security guard to monitor and control access of at each indicated airport access point indicated on the Construction Safety Phasing Plan. The security guard shall be in place prior to the start of hauling operations and be present until operations are completed and the access point is secured. The security guard shall be trained by the Duluth Airport Authority and have a current Duluth Airport Authority security badge.

f. The Contractor shall provide a portable bathroom facility at each airport access point for the entire duration of the project.

g. The security guard shall have a map/exhibit to review and issue to each person entering the airport indicating haul routes, staging areas, and proper access to the construction site.

h. The Contractor shall provide adequate badged personnel so that all personnel entering the site are continuously visually monitored and controlled per the DAA security plan.

i. The Contractor shall provide an "Access Gate List" to the Engineer 1 week prior to the start of construction. The list may be updated and submitted to the Engineer daily. The list must be clear and legible.

**102-5.3 MATERIAL SUPPLIERS.** All material suppliers, subcontractors and visitors to the work site are obligated to follow the same safety and security operating procedures as the Contractor. All material suppliers shall make their deliveries using the same access points and routes as the Contractor and shall be advised of the appropriate delivery procedures at the time the materials order is placed. The Contractor shall not use the Airport address for any delivery but shall use the street address appropriate to the location of the entrance of the work site. If it is not practical to conform to the vehicle identification requirements of Section 102-5.1 and the safety and security operations program requirements of Section 102-2.2, the Contractor shall be prepared to escort all suppliers, subcontractors and visitors while they are on the airport.

**102-5.4 PERSONNEL IDENTIFICATION.** All employees, agents, vendors, invitees, etc. of the Contractor or subcontractors requiring access to the construction site shall, conform to the Security Program.

### GENERAL SAFETY REQUIREMENTS

**102-6.1** All Contractor vehicles that are authorized to operate on the airport outside of the designated construction area limits or haul routes as defined herein shall display in full view above the vehicle a flashing amber (yellow) dome-type light or a three-foot by three-foot, or larger, orange and white checkerboard flag, each checkerboard color being one-foot square. Vehicles must be under control of a Contractor mobile (two-way) radio operator (flagmen) monitoring the Airport frequency. Vehicle operators must be vigilant for conflict with any aircraft and give way to any operating aircraft.

All Contractor vehicles that are required to operate outside of the construction area limits as defined herein and cross active runways, taxiways, aprons, or runway approach clear zones shall do so under the direct control of a flagman who is monitoring the Airport frequency. Flagmen and two-way radios shall be furnished by the Contractor. Flagmen shall be instructed in the use of two-way radios prior to use. All aircraft traffic on runways, taxiways and aprons shall have priority over Contractor's traffic.

Construction vehicles not in use for extended periods during the work day, or during nights and weekends (nonwork periods) shall be parked away from active runways, taxiways, and aprons in designated vehicle marshalling areas.

**102-6.2** In order to protect all aircraft traffic, aviation related businesses, terminal apron areas, etc. from potential damage caused by foreign object debris (FOD) generated by construction activities, the Contractor shall provide a vacuum truck as required at the startup of construction to daily vacuum all pavements affected by construction. The vacuum truck shall remain on-site for the duration of the project and shall be available at the discretion of the Owner to vacuum pavement areas adjacent to the construction areas to ensure no FOD is present on pavements within 500 feet of any construction area. Protecting the aircraft, airport tenants, users, public, etc. against FOD is a critical safety issue therefore the cost of the vacuum truck will be included in the cost established for this specification item.

## CONSTRUCTION CONTROL

**102-7.1** A primary and alternate responsible Contractor's representative shall be designated by the Contractor. The Contractor's representatives shall be available locally on a 24-hour basis. Names of the primary and alternate, including phone number, shall be made available to the Engineer by the Contractor. The Contractor shall insure that the names and phone numbers are kept current and made available to the Engineer.

## CONSTRUCTION TECHNIQUES

**102-8.1** Construction shall be planned and conducted throughout this project in such a manner as to allow the maintenance of completely safe airport operations. Every effort shall be made to reduce the impact of construction activity on overall airport operations. To this end the Contractor's activities shall be conducted in such a manner so as to preclude, except where absolutely required, open excavations, trenches, ditches and above ground obstacles such as booms on cranes or obstacle markers such as wooden saw horses. The primary responsibility for assuring that the safest possible construction techniques are followed rests with the Contractor Safety and Security Officer (CSSO).

## METHOD OF MEASUREMENT

**102-9.1** The item of Safety and Security shall be measured as a lump sum item when required and furnished for the life of the Contract.

## BASIS OF PAYMENT

**102-10.1** Payment shall be made for airport safety and security measures for personnel or materials related to this specification item and incidentally required to satisfy the specified objective(s) under item P-102-10.0, Safety and Security. This compensation shall be full compensation for furnishing all materials and for all labor, equipment, tools, and incidentals necessary to complete the item.

PARTIAL PAYMENTS. Partial payments will be made in accordance with the following:

<u>Percentage of Original Contract Earned</u>	<u>Allowable Percent of the Lump Sum Price for the Item</u>
5	15
15	20
25	25
50	50
75	75
100 (or Contract Completion)	100

Payment shall be made under:

Item P-102-10.1	Safety and Security - Per Lump Sum.
-----------------	-------------------------------------

## TESTING REQUIREMENTS

**102-11.1** None.

## END OF ITEM P-102