

BID # 12-0458

10th STREET ROAD REPAIRS

CITY OF DULUTH PROJECT NO. 1136

EXHIBIT A

ITEM NO.	SPEC. NO.	ITEM DESCRIPTION	UNIT	ESTIMATED QUANTITIES	UNIT PRICE	TOTAL PRICE
1	2021.501	MOBILIZATION	LUMP SUM	1		
2	2104.501	REMOVE SEWER PIPE (STORM)	(P) LIN FT	40		
3	2104.501	REMOVE CURB AND GUTTER	LIN FT	65		
4	2104.503	REMOVE CONCRETE DRIVEWAY PAVEMENT	(P) SQ FT	142		
5	2104.509	REMOVE MANHOLE OR CATCH BASIN	EACH	1		
6	2104.513	SAWING BIT PAVEMENT (FULL DEPTH)	LIN FT	70		
7	2104.601	REMOVE MISCELLANEOUS DEBRIS	LUMP SUM	1		
8	2105.501	COMMON EXCAVATION (CV)	CU YD	34		
9	2105.522	SELECT GRANULAR BORROW MOD 7% (CV)	CU YD	46		
10	2105.523	COMMON BORROW (LV)	CU YD	200		
11	2105.604	GEOTEXTILE FABRIC TYPE V	SQ YD	70		
12	2211.503	AGGREGATE BASE (CV) CLASS 5	CU YD	20		
13	2360.501	TYPE SP 9.5 WEARING COURSE MIXTURE (3.C)	TON	14		
14	2360.501	TYPE SP 12.5 NON WEARING COURSE MIXTURE (3.C)	TON	17		
16	2501.515	60" RC PIPE APRON	EACH	2		
15	2502.541	4" PERF PVC PIPE DRAIN	LIN FT	126		
17	2503.602	CONNECT TO EXISTING DRAIN TILE	EACH	4		
18	2503.541	60" RC PIPE SEWER CLASS III	LIN FT	71		
19	2503.602	CONNECT TO EXISTING STORM SEWER	EACH	2		
20	2504.602	CONNECT TO EXISTING WATERMAIN	EACH	2		
21	2504.603	8" HDPE WATER MAIN SDR-11	LIN FT	38		
22	2504.604	3" POLYSTYRENE INSULATION	SQ YD	5		
23	2505.602	CONNECT TO EXISTING GAS MAIN (ABANDONED)	EACH	2		
24	2506.501	CONSTRUCT DRAINAGE STRUCTURE DESIGN 96-4020	LIN FT	11.23		
25	2506.516	CASTING ASSEMBLY	EACH	1		
26	2531.501	CONCRETE CURB & GUTTER DESIGN B624	LIN FT	126		
27	2531.507	7" CONCRETE DRIVEWAY PAVEMENT	SQ YD	16		
28	2563.601	TRAFFIC CONTROL	LUMP SUM	1		
29	2573.502	SILT FENCE, TYPE HEAVY DUTY	LIN FT	100		
30	2573.530	STORM DRAIN INLET PROTECTION	EACH	4		
31	2573.602	TEMPORARY ROCK CONSTRUCTION ENTRANCE	EACH	2		
32	2575.555	TURF ESTABLISHMENT	LUMP SUM	1		
33						

GRAND TOTAL = \$