

ADDENDUM NO. 1
43RD AVENUE WEST SANITARY SEWER EXTENSION
CITY OF DULUTH
PROJECT NO. 1331
BID OPENING DATE: 2:00 PM , MAY 28, 2014
Date: May 27, 2014

NOTICE

This Addendum is issued to modify, explain or correct the original drawings, specifications and/or previous addenda and is hereby made a part of the Contract Documents. Please attach this Addendum to the specification and note receipt of this Addendum on the Request for Bid.

SPECIFICATIONS

EXHIBIT A

The estimated quantities for Bid Items, 2104.503 Remove Concrete Walk and 2521.501 4" Concrete Walk have been revised. For each bid item the quantity changed from **155 sq ft to 1,355 sq ft. Use the revised Exhibit A when submitting you bid.**

END OF ADDENDUM

		EXHIBIT A - REVISED					
		BID NO. 14-0362	JOB NO. 1331				
		43RD AVENUE WEST SANITARY SEWER EXTENSION					
Item No.	Spec No.	Description	Unit	Est. Quantity	Unit Price	Total Price	
1	2021.501	Mobilization	Lump Sum	1			
2	2104.501	Remove Integrant Curb	LN FT	133			
3	2104.503	Remove Concrete Walk	SQ FT	1355			
4	2104.505	Remove Bituminous Pavement	SQ YD	87			
5	2104.505	Remove 7.5" Reinforced Concrete Pavement	SQ YD	245			
6	2104.509	Remove 20" CAL BR Deciduous Tree	Each	2			
7	2104.509	Remove Concrete Stair	Each	1			
8	2104.511	Sawing Reinforced Concrete Pavement (Full Depth)	LN FT	356			
9	2104.513	Sawing Bituminous Pavement (Full Depth)	LN FT	100			
10	2104.522	Select Granular Borrow, 7% Mod. (CV) (P)	CU YD	122			
11	2105.604	Geotextile Fabric, Type V (P)	SQ YD	253			
12	2211.503	Aggregate Base (CV) Class 5 (P)	CU YD	58			
13	2301.501	Concrete Pavement, 7.5" (High Early Concrete Mix)	SQ YD	245			
14	2301.602	Drill & Grout Dowel Bar (Epoxy Coated) 1" Dia X 18" Long	Each	178			
15	2360.501	Type SP 9.5 Wearing Course Mixture (3.C)	Ton	10.6			
16	2411.607	Concrete Steps	CU YD	0.5			
17	2451.503	Select Granular Backfill Mod 7% (CV)	CU YD	83			
18	2503.511	6" PVC Pipe Sewer SDR35	LN FT	171			
19	2503.511	8" PVC Pipe Sewer, SDR 35	LN FT	295			
20	2503.602	Tracer Box	Each	6			
21	2503.602	8" X 6" PVC Wye	Each	6			
22	2503.602	Connect Sanitary Sewer Service	Each	5			
23	2503.602	Plug and Abandon 6" Sanitary Sewer	Each	4			

24	2504.602	Reconnect Existing Water Service	Each	2		
25	2504.602	3/4" Corporation Stop	Each	3		
26	2504.602	3/4" Curb Stop & Box	Each	3		
27	2504.603	3/4" Type K Copper Pipe	LN FT	105		
28	2506.501	Construct Drainage Structure Design F	LN FT	15.11		
29	2506.516	Casting Assembly	Each	2		
30	2506.602	Connect To Existing Sanitary Manhole	Each	1		
31	2506.602	Manhole Frame Seal, External	Each	2		
32	2,506.602	Manhole Vacuum Testing	Each	2		
33	2,506.602	Adjust Manhole Frame And Rings	Each	1		
34	2506.602	Location Of Sanitary Sewer Lateral By Sonde Method	Each	5		
35	2521.501	4" Concrete Walk	SQ FT	1355		
36	2531.501	Integrant Curb, Design B6	LN FT	133		
37	2531.618	Truncated Dome	SQ FT	8		
38	2563.601	Traffic Control	Lump Sum	1		
39	2571.502	Deciduous Tree 2" CAL BR	Tree	5		
40	2575.505	Sodding	SQ YD	254		
					TOTAL	