


DECC SEAWALL PROJECTDuluth, MN



CHAD SCOTT, PE CHASE DEWHIRST, PE

AMI Consulting Engineers, PA - Multidiscipline Engineering Firm Marine | Civil | Structural | Mechanical | Environmental



OWNER

· City of Duluth / DECC

ENGINEER:

- Civil, Marine, Mechanical, Environmental – AMI
- · Electrical Gausman & Moore














<u>Limits of Construction: Inner End of MN Slip & STA 0+00 to 12+08</u>



GENERAL CONSTRUCTION OVERVIEW

- Install New Epoxy Coated Seawall 54,810 SF
 - o 1,218 LF x 45' Length SSP
 - o C12x30 Double Wale
 - o 1-3/4" Tierods
 - o Timber Rub Rails
- Install New Tieback System 1,140 LF
 - o HP10x42 Piling
 - o W14x120 Transfer Beam
 - o Design Helical Anchors
- Install New Bollards & Foundations 8 EA
- Design & Install Camel System 1 LS
- Demo portions of existing seawall
- Demo Vista Fleet Building
- Demo Vista Temporary Platform
- Civil / Mechanical / Electrical Work
- Alternatives
 - o #1 Curb & Gutter / Bike Path
 - o #2 Remaining Concrete Flatwork & Sidewalks
 - o #3 Mechanical Material Installation
 - o #4 Electrical Installation
 - o BIDS DUE 11/8/17

GENERAL CONSTRUCTION OVERVIEW/CONT

- ADDENNDUMS
 - Bid form to include Electrical & Updated Quantities
 - Documentation further explaining what is included in each bid item
 - Final Construction Documents
 - Historical Documents

OWNER FURNISHED MATERIALS

- Two Request For Bids Currently Out
 - o Structural Steel (Bid Opening 10/31/17)
 - ❖ Steel Sheet Pile
 - HP10x42 Steel Piling for Tieback System
 - ❖ W14x120 Steel Transfer Beam for Tieback System
 - ❖ 3/8" Bent Steel Cap
 - Application of High-Performance Coating (Bid Opening 11/7/17)

***All Owner furnished materials are based on Neat Line Quantities per the Bid Form. The Contractor is responsible for any additional materials including the installation of a high-performance coating on the steel sheet piling per the technical specifications.



SITE CONDITIONS & GENERAL INFORMATION

- Scope of Work Limits
 - o MN Slip Inner End, and STA 0+00 to 12+08
- Schedule
 - o Substantial Completion by June 1, 2018
 - o Final Completion by June 15, 2018
- Liquidated Damages
 - o \$1,000 per Day after June 1, 2018
- Vista Fleet Building
 - o Asbestos
 - o Underground Storage Tank
 - o Electronics
- Contaminated Soils
- Tight Work Area
 - May need to shore roadway during Helical Anchor Installation
 - Work restricted within 30' of existing retaining structure
 - ❖ Wood Relieving Platform
 - One lane closure Harbor Drive

SITE CONDITIONS & GENERAL INFORMATION/CONT.


- Winter Work
- Staging Areas
 - o On-site DECC
 - o Off-site
- Permits
 - o MPCA
 - o Building Demo
 - o Lane Closures
 - o DNR, USACE Pending

OWNER FURNISHED MATERIAL SCHEDULE

- City Council Meeting: November 20, 2017
- Steel Sheet Piling & Cap, H Piling, W Beams
 - o FOB DECC: December 18, 2017
- High-Performance Coating on Steel Sheet Piling
 - o FOB DECC: February 2, 2018



Onsite Staging Area



<u>Limits of Construction: Inner End of MN Slip & STA 0+00 to 12+08</u>








MN SLIP INNER END

- Existing Steel Sheet Pile
- New Steel Sheet Pile Cap





MN SLIP INNER END — Existing Steel Sheet Pile









STA 0+00 to 6+02


- Wakefield Piling
- Pile Supported Concrete Dock Cap





STA 0+00 to 6+02 — Wakefield Piling








STA 0+00 to 6+02 – Pile Supported with Wakefield Piling








STA 0+00 to 6+02 – Pile Supported with Wakefield Piling









STA 6+02 to 9+00 & 9+25 to 9+85

- Wood Relieving Platform
- Partial Wall Demolition






STA 6+02 to 9+00 & 9+25 to 9+85 – Wood Relieving Platform








STA 6+02 to 9+00 & 9+25 to 9+85 – Wood Relieving Platform





DOCK WALL DEMOLITION

- · Demo Temporary Vista Platform
- Remove wood platform, Vertical Piling, portions of wall, and misc. debris as noted.





DOCK WALL DEMOLITION


- Demo Temporary Vista Platform
- Remove wood platform, Vertical Piling, portions of wall, and misc. debris as noted.





DOCK WALL DEMOLITION

- · Demo Temporary Vista Platform
- Remove wood platform, Vertical Piling, portions of wall, and misc. debris as noted.






STA 9+00 to 9+25

Slip Bridge Abutment






STA 9+00 to 9+25 – Slip Bridge Abutment






STA 9+00 to 9+25 – Slip Bridge Abutment






STA 9+85 to 12+08


Crib Dock Wall





STA 9+85 to 12+08 – Crib Supported Concrete Structure








STA 9+85 to 12+08 – Crib Supported Concrete Structure








OTHER REMARKS


- Survey GPS Points for Seawall
 - o Example Shown at STA 6+02
- Key Submittals
 - Driving Logs & Alignment Checks – SSP (Daily)
 - o Driving Logs & Alignment Checks – H Piles (Daily)
 - o Experienced Surveyor
 - o Helical Anchor Design
 - o Camel System Design
- Irvin Cannot Leave Slip Prior to Dock Wall Rehabilitation
- AMI Full Time Project Management





QUESTIONS ON MARINE?








- Demolition
- Grading
- Concrete Flatwork
- Concrete Sidewalks
- Bike Path



ELI RUPNOW, PEAMI Consulting Engineers, PA




- Demolition
 - o Base
 - ❖ Vista Fleet Building
 - Irving Loading Platforms
 - Concrete flatwork, bollards, signage, and other misc. Items






- Demolition
 - o Add Alt 1
 - 1167 LF of Curb and Gutter
 - ❖ 1200 SY of Concrete Pavement
 - Remove Storm Structure and Adjust Frame and Casting
 - o Add Alt 2
 - · Concrete Walks
 - · 400 SF






- Site
 - o Base
 - Vista Loading Ramps and Platform
 - Planter Boxes and Stairs
 - Irving Loading Platforms






- Site
 - o Add Alt 1
 - ❖ 1098 ft 8 in Curb
 - ❖ 1208 LF of 10 ft Wide Bike Trail
 - ❖ 6 Pedestrian Ramps
 - ❖ Storm Structure





- Site
 - o Add Alt 2
 - ❖ 10100 SF Concrete Sidewalk




STA: 5+00



QUESTIONS ON CIVIL?







MECHANICAL




ADAM MARKSTEINER, PE AMI Consulting Engineers, PA



MECHANICAL

· Installation





MECHANICAL

· Installation





QUESTIONS ON MECHANICAL?





ELECTRICAL

- · Demolition
- · Installation



SCOTT HAEDTKE Gausman & Moore

Gausman &Moore Mechanical and Electrical Engineers


ELECTRICAL

Demolition

GENERAL NOT

A. IT IS THE RESPONSIBILITY OF THIS CONTRACTOR TO PROVIDE COMPLETE DEMOLITION TO FACILITATE NEW CONSTRUCTION IN PHASES REQUIRED FIELD VERIFY EXISTING CONDITIONS PRIOR TO BID. NO EXTRAG WILL BE ALLOWED DUE TO CONTRACTORS LACK OF INVOICEDED OF EXISTING CONSTRUCTS, SCOPE, AND/OR SCHEDULE.


- DISCONNECT AND REMOVE LIGHT FIXTURES, POWER, SECURITY AND DATA DEVICES IN THIS AREA COORDINATE WITH CITY OF DULLITH POLICE DEPARTMENT FOR OCTV EQUIPMENT REMOVAL AND REINSTALLATION.
- 3. REMOVE LIGHT FIXTURE, POLE, BASE, AND BRANCH CIRCUITING COMPLETE.
- 4. DISCONNECT EXISTING COPPER AND FIBER SERVICES FROM IRVIN TO FACILITATE SHIP REMOVAL, REMOVE EXISTING COMM, PEDESTAL AND RENOTALL AFTER SLIP WALL, CONSTRUCTION IS COMPLETE, RECONNECT EXISTING COPPER AND PIBER SERVICES AS REQUIRED.
- REMOVE EXISTING LIGHTING SYSTEMS IN THIS AREA COMPLETE. SALVAGE EXISTING HOMERUN FOR CONNECTION TO NEW AS INDICATED ON SHEET E1.2.
- REMOVE EXISTING LANDSCAPE, INCLUDING BUT NOT LIMITED TO TREES, SHRUES, EXCESS DRY, LANDSCAPE WALLS AND ELECTRICAL CONNECTIONS IN AREA TO FACILITATE CONSTRUCTION OF NEWWIN, POWER SERVICE AREA




Gausman & Moore Mechanical and Electrical Engineers

ELECTRICAL


· Installation





ELECTRICAL


Installation



Gausman &Moore

ELECTRICAL

Installation





Gausman &Moore

Mechanical and Electrical Engineers

ELECTRICAL

· Installation Details









QUESTIONS



