



CITY OF DULUTH
PURCHASING DIVISION
Room 100 City Hall
411 West First Street
Duluth, Minnesota 55802-1199
218/730-5340
purchasing@duluthmn.gov

Addendum 5
File 18-0084
Grand Ave Nordic Ski Trail Construction

This addendum serves to notify all bidders of changes to the solicitation documents as follows:

1. The Unit of Measure for 12" CS Pipe Aprons in both the base bid and Add Alt 2 has been corrected to EACH. Quantities remain the same.
2. The following question is asked and answered: What are the requirements for the high strength helical pile shown on the above ground elevated pipe support assembly? (i.e. depth, diameter, or load).
Supports per "Above Ground Elevated Pipe Support Assembly" detail on drawing 852615-M1 sheet 9.

Supports are site specific in areas where pipe spans a contour more than approximately 10 ft. and should be sized to support the pipe full of water.

Height to prevent low point dips in the pipe span.

Helical depth to 6 feet deep or to solid rock whichever comes first.

Piling by Heli-Pile, Denver CO, 1.5" modular high strength single helix pile with HP-15-PC load transfer bracket or equal.

Please acknowledge receipt of this Addendum by checking the appropriate box in your Bid Express bid or by initialing and dating Addendum #5 on the bid form.

Posted: March 19, 2018