

Bid # 2011-00000-313 Project # 0851TR
Ivanhoe Street Reconstruction, from 49th Avenue East to 54th Avenue East
EXHIBIT A - Addendum 1

Item No.	Spec. No.	Description	Unit	Est. Qty	Unit Price	Total Price
1	2021.501	MOBILIZATION	LUMP SUM	1.00		
2	2101.502	CLEARING	TREE	25.00		
3	2101.507	GRUBBING	TREE	31.00		
4	2101.511	CLEARING AND GRUBBING	LUMP SUM	1.00		
5	2104.501	REMOVE CURB AND GUTTER	L.F.	2,066.80		
6	2104.501	REMOVE SEWER PIPE (STORM)	L.F.	2,048.00		
7	2104.501	REMOVE SEWER PIPE (SANITARY)	L.F.	1,491.00		
8	2104.501	REMOVE WATERMAIN	L.F.	2,466.80		
9	2104.501	REMOVE FENCE	L.F.	70.00		
10	2104.501	REMOVE CONCRETE STEPS	L.F.	9.90		
11	2104.503	REMOVE CONCRETE SIDEWALK	S.F.	4,942.50		
12	2104.505	REMOVE BITUMINOUS PAVEMENT	S.Y.	8,003.00		
13	2104.505	REMOVE CONCRETE PAVEMENT	S.Y.	251.00		
14	2104.505	REMOVE BITUMINOUS DRIVEWAY PAVEMENT	S.Y.	682.00		
15	2104.505	REMOVE CONCRETE DRIVEWAY PAVEMENT	S.Y.	318.00		
16	2104.509	REMOVE HYDRANT	EACH	4.00		
17	2104.509	REMOVE GATE VALVE & BOX	EACH	6.00		
18	2104.509	REMOVE CATCH BASIN	EACH	18.00		
19	2104.509	REMOVE MANHOLE	EACH	15.00		
20	2104.509	REMOVE CURB STOP & BOX	EACH	51.00		
21	2104.509	REMOVE SIGN	EACH	6.00		
22	2104.509	REMOVE CONCRETE APRON	EACH	1.00		
24	2104.509	REMOVE MAILBOX AND SUPPORT	EACH	26.00		
24	2104.511	SAWING CONCRETE PAVEMENT (FULL DEPTH)	L.F.	229.90		
25	2104.513	SAWING BITUMINOUS PAVEMENT (FULL DEPTH)	L.F.	616.60		
26	2104.521	SALVAGE WOODEN FENCE	L.F.	67.00		
27	2104.523	SALVAGE CASTING	EACH	29.00		
28	2104.618	SALVAGE CONCRETE BLOCK RETAINING WALL	S.Y.	40.00		
29	2105.501	COMMON EXCAVATION (P)	C.Y.	6,202.00		
30	2105.521	GRANULAR BORROW (CV)	C.Y.	780.00		
31	2105.522	SELECT GRANULAR BORROW MOD 7% (CV)(P)	C.Y.	2,700.00		
32	2105.604	GEOTEXTILE FABRIC TYPE V	S.Y.	8,700.00		
33	2105.607	EXCAVATION SPECIAL	C.Y.	780.00		

34	2211.502	AGGREGATE BASE (LV) CLASS 5					
35	2211.503	AGGREGATE BASE (CV) CLASS 5 (P)		C.Y.	110.50		
				C.Y.	2,100.00		
36	2301.604	CONCRETE PAVEMENT 7"		S.Y.	251.00		
37	2360.501	TYPE SP 9.5 WEARING COURSE MIXTURE (3,C)		TON	700.00		
38	2360.502	TYPE SP 12.5 NON WEARING COURSE MIXTURE (3,C)		TON	900.00		
39	2360.505	TYPE SP 9.5 BITUMINOUS MIXTURE FOR PATCHING		TON	176.50		
40	2411.618	INSTALL CONCRETE BLOCK RETAINING WALL		S.Y.	40.00		
41	2451.501	STRUCTURE EXCAVATION CLASS R		C.Y.	50.00		
42	2451.503	GRANULAR BACKFILL (CV)		C.Y.	50.00		
43	2451.511	COARSE FILTER AGGREGATE (CV)		C.Y.	50.00		
44	2501.515	12" RC PIPE APRON		EACH	1.00		
45	2502.521	4" PVC PIPE DRAIN		L.F.	277.50		
46	2502.521	10" PVC PIPE DRAIN		L.F.	363.00		
47	2502.541	4" PERFORATED PVC PIPE DRAIN		L.F.	4,940.00		
48	2502.601	DRAINAGE SYSTEM		LUMP SUM	1.00		
49	2502.602	10" PVC PIPE DRAIN CLEANOUT		EACH	2.00		
50	2502.511	10" PVC PIPE SEWER SDR 35		L.F.	13.00		
51	2503.511	8" PVC PIPE SEWER SDR 35		L.F.	1,456.50		
52	2503.511	6" PVC PIPE SEWER SERVICE SDR 35		L.F.	1,659.00		
53	2503.541	12" RC SEWER PIPE DESIGN 3006, CLASS III		L.F.	1,077.80		
54	2503.541	15" RC SEWER PIPE DESIGN 3006, CLASS III		L.F.	634.00		
55	2503.541	18" RC SEWER PIPE DESIGN 3006, CLASS III		L.F.	422.80		
56	2503.541	24" RC SEWER PIPE DESIGN 3006, CLASS III		L.F.	507.30		
57	2503.602	CONNECT TO EXISTING SANITARY SEWER SERVICE		EACH	51.00		
58	2503.602	CONNECT TO EXISTING SANITARY SEWER		EACH	4.00		
59	2503.602	MAGNETIZED TRACER BOX		EACH	51.00		
60	2503.602	8" X 6" PVC WYE SDR 35		EACH	51.00		
61	2503.603	CONSTRUCT 8" INSIDE DROP		L.F.	11.10		
62	2503.603	CIPP 8" MAIN LINING		L.F.	836.00		
63	2504.601	TEMPORARY WATER SERVICE		LUMP SUM	1.00		
64	2504.602	0.75" TAPPING TEE WITH ELECTROFUSION SADDLE		EACH	41.00		
65	2504.602	1.0" TAPPING TEE WITH ELECTROFUSION SADDLE		EACH	10.00		
66	2504.602	0.75" CURB STOP & BOX		EACH	41.00		
67	2504.602	1.0" CURB STOP & BOX		EACH	10.00		
68	2504.602	HYDRANT		EACH	6.00		
69	2504.602	8" GATE VALVE AND BOX		EACH	6.00		

70	2504.602	CONNECT TO EXISTING WATERMAIN	EACH	4.00	
71	2504.602	CONNECT TO EXISTING WATER SERVICE	EACH	51.00	
72	2504.602	MAGNETIZED TRACER BOX	EACH	51.00	
73	2504.602	ADJUST VALVE BOX	EACH	1.00	
74	2504.603	0.75" HDPE SDR 11 TAP SERVICE PIPE	L.F.	1,320.00	
75	2504.603	1.0" HDPE SDR 11 TAP SERVICE PIPE	L.F.	330.00	
76	2504.603	8" DIPS HDPE WATERMAIN SDR 11	L.F.	2,338.00	
77	2504.604	3" POLYSTYRENE INSULATION	S.Y.	131.70	
78	2504.608	WATERMAIN FITTINGS	POUND	665.00	
79	2506.501	CONSTRUCT DRAINAGE STRUCTURE DESIGN 4007C	L.F.	81.80	
80	2506.501	CONSTRUCT DRAINAGE STRUCTURE DESIGN 4020 - 72	L.F.	7.51	
81	2506.501	CONSTRUCT DRAINAGE STRUCTURE DESIGN F	L.F.	112.35	
82	2506.501	CONSTRUCT DRAINAGE STRUCTURE DESIGN G	L.F.	65.80	
83	2506.516	CASTING ASSEMBLY	EACH	51.00	
84	2506.602	ADJUST FRAME AND RING CASTING	EACH	1.00	
85	2506.602	MANHOLE FRAME SEAL	EACH	10.00	
86	2506.602	MANHOLE VACUUM TESTING	EACH	7.00	
87	2506.602	CONNECT TO EXISTING STORM SEWER	EACH	6.00	
88	2511.501	RANDOM RIP RAP CLASS II	C.Y.	10.00	
89	2521.501	4" CONCRETE WALK	S.F.	268.20	
90	2521.501	7" CONCRETE WALK	S.F.	158.00	
91	2531.501	CONCRETE CURB AND GUTTER DESIGN B624	L.F.	4,950.00	
92	2531.507	7" CONCRETE DRIVEWAY PAVEMENT	S.Y.	690.00	
93	2531.521	STRUCTURAL CONCRETE	C.Y.	1.00	
94	2531.618	TRUNCATED DOMES	S.F.	16.00	
95	2540.602	FURNISH AND INSTALL MAILBOX AND SUPPORT	EACH	52.00	
96	2557.603	INSTALL WOODEN FENCE	L.F.	67.00	
97	2563.601	TRAFFIC CONTROL	LUMP SUM	1.00	
98	2564.533	FURNISH SIGN PANELS TYPE C	S.F.	47.00	
99	2564.536	INSTALL SIGN PANELS TYPE C	EACH	10.00	
100	2571.502	DECIDUOUS TREE 2.5" CAL B&B	EACH	27.00	
101	2571.602	TREE PROTECTION TYPE 1	EACH	25.00	
102	2573.502	SILT FENCE, TYPE HEAVY DUTY	L.F.	2,570.00	
103	2573.502	FILTER LOG TYPE ROCK LOG	L.F.	100.00	
104	2573.530	STORM DRAIN INLET PROTECTION	EACH	32.00	
105	2573.602	TEMPORARY ROCK CONSTRUCTION ENTRANCE	EACH	6.00	
106	2573.602	TEMPORARY SEDIMENT TRAP	EACH	4.00	
107	2575.505	SODDING TYPE LAWN	S.Y.	9,217.00	

108	2582.502	12" SOLID LINE WHITE EPOXY							
109	2582.502	24" STOP LINE WHITE EPOXY				L.F.		61.00	
						L.F.		44.00	

GRAND TOTAL: _____