

PAVEMENT MARKING LAYOUT - 0852TR - SWAN LAKE ROAD								
STATION / STATION	LOCATION	LT	CL	RT	4 " SOLID LINE WHITE - EPOXY 2582 LIN FT	4 " DOUBLE SOLID YELLOW - EPOXY 2582 LIN FT	24 " STOP LINE SOLID YELLOW - EPOXY 2582 LIN FT	COMMENTS
300+35	303+75	SWAN LAKE RD		X		340		CENTERLINE
304+15	315+85	SWAN LAKE RD		X		1170		CENTERLINE
316+50	317+15	SWAN LAKE RD		X		65		CENTERLINE
317+70	325+00	SWAN LAKE RD		X		730		CENTERLINE
325+45	332+53	SWAN LAKE RD		X		708		CENTERLINE
332+90	336+75	SWAN LAKE RD		X		385		CENTERLINE
337+18	348+00	SWAN LAKE RD		X		1082		CENTERLINE
347+94		SWAN LAKE RD			X		11	STOP BAR
348+21		EKLUND AVE	X				11	STOP BAR (48' LT)
348+88		WALNUT ST	X				11	STOP BAR (48' LT)
348+90	356+00	SWAN LAKE RD		X		710		CENTERLINE
349+09		SWAN LAKE RD	X				11	STOP BAR
356+50	363+45	SWAN LAKE RD		X		695		CENTERLINE
364+05	366+80	SWAN LAKE RD		X		275		CENTERLINE
367+35	374+00	SWAN LAKE RD		X		665		CENTERLINE
374+35	377+76	SWAN LAKE RD		X		341		CENTERLINE
300+14	377+76	SWAN LAKE RD	X		X			FOG LINES
TOTAL						15524	7166	44

PAVEMENT MARKING LAYOUT - 0787TR - SKYLINE PWKY										
STATION / STATION	LOCATION	OFFSET FT.	LT	CL	RT	4" DOUBLE SOLID YELLOW - EPOXY 2582 LIN FT	4" SOLID LINE WHITE - EPOXY 2582 LIN FT	12" SOLID LINE WHITE - EPOXY 2582 LIN FT	24" STOP LINE WHITE - EPOXY 2582 LIN FT	COMMENTS
400+00	470+25	SKYLINE PKWY		X		7025				CENTERLINE
470+95	486+61	SKYLINE PKWY		X		1566				CENTERLINE
500+30	523+30	HANK JENSEN DR		X		2300				CENTERLINE
428+26		SKYLINE PKWY		X				88		CROSSWALK
501+00		HANK JENSEN DR	X						21	STOP BAR
471+00		SKYLINE PKWY	X						14	STOP BAR
486+50		SKYLINE PKWY			X				12	STOP BAR
400+00	486+61	HANK JENSEN DR					17322			
500+00	523+88	SKYLINE PKWY					4776			FOG LINE
TOTAL						10891	22098	88	47	

INTERIM PAVEMENT MARKINGS LAYOUT									
LOCATION	LT	CL	RT	4" SOLID LINE YELLOW - EPOXY 2580 LIN FT	4" BROKEN LINE WHITE -EPOXY 2580 LIN FT	NUMBER OF LINES	NUMBER OF OCCURRENCES	TOTAL	COMMENTS
4TH AVE W		X		762		2	3	4,572	CENTERLINE OF ROAD
ARROWHEAD RD.		X		6507		2	4	52,056	CENTERLINE OF ROAD
ARROWHEAD RD.	X				1150	1	4	4,600	CENTERLINE BETWEEN LANE
ARROWHEAD RD.			X		1150	1	4	4,600	CENTERLINE BETWEEN LANE
88TH AVE W.		X		8159		2	3	48,954	CENTERLINE OF ROAD
EAST 1st STREET		X			972	1	3	2,916	CENTERLINE OF ROAD
SWAN LAKE RD		X		7166		2	2	28,664	CENTERLINE OF ROAD
SKYLINE PKWY		X		10891		2	2	43,564	CENTERLINE OF ROAD
TOTAL								189,926	

NOTE: 1) INTERIM PAVEMENT MARKINGS SHALL BE PLACED AFTER EACH DAY OF MILLING & PAVING.

CERTIFIED BY: CAROLINE PEDERSEN	REG. NO.: 42634	REVISION	DRAWN BY: SGA
SIGNATURE: 	DATE: 5-10-11	REMOVE "EPOXY" AND CHANGE SPEC # FROM 2582	STRIPING QUANT 1
			SHEET NO. 10 OF 63