

Bid #11-0332 Project #0828TR
2011 Street Preservation Project

Revised 5/9/2011

EXHIBIT A

Item No.	Spec. No.	Description	Unit	Est. Qty	Unit Price	Total Price
1	2021.501	MOBILIZATION	LUMP SUM	1		
2	2104.501	REMOVE PIPE CULVERTS	LIN.FT.	1007		
3	2104.501	REMOVE CURB AND GUTTER	LIN.FT.	2062		
4	2104.501	REMOVE GUARD RAIL	LIN.FT.	760		
5	2104.503	REMOVE CONCRETE WALK	SQ. FT.	2250		
6	2104.503	REMOVE CONCRETE DRIVEWAY PAVEMENT	SQ. FT.	65		
7	2401.511	SAWING CONCRETE PAVEMENT (FULL DEPTH)	LIN.FT.	13		
8	2401.513	SAWING BITUMINOUS PAVEMENT (FULL DEPTH)	LIN.FT.	1059		
9	2123.503	MOTOR GRADER	HOUR	60		
10	2123.507	3 CU. YD. SHOVEL	HOUR	64		
11	2123.51	10 CU. YD. TRUCK	HOUR	128		
12	2123.525	8 TON STEEL-WHEELED ROLLER	HOUR	60		
13	2123.61	STREET SWEEPER (WITH PICKUP BROOM)	HOUR	60		
14	2130.501	WATER	MGALLONS	90		
15	2131.502	CALCIUM CHLORIDE SOLUTION	GALLON	11785		
16	2211.501	AGGREGATE BASE CLASS 5	TON	544		
17	2221.501	AGGREGATE SHOULDERING CLASS 1	TON	2243		
18	2232.501	MILL BITUMINOUS SURFACE (2.0")	SQ. YD.	802		
19	2232.501	MILL BITUMINOUS SURFACE (3.5")	SQ. YD.	74412		
20	2232.501	MILL BITUMINOUS SURFACE (5.0")	SQ. YD.	31746		
21	2331.604	BITUMINOUS PAVEMENT RECLAMATION	SQ. YD.	88323		
22	2357.606	BITUMINOUS MATERIAL FOR SHOULDER TACK	GALLON	2510		
23	2360.501	TYPE SP 12.5 WEARING COURSE MIX (3,B)	TON	16378		

24	2360.501	TYPE SP 12.5 WEARING COURSE MIX (3,C)	TON	20690	
25	2360.502	TYPE SP 12.5 NON WEARING COURSE MIX (3,B)	TON	3968	
26	2501.511	12" CS PIPE CULVERT	LIN.FT.	338	
27	2501.515	15" RC PIPE APRON	EACH	6	
28	2501.515	24" RC PIPE APRON	EACH	1	
29	2501.515	42" RC PIPE APRON	EACH	2	
30	2501.521	28" SPAN RC PIPE-ARCH CULVERT CL IIA	LIN.FT.	212	
31	2501.525	28" SPAN RC PIPE-ARCH APRON	EACH	7	
32	2053.541	15" RC PIPE SEWER CES 3006 CL III	LIN.FT.	141	
33	2053.541	24" RC PIPE SEWER CES 3006 CL III	LIN.FT.	221	
34	2053.541	42" RC PIPE SEWER CES 3006 CL III	LIN.FT.	92	
35	2504.602	ADJUST VALVE BOX	EACH	77	
36	2506.501	CONSTRUCT DRAINAGE STRUCTURE DESIGN C	LIN.FT.	32	
37	2506.516	CASTING ASSEMBLY	EACH	31	
38	2506.602	MANHOLE FRAME SEAL	EACH	53	
39	2506.602	ADJUST FRAME & RING CASTING (SPECIAL)	EACH	114	
40	2511.501	RANDOM RIPRAP CALSS III	CU. YD.	142.1	
41	2521.501	4" CONCRETE WALK	SQ. FT.	1500	
42	2521.501	6" CONCRETE WALK	SQ. FT.	750	
43	2531.501	CONCRETE CURB & GUTTER DESIGN B624	LIN.FT.	2062	
44	2531.502	CONCRETE CURB DESIGN V6	LIN.FT.	160	
45	2531.507	6" CONCRETE DRIVEWAY PAVEMENT	SQ. YD.	7.2	
46	2531.602	PEDESTRIAN CURB RAMP (DETAIL A,B,C)	EACH	41	
47	2531.602	PEDESTRIAN CURB RAMP (DETAIL D)	EACH	2	
48	2531.602	PEDESTRIAN CURB RAMP (DETAIL F)	EACH	10	
49	2531.602	PEDESTRIAN CURB RAMP (DETAIL H)	EACH	7	
50	2531.618	TRUNCATED DOMES	SQ. FT.	552	
51	2540.602	ADJUST MONUMENT BOX	EACH	2	
52	2540.602	CONSTRUCT SURVEY MONUMENT	EACH	3	
53	2540.602	MAIL BOX SUPPORT	EACH	49	
54	2554.501	TRAFFIC BARRIER DESIGN B8338	LIN.FT.	736	

55	2554.523	END TREATMENT-ENERGY ABSORBING TERMINAL	EACH	4	
56	2563.601	TRAFFIC CONTROL	LUMP SUM	1	
57	2573.502	SILT FENCE HEAVY DUTY	LIN.FT.	895	
58	2573.531	STORM DRAIN INLET PROTECTION	LUMP SUM	1	
59	2573.540	FILTER LOG TYPE WOOD FIBER BIOROLL	LIN.FT.	370	
60	2575.501	SEEDING	ACRE	3.46	
61	2575.502	SEED MIXTURE 250	POUND	242	
62	2575.511	MULCH MATERIAL TYPE 1	TON	6.92	
63	2575.523	EROSION CONTROL BLANKETS CATEGORY 3	SQ. YD.	1309	
64	2575.531	FERTILIZER TYPE 1	TON	0.52	
65	2580.603	INTERIM PAVEMENT MARKING	LIN.FT.	189926	
66	2582.502	4" SOLID LINE WHITE-EPOXY	LIN. FT.	47144	
67	2582.502	12" SOLID LINE WHITE-EPOXY	LIN. FT.	2300	
68	2582.502	4" BROKEN LINE WHITE-EPOXY	LIN. FT.	3503	
69	2582.502	24" STOP LINE WHITE-EPOXY	LIN. FT.	525	
70	2582.502	4" SOLID LINE YELLOW-EPOXY	LIN. FT.	2808	
71	2582.502	4" DOUBLE SOLID LINE YELLOW-EPOXY	LIN. FT.	33485	

TOTAL CONSTRUCTION COST=