



Purchasing Division
Finance Department
Room 120
411 West First Street
Duluth, Minnesota 55802

218-730-5340
purchasing@duluthmn.gov

Addendum 1
Solicitation 20-99212
Woodland-Ken-East 8th St Traffic Signal Replacement

This addendum serves to notify all bidders of the following changes to the solicitation documents:

1. Revised quantity for Item No. 2104.504 REMOVE PAVEMENT (SQ YD) to 180 on Sheet 2 of the Plans.
2. Revised quantity for Item No. 2104.504 REMOVE CONCRETE PAVEMENT (SQ YD) to 20 on Sheet 2 of the Plans.
3. Revised quantity for Item No. 2301.504 CONCRETE PAVEMENT 8.0" (SQ YD) to 12 on Sheet 2 of the Plans.

Please acknowledge receipt of this Addendum by checking the acknowledgment box within the www.bidexpress.com solicitation.

Posted: 3.9.20

STEVE PRUSAK | 3/9/2020 1:54:23 PM
22:05 (LMS TECH) | C:\Users\sprusak\AppData\Roaming\Autodesk\C3D 2018\enu\H:\Projects\12000\12369\DESIGN\PLANSHEETS\FINALPLAN\12369_SEQ01.dwg;SEQ-01

STATEMENT OF ESTIMATED QUANTITIES							
NOTES	ITEM NO.	ITEM DESCRIPTION	UNIT	PROJECT			TOTAL
				EAST 8TH ST S.A.P. 118-134-018 25% OF TOTAL	KENT ROAD S.A.P. 118-153-003 25% OF TOTAL	WOODLAND AVE S.A.P. 118-157-024 50% OF TOTAL	
				QUANTITY	QUANTITY	QUANTITY	
	2011.601	AS BUILT	LUMP SUM	0.25	0.25	0.50	1
	2021.501	MOBILIZATION	LUMP SUM	0.25	0.25	0.50	1
	2102.518	PAVEMENT MARKING REMOVAL	SQ FT	150	150	300	600
	2104.502	REMOVE SIGNAL SYSTEM	EACH	0.25	0.25	0.50	1
	2104.503	SAWING CONCRETE PAVEMENT (FULL DEPTH)	LIN FT	100	100	200	400
	2104.503	SAWING BITUMINOUS PAVEMENT (FULL DEPTH)	LIN FT	70	70	140	280
	2104.503	REMOVE CURB & GUTTER	LIN FT	53	53	109	215
(1)	2104.504	REMOVE PAVEMENT	SQ YD	45	45	90	180
(2)	2104.504	REMOVE CONCRETE PAVEMENT	SQ YD	5	5	10	20
	2104.518	REMOVE CONCRETE WALK	SQ FT	326	326	653	1305
	2106.507	EXCAVATION-COMMON	CU YD	10	10	20	40
	2106.507	COMMON EMBANKMENT (CV)	CU YD	10	10	20	40
	2123.610	STREET SWEEPER (WITH PICKUP BROOM)	HOURL	5	5	10	20
(3)	2211.509	AGGREGATE BASE (CV) CLASS 5	TON	9	9	18	36
(4)	2231.509	BITUMINOUS PATCHING MIXTURE	TON	27	27	54	108
(5)	2301.504	CONCRETE PAVEMENT 8.0"	SQ YD	3	3	6	12
	2301.602	DRILL AND GROUT REINFORCEMENT BAR (EPOXY COATED)	EACH	10	10	20	40
	2504.602	ADJUST VALVE BOX	EACH		1		1
	2506.502	ADJUST FRAME & RING CASTING	EACH	1			1
	2521.518	6" CONCRETE WALK	SQ FT	370	370	740	1480
	2531.503	CONCRETE CURB AND GUTTER DESIGN B624	LIN FT	56	56	112	224
	2531.618	TRUNCATED DOMES	SQ FT	35	35	70	140
	2550.601	FIBER OPTIC CABLE TESTING	LUMP SUM			1	1
	2550.602	FIBER OPTIC SPLICE / PATCH PANEL	EACH			3	3
	2550.602	FIBER OPTIC PIGTAIL TERMINATION	EACH			3	3
	2550.603	ARMORED FIBER OPTIC PIGTAIL CABLE 12SM	LIN FT			850	850
(6)	2563.601	TRAFFIC CONTROL	LUMP SUM	0.25	0.25	0.50	1
	2563.601	ALTERNATE PEDESTRIAN ROUTE	LUMP SUM	0.25	0.25	0.50	1
	2565.501	EMERGENCY VEHICLE PREEMPTION SYSTEM	LUMP SUM	0.25	0.25	0.50	1
	2565.516	TRAFFIC CONTROL SIGNAL SYSTEM	SYSTEM	0.25	0.25	0.50	1
	2573.502	STORM DRAIN INLET PROTECTION	EACH	2	2	4	8
	2573.503	SILT FENCE, TYPE MS	LIN FT	50	50	100	200
	2573.503	SEDIMENT CONTROL LOG TYPE STRAW	LIN FT	25	25	50	100
(7)	2575.602	SITE RESTORATION	EACH	1	1	2	4
	2582.518	CROSSWALK PREFORM THERMOPLASTIC GROUND IN	SQ FT	150	150	300	600

ADDENDUM #1
ADDENDUM #1

ADDENDUM #1

NOTES:

- (1) FOR FULL DEPTH REMOVAL OF EXISTING OVERLAID CONCRETE PAVEMENT ON WOODLAND AVENUE & EAST 8TH STREET
- (2) FOR FULL DEPTH REMOVAL OF EXISTING CONCRETE PAVEMENT ON KENT ROAD.
- (3) FOR BASE UNDER PROPOSED CONCRETE WALKS. CONTRACTOR SHALL PRESERVE EXISTING ROADWAY BASE MATERIAL.
- (4) FOR MATCHING EXISTING BITUMINOUS OVERLAY. QUANTITY ASSUMES 4 INCHES OF MATERIAL. REPLACEMENT SHALL MATCH EXISTING DEPTH.
- (5) FOR CONCRETE SURFACE PAVEMENT ON KENT ROAD AND CONCRETE BASE PAVEMENT ON WOODLAND AVENUE AND EAST 8TH STREET.
- (6) FOR ALL SIGNING AND DEVICES SPECIFIED IN THE TRAFFIC CONTROL PLAN.
- (7) FOR TURF ESTABLISHMENT AT EACH INTERSECTION QUADRANT.

1	3/9/2020	SBP	SBP	SBP	ADDENDUM #1 -- REVISE SQ YD QUANTITIES
NO	DATE	BY	CKD	APPR	

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota.
Print Name: **STEVEN B. PRUSAK**
Steven B. Prusak
Date 1/27/2020 License # 47622

STATE AID PROJECT NO.
118-134-018
118-153-003
118-157-024
CITY PROJECT NO. 1807

DRAWN BY
A. GARFIELD
DESIGNED BY
A. GARFIELD
CHECKED BY
S. PRUSAK
COMM. NO. 12369



CITY OF DULUTH
STATEMENT OF ESTIMATED QUANTITIES
WOODLAND AVENUE AND KENT ROAD/EAST 8TH STREET SIGNAL REPLACEMENT

SHEET
2
OF
33