## Keene Creek Resiliency

\_\_\_\_

# Irving Park Stormwater Basin

Ryan Granlund & Allison Brooks City of Duluth


Irving Park Community Club August 26, 2025





# Keene Creek: A Priority Watershed

- There are 42 watersheds in Duluth!
- 3 are currently prioritized: Amity, Tischer, and Keene
- Prioritized due to water quality, funding availability, & partner priorities.





# Morris Thomas Keene Creek Skyline Parkway Highland Street Irving Park

## Improving Keene Creek

- Keene Creek stretches from Hermantown to Grassy Point, cold water and habitat – Trout Stream
- The creek is impaired for E. Coli & chloride
  - City and other area MS4's must implement actions that reduce pollutant loads
- 2020 E. Coli Source Assessment Study
- Trout Unlimited and South St. Louis Soil & Water Conservation District restored ~1,500 feet of creek to improve trout habitat
- MN DNR is developing a "Roadmap to Resilience" in 2025
- Future Stormwater Basin at 59<sup>th</sup> Ave W
- Irving Stormwater Basin!











## Depiction of Green Infrastructure Projects With Associated Catchment Areas Keene Creek Resiliency Report City of Duluth, Minnesota Map A-3 Projects in Keene Creek Watershed Location Map A-4 Projects in Keene Creek Watershed Determined Green Infrastructure Catchment Areas Keene Creek Watershed Gravity Mains/Collectors Infeasible > Collector Streams Under Ground False True — <all other values> 0.3 Miles

## Stormwater Management

- Stormwater rain and snowmelt runoff is carried to nearby discharge points via catch basins, pipes and culverts/ditches.
- Stormwater management helps reduce runoff and improve water quality before discharge to receiving waters.
- Irving Park Basin will manage approx. 17.5 acres of stormwater (see left)





## **Project Details**

- Will be mostly completed September 2025
  - Final vegetation install will happen in Spring of 2026
  - Contractor to maintain vegetation until 2028 to provide best chance for establishment

#### **Funding Sources**

- Great Lakes Sediment & Nutrient Reduction Program
- Great Lakes Restoration Initiative





























## Getting Established

- Basin will be planted with a variety of native species
  - NE MN seed mix in basin footprint, planted with over 2,000 wildflower plugs
- Contractor maintenance planned through 2028 to remove invasives
  will help nurture it
- It will take some time to get established





## Other Work in the Area:

**Street Preservation** 

### S 57<sup>th</sup> Ave W

- Sinkholes due to undersized & failing structures below ground
- Funded through the Street Preservation Program – Street Sales Tax

#### What's planned?

- New storm sewer & utility work
- Repaving the street

#### What's happening?

- Sawcutting is complete
- Removals & utility work waiting for Irving Basin completion
- Work scheduled for the week of September 22, 2025

## Thank you!

## Irving Park Stormwater Basin

Ryan Granlund – rgranlund@DuluthMN.gov Allison Brooks – abrooks@DuluthMN.gov

Project Updates at <a href="https://duluthmn.gov/parks/parks-parks/irving-planning/progress-in-the-parks/irving-park-stormwater/">https://duluthmn.gov/parks/parks-parks/irving-park-stormwater/</a>



