



Addendum No. 1
Solicitation 26-99494
Storm System Improvements

This addendum serves to notify all bidders of the following changes to the solicitation documents:

1. The Bid Item Listing has been updated to include line item '2411.502 CONCRETE FLUME'

Below are questions asked by contractors and their subsequent answers (in italics):

1. There is Concrete Flume in the SEQ but not in BidExpress?
a. The Bid Item Listing in BidExpress will be updated to include this line item.
2. What will the 3" Polystyrene Insulation be used for and where is it in the plans?
a. The 3" Polystyrene Insulation is undistributed in the plans. This item will be used for insulating water service and other utility crossings.
3. There appears to be a keynote missing on Page 8 for structure ST0580013?
a. The circle on this sheet is inadvertent and no note was intended.
4. What is the detail for Construct Drainage Structure Design DI TP 6" and is a Nylaplast PVC structure acceptable?
a. Refer to MnDOT standard plate 4025B for the detail for this bid item. We will accept a Nylaplast PVC structure.
5. What is required for the Stabilized Construction Entrance by the Lump Sum?
a. The Stabilized Construction Entrance is used to prevent vehicles tracking mud or dirt on the paved roadway. It is intended that one of the details on MNDOT standard plan 5-297.405 sheet 5 be used for the Stabilized Construction Entrance. The Lump Sum will be payment in full for constructing and maintaining the stabilized construction entrance at all sites.

Please acknowledge receipt of this Addendum by checking the acknowledgement box within the solicitation at www.bidexpress.com.

Posted: May 19, 2026