



**Purchasing Division**  
Finance Department  
Room 120  
411 West First Street  
Duluth, Minnesota 55802

218-730-5340  
purchasing@duluthmn.gov

**Addendum No. 4**  
**Solicitation 25-99824**  
**Perch Lake Landing Site Improvements**

This addendum serves to notify all bidders of the following changes to the solicitation documents:

The following are questions asked by contractors and their subsequent answers (in italics):

1. What size footings are we to assume for bidding purposes for the Alt 1 Picnic Shelter?
  - a. *Shelter foundations are to be designed and signed off on by a licensed structural engineer; they must be at frost depth, which typically means a minimum of 6' depth. The notes below are from the manufacturer and are included in the shelter details in the plan:*

**STEEL COLUMN PIER DETAIL**

TYPICAL PIER DIAMETER IS BETWEEN 2'-0" AND 3'-0"±  
TYPICAL PIER DEPTH IS BETWEEN 3'-6" AND 5'-6"±

ACTUAL DESIGN WILL VARY DUE TO BUILDING CODE REQUIREMENTS AND MAY BE SUBSTANTIALLY LARGER.

2. What type of beach sand is required?
  - a. *Beach sand is to be well-graded, screened local sand, 0.45mm minus, with the majority of the particles between 0.125 and 0.25mm (fine). Contractor to submit sample for approval prior to placing sand.*
3. CLARIFICATION: The required gate (shown on plan sheet L-1) will **not** be supplied by the Owner/City; the Contractor is responsible for providing and installing the gate per Detail 8/ Sheet D-1. Please strike "Owner Supplied" from Construction Note 1 on plan sheet D-1, Detail 8, and "City-provided" from specification Section 01 010, 1.01.A.13 (page 11).

Please acknowledge receipt of this Addendum by checking the acknowledgement box within the [www.bidexpress.com](http://www.bidexpress.com) solicitation.

Posted: **January 20, 2026**