





Purchasing Division
Finance Department
Room 120
411 West First Street
Duluth, Minnesota 55802

 218-730-5340
 purchasing@duluthmn.gov

Addendum # 2
Solicitation # 25-99193
Project 2082 & 2214
Lead Water Service Replacement – Lincoln Park 2 & 3

NOTICE

This Addendum is issued to modify, explain or correct the original drawings, specifications and/or previous addenda and is hereby made a part of the Contract Documents.

CHANGES TO BID EXPRESS POST

Exhibit A – Item Listing for 2082 posted to Bid Express has been updated with the following changes:

1. Line 6, REMOVE & REPLACE INTEGRANT CURB has been updated so that the total estimated quantity is “144”.
2. Line 11, REMOVE & REPLACE STREET SECTION, TYPE (C) has been updated so that the total estimated quantity is “159”.
3. Line 26, CONCRETE RETAINING WALL, TYPE L has been updated so that the unit measure is “CU YD”.
4. Line 27, STRUCTURE EXCAVATION CLASS R has been updated so that the total estimated quantity is “75”.
5. Line 31, SANITARY REPAIR IN TRENCH has been updated so that the total estimated quantity is “15”.
6. Line 50, POLYSTYRENE INSULATION has been updated so that the total estimated quantity is “360”.
7. Line 56, SALVAGE & REINSTALL PLANTING (BUSH, SHRUB, SMALL TREE) has been updated so that the total estimated quantity is “3”.
8. Line 58, SODDING TYPE LAWN (PUBLIC) has been updated so that the total estimated quantity is “763”.
9. Line 59, SALVAGE & REINSTALL LANDSCAPE GARDEN has been updated so that the total estimated quantity is “465”.

Exhibit B – Item Listing for 2214 posted to Bid Express has been updated with the following changes:

1. Line 18, REMOVE & REPLACE 6” CONCRETE WALK has been updated so that the total estimated quantity is “2200”.
2. Line 22, CONCRETE RETAINING WALL, TYPE L has been updated so that the unit measure

is CU YD”.

3. Line 27, SANITARY SERVICE REPAIR IN TRENCH has been updated so that the total estimated quantity is “25”.

CHANGES TO DRAWINGS

The SEQ on page Q1 of plan set 2082 is hereby edited as follows:

1. Line 26, 2411.618 Concrete Retaining Wall, Type L is updated so that the unit measure is “CU YD”.
2. Line 26, 2411.618 Concrete Retaining Wall, Type L is updated so that the total estimated quantity is “20”.
3. Line 31, SANITARY REPAIR IN TRENCH is updated so that the total estimated quantity is “15”.
4. Line 33, CONCRETE ENCASED VALVE BOX COVER is updated to “CONCRETE ENCASED VALVE BOX COLLAR”.
5. Line 52, ELECTRICAL SERVICE GROUND is updated so that SEQ Note 1 (“Quantities are an estimate. Necessary quantities will be determined by field conditions.”) applies.

The SEQ on page Q1 of plan set 2214 is hereby edited as follows:

1. Line 18, REMOVE & REPLACE 6” CONCRETE WALK is updated so that the total estimated quantity is “2200”.
2. Line 29, CONCRETE ENCASED VALVE BOX COVER is updated to “CONCRETE ENCASED VALVE BOX COLLAR”.
3. Line 27, SANITARY SERVICE REPAIR IN TRENCH is update so that the total estimated quantity is “25”.

CHANGES TO SPECIAL PROVISIONS

The following is hereby added to the Project Special Provisions for 2214 LSLR Lincoln Park 3:

SP-65 (2504) ROUTE WATER SERVICE WITHIN STRUCTURE

SP-65.1 DESCRIPTION

This Work includes payment for interior plumbing required to extend a water service to a secondary structure through the primary structure on the same property.

SP-65.2 CONSTRUCTION REQUIREMENTS

The work shall consist of the following:

1. Furnish and install a 1" x 1" tee fitting above the floor on the main water service entering the primary structure.
2. Furnish and install two (2) 1" ball valves to isolate the primary and secondary structure water services.
3. Furnish and install 1" service pipe through the primary structure, along the

ceiling, from the entry point at the front of the house to the wall closest to the secondary structure.

4. Connect service pipe to the new 1" HDPE water service to the secondary structure above the floor at the exit point in the primary structure. This work is in addition to the work included in the item "Connect to Existing Indoor Plumbing". The Contractor shall obtain a plumbing permit for all plumbing work at each work site and shall schedule plumbing inspections with the City of Duluth Construction Services & Inspections Division. All plumbing work and materials shall meet all applicable plumbing codes. New pipe and fittings under this item shall be either copper or PEX. The existing lead service shall be shut off, disconnected and capped and the house plumbing cut and/or capped at this location.

SP-65.3 Measurement and Payment

Payment will be under item number 2504.602 ROUT WATER SERVICE WITHIN STRUCTURE per each which shall be compensation in full for all labor, equipment, and materials required to complete the work.

RESPONSES TO SELECTED BIDDER QUESTIONS

None.

SUPPLEMENTAL INFORMATION

None.

Please acknowledge receipt of this Addendum by including a copy of it with your proposal.

Posted: **2/11/2025**

END OF ADDENDUM