



Purchasing Division
Finance Department
Room 120
411 West First Street
Duluth, Minnesota 55802

218-730-5340
purchasing@duluthmn.gov

Addendum No. 3
Solicitation #25-99625
32nd Ave W Creek Watershed Stormwater Resiliency Improvements

This addendum serves to notify all bidders of the following changes to the solicitation documents:

DRAWINGS

1) Sheet 4 – SEQ & Notes

- A. Bid item 30A – “2501.602 Trash Guard for 36” Pipe Apron” was added. Paid for by the each with a quantity of 1 each.
- B. Bid item 30B – “2501.602 Trash Guard for 58” Pipe Apron” was added. Paid for by the each with a quantity of 1 each.

QUESTIONS

- 1) Are Trash Guards for the 26” and 58” Pipe Aprons incidental?
 - A. No, bid items were added to the SEQ and the bid form.

Please acknowledge receipt of this Addendum by checking the acknowledgement box within the www.bidexpress.com solicitation.

Posted: **August 11, 2025**

STATEMENT OF ESTIMATED QUANTITIES CONTINUED						
ITEM NO.	TAB	NOTE NO.	ITEM NO.	ITEM DESCRIPTION	UNITS	TOTAL ESTIMATED QUANTITIES
30A			2501.602	TRASH GUARD FOR 36" APRON	EACH	1
30B			2501.602	TRASH GUARD FOR 58" APRON	EACH	1
31	C, D	8	2502.503	4" PERF PVC PIPE DRAIN	LIN FT	1868
32	E		2502.503	10" PVC PIPE DRAIN	LIN FT	10
33	E		2503.503	12" RC PIPE SEWER DES 3006 CLASS III	LIN FT	1142
34	E		2503.503	15" RC PIPE SEWER DES 3006 CLASS III	LIN FT	233
35	E		2503.503	18" RC PIPE SEWER DES 3006 CLASS III	LIN FT	287
36	E		2503.503	24" RC PIPE SEWER DES 3006 CLASS III	LIN FT	333
37	E		2503.503	30" RC PIPE SEWER DES 3006 CLASS III	LIN FT	12
38	E		2503.503	36" RC PIPE SEWER DES 3006 CLASS III	LIN FT	12
39	E		2503.503	48" RC PIPE SEWER DES 3006 CLASS III	LIN FT	106
40	E		2503.503	58" SPAN RC PIPE-ARCH SEWER CLASS IIA	LIN FT	33
41	E		2503.602	CONNECT TO EXISTING STORM SEWER	EACH	28
42	E		2503.602	CONSTRUCT BULKHEAD	EACH	2
43	B		2504.602	ADJUST VALVE BOX	EACH	3
44	B		2506.502	ADJUST FRAME & RING CASTING	EACH	1
45	B, E		2506.502	CASTING ASSEMBLY	EACH	82
46	E		2506.503	CONSTRUCT DRAINAGE STRUCTURE DESIGN 48-4020	LIN FT	158
47	E		2506.503	CONSTRUCT DRAINAGE STRUCTURE DESIGN 72-4020	LIN FT	34
48	E		2506.503	CONSTRUCT DRAINAGE STRUCTURE DESIGN 84-4020	LIN FT	17
49	E		2506.503	CONSTRUCT DRAINAGE STRUCTURE DESIGN G	LIN FT	69
50	E		2506.503	CONSTRUCT DRAINAGE STRUCTURE DESIGN H	LIN FT	101
51	B, E		2506.602	CONCRETE ENCASED CASTING COLLAR	EACH	16
52	E		2506.602	CONSTRUCT DRAINAGE STRUCTURE DESIGN SPECIAL 1	EACH	4
53	E		2506.602	CONSTRUCT DRAINAGE STRUCTURE DESIGN SPECIAL 2	EACH	1
54	F		2511.504	GEOTEXTILE FILTER TYPE 3	SQ YD	84
55	F		2511.504	GEOTEXTILE FILTER TYPE 4	SQ YD	72
56	F	9	2511.507	RANDOM RIPRAP CLASS II	CU YD	24
57	F	9	2511.507	RANDOM RIPRAP CLASS IV	CU YD	30

STATEMENT OF ESTIMATED QUANTITIES CONTINUED						
ITEM NO.	TAB	NOTE NO.	ITEM NO.	ITEM DESCRIPTION	UNITS	TOTAL ESTIMATED QUANTITIES
58	D	10	2521.504	4" CONCRETE WALK	SQ YD	381
59	D	10	2521.504	6" CONCRETE WALK	SQ YD	112
60	D		2531.503	CONCRETE CURB AND GUTTER DESIGN B624	LIN FT	2732
61	D	11	2531.504	7" CONCRETE DRIVEWAY PAVEMENT	SQ YD	87
62	D	11	2531.504	8" CONCRETE DRIVEWAY PAVEMENT	SQ YD	63
63	D		2531.618	TRUNCATED DOMES	SQ FT	180
64			2563.601	TRAFFIC CONTROL	LUMP SUMP	1
65	D		2564.502	INSTALL SIGN	EACH	4
66			2573.501	STABILIZED CONSTRUCTION EXIT	LUMP SUMP	1
67	F		2573.502	STORM DRAIN INLET PROTECTION	EACH	107
68	F		2573.503	SEDIMENT CONTROL LOG TYPE ROCK	LIN FT	300
69	F		2573.503	SEDIMENT CONTROL LOG TYPE WOOD FIBER	LIN FT	3014
70	F		2573.503	SILT FENCE, TYPE HI	LIN FT	288
71	F	12	2574.507	COMMON TOPSOIL BORROW	CY YD	24
72	F	13	2574.508	FERTILIZER TYPE 3	POUND	79
73	F		2575.505	SEEDING	ACRE	0.23
74	F	14	2575.501	SEED MIXTURE 25-131	POUND	35
75	F		2575.504	ROLLED EROSION PREVENTION CATEGORY 20	SQ YD	973
76	F		2575.504	SODDING TYPE LAWN	SQ YD	933

REVISION 1 - 08/11/2025
 REVISION 2 - 08/11/2025

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

SIGNATURE: _____

NATHAN BRUNO
 TYPE NAME

DATE: 07/21/2025

LIC. NO: 46584



CITY OF DULUTH
 ENGINEERING DIVISION
 411 W. 1ST ST. STE. 211
 DULUTH, MN 55802

32ND AVE W CREEK WATERSHED STORMWATER RESILIENCY IMPROVEMENTS

CITY PROJECT NO.: 2069

STATE AID PROJECT NO.: NA

DRAWN BY: JDO

SEQ & NOTES

SHEET NO. 4 OF 120